SECTION 01 10 00.[Not Supplied - ProjectInfo : TONUM] TASK ORDER STATEMENT OF WORK

1.0	PROJECT OBJECTIVES
1.1.	SECTION ORGANIZATION
2.0	SCOPE
2.1.	COMPANY OPERATIONS FACILITY
2.2.	SITE
2.3.	GOVERNMENT-FURNISHED GOVERNMENT INSTALL EQUIPMENT (GFG
2.4.	FURNITURE REQUIREMENTS
3.0	COMPANY OPERATIONS FACILITY
3.1.	GENERAL REQUIREMENTS
3.2.	FUNCTIONAL AND AREA REQUIREMENTS
4.0	APPLICABLE CRITERIA
4.1.	INDUSTRY CRITERIA
4.2.	MILITARY CRITERIA
5.0	GENERAL TECHNICAL REQUIREMENTS
5.1.	SITE PLANNING AND DESIGN
5.2.	SITE ENGINEERING
5.3.	ARCHITECTURE AND INTERIOR DESIGN
5.4.	STRUCTURAL DESIGN
5.5.	THERMAL PERFORMANCE
5.6.	PLUMBING
5.7.	ELECTRICAL AND TELECOMMUNICATIONS SYSTEMS
5.8.	HEATING, VENTILATING AND AIR CONDITIONING
5.9.	ENERGY CONSERVATION
5.10.	FIRE PROTECTION
5.11.	SUSTAINABLE DESIGN
5.12.	CONSTRUCTION AND DEMOLITION (C&D) WASTE MANAGEMENT

5.13. SECURITY (ANTI-TERRORISM STANDARDS)

Section: 01 10 00 [Not Supplied]
Page 2 of 151

6.0 PROJECT SPECIFIC REQUIREMENTS

- 6.1. GENERAL
- 6.2. APPROVED DEVIATIONS
- 6.3. SITE PLANNING AND DESIGN
- 6.4. SITE ENGINEERING
- 6.5. ARCHITECTURE
- 6.6. STRUCTURAL DESIGN
- 6.7. THERMAL PERFORMANCE
- 6.8. PLUMBING
- 6.9. SITE ELECTRICAL AND TELECOMMUNICATIONS SYSTEMS
- 6.10. FACILITY ELECTRICAL AND TELECOMMUNICATIONS SYSTEMS
- 6.11. HEATING, VENTILATING AND AIR CONDITIONING
- 6.12. ENERGY CONSERVATION
- 6.13. FIRE PROTECTION
- 6.14. SUSTAINABLE DESIGN
- 6.15. ENVIRONMENTAL
- 6.16. PERMITS
- 6.17. DEMOLITION
- 6.18. ADDITIONAL FACILITIES

Section: 01 10 00 [Not Supplied]
Page 3 of 151

1.0 PROJECT OBJECTIVES

The project objective is to design and construct facilities for the military that are consistent with the design and construction practices used for civilian sector projects that perform similar functions to the military projects. For example, a Company Operations Facility has the similar function as an office/warehouse in the civilian sector; therefore the design and construction practices for a company operations facility should be consistent with the design and construction of an office/warehouse building.

Comparison of Military Facilities to Civilian Facilities

Military Facility	Civilian Facility
Company Operations Facility (COF)	Office Warehouse

It is the Army's objective that these buildings will have a 25-year useful design life before a possible re-use/re-purpose or renovation requirement, to include normal sustainment, restoration, modernization activities and a 50-year building replacement life. Therefore, the design and construction should provide an appropriate level of quality to ensure the continued use of the facility over that time period with the application of reasonable preventive maintenance and repairs that would be industry-acceptable to a major civilian sector project OWNER. The site infrastructure will have at least a 50-year life expectancy with industry-accepted maintenance and repair cycles.

The project site should be developed for efficiency and to convey a sense of unity or connectivity with the adjacent buildings and with the Installation as a whole.

Requirements stated in this contract are minimums. Innovative, creative, and life cycle cost effective solutions, which meet or exceed these requirements are encouraged. Further, the OFFEROR is encouraged to seek solutions that will expedite construction (panelization, pre-engineered, etc.) and shorten the schedule. The intent of the Government is to emphasize the placement of funds into functional/operational requirements. Materials and methods should reflect this by choosing the lowest Type of Construction allowed by code for this occupancy/project allowing the funding to be reflected in the quality of interior/exterior finishes and systems selected.

1.1. SECTION ORGANIZATION

This Section is organized under 6 major "paragraphs".

- (1) Paragraph 1 is intended to define the project objectives and to provide a comparison between the military facility(ies) and comparable "civilian" type buildings.
- (2) Paragraph 2 describes the scope of the project.
- (3) Paragraph 3 provides the functional, operational and facility specific design criteria for the specific facility type(s) included in this contract or task order.
- (4) Paragraph 4 lists applicable industry and government design criteria, generally applicable to all facility types, unless otherwise indicated in the Section. It is not intended to be all-inclusive. Other industry and government standards may also be used, where necessary to produce professional designs, unless they conflict with those listed.
- (5) Paragraph 5 contains Army Standard Design Criteria, generally applicable to all facility types, unless otherwise indicated in the Section.
- (6) Paragraph 6 contains installation and project specific criteria supplementing the other 5 paragraphs.

Section: 01 10 00 [Not Supplied]
Page 4 of 151

2.0 SCOPE

2.1. COMPANY OPERATIONS FACILITY (COF)

Provide Company Operations Facilities (COF). This project type is to house Company administrative operations and store and move supplies. It is intended to be similar to office and warehouse type buildings in the private sector community.

The project will include Company Operations Facilities for 0 Companies. The number of unified companies (UNICOF) per battalion and number of personnel per company for this project is as follows:

[Not Supplied - COF : COF_REPEAT]

A Troop Aid Station to support the Brigade IS NOT required

Section: 01 10 00 [Not Supplied]
Page 5 of 151

2.2. SITE:

Provide all site design and construction within the COF limits of construction necessary to support the new building facilities. Supporting facilities include, but are not limited to, utilities, electric service, exterior and security lighting, fire protection and alarm systems, security fencing and gates, water, gas, sewer, oil water separators, storm drainage and site improvements. Include Antiterrorism/Force Protection measures the facility design in accordance with applicable criteria.

Maintain the construction site and haul route. Repair/replace damage to existing sidewalks, pavements, curb and gutter, utilities, and/or landscaping within the construction limit, adjacent to the construction site, and along the Contractor's haul route resulting from the Contractor's construction activities at no additional cost to the Government. Prior to construction activities, the Contractor and Contracting Officer Representative shall perform an existing condition survey. At the completion of the Task Order, the Contractor and Contracting Officer representative shall perform a final condition survey to determine repair/replacement requirements.

Approximate area available for this (these) facility(ies) is shown on the drawings.

Provide all site improvements necessary to support the new building facilities. Refer to Paragraph 6.

Approximate area available 0.00 acres

2.3. GOVERNMENT-FURNISHED GOVERNMENT-INSTALLED EQUIPMENT (GFGI)

Coordinate with Government on GFGI item requirements and provide suitable structural support, brackets for projectors/VCRs/TVs, all utility connections and space with required clearances for all GFGI items. Fire extinguishers are GF/GI personal property, while fire extinguisher brackets and cabinets are Contractor furnished and installed CF/CI. All Computers and related hardware, copiers, faxes, printers, video projectors, VCRs and TVs are GFGI.

The following are also GFGI items: [Not Supplied - FacilityAddREq: GFGI ITEMS]

2.4. FURNITURE REQUIREMENTS

Provide furniture design for all spaces listed in Chapter 3 and including any existing furniture and equipment to be re-used. Coordinate with the user to define requirements for furniture systems, movable furniture, storage systems, equipment, any existing items to be reused, etc. Early coordination of furniture design is required for a complete and usable facility.

The procurement and installation of furniture is NOT included in this contract. Furniture will be provided and installed under a separate furniture vendor/installer contract. The general contractor shall accommodate that effort with allowance for entry of the furniture vendor/installer onto this project site at the appropriate time to permit completion of the furniture installation for a complete and usable facility to coincide with the Beneficial Occupancy Date (BOD) of this project. The furniture vendor/installer contract will include all electrical pre-wiring and the whips for final connection to the building electrical systems however; the general contractor shall make the final connections to the building electrical systems under this contract. Furthermore, the general contractor shall provide all Information/Technology (IT) wiring (i.e. LAN, phone, etc.) up to and including the face plate of all freestanding and/or systems furniture desk tops as applicable, the services to install the cable and face plates in the furniture, the coordination with the furniture vendor/installer to accomplish the installation at the appropriate time, and all the final IT connections to the building systems under this contract.

The Government reserves the right to change the method for procurement of and installation of furniture to Contractor Furnished/Contractor Installed (CF/CI). CF/CI furniture will require competitive open market procurement by the Contractor using the Furniture, Fixtures and Equipment (FF&E) package.

2.5. NOT USED

Section: 01 10 00 [Not Supplied]
Page 6 of 151

3.0 COMPANY OPERATIONS FACILITY (COF)

3.1. General Requirements:

COFs provide administrative and supply facilities for unit personnel functions and storage of their equipment. These facilities serve as the primary staging, training, and deployment center for personnel and their individualized gear.

3.1.1. Facility Relationships

COFs are typically located within an operations complex along with Tactical Equipment Maintenance Facilities (motor pools) and Battalion/Brigade HQ. The facilities within this complex shall be oriented to support deployment and daily operations, and should also be located within walking distance of associated community facilities such as barracks and dining facilities.

3.1.2. Gross Building Area

Gross areas of facilities shall be computed according to subparagraphs below. Maximum gross area limits indicated in Paragraph 2.0, SCOPE, may not be exceeded. A smaller overall gross area is permissible if all established net area program requirements are met.

- (1) Enclosed Spaces. The gross area includes the total area of all floors, including basements, mezzanines, penthouses, usable attic or sloping spaces used to accommodate mechanical equipment or for storage with an average height of 6'-11" measured from the underside of the structural system and with the perimeter walls measuring a minimum of 4'-11" in height, and other enclosed spaces as determined by the effective outside dimensions of the building. (NOTE: Exterior Covered Hardstand area associated with Company Operations Facilities shall be calculated as enclosed space, i.e. full scope).
- (2) One-Half Spaces. One-half of the area will be included in the gross area for balconies and porches; exterior covered loading platforms or facilities, either depressed, ground level, or raised; covered but not enclosed passageways or walks; covered and uncovered but open stairs; and covered ramps.
- (3) Excluded Spaces. Crawl spaces; exterior uncovered loading platforms or facilities, either depressed, ground level, or raised; exterior insulation applied to existing buildings; open courtyards; open paved terraces'; roof overhangs and soffits for weather protection; uncovered ramps; uncovered stoops; and utility tunnels and raceways will be excluded from the gross area.

3.1.3. Functional Spaces

Net area requirements for functional spaces are included in the space program table (Table 2). If net area requirements are not specified in the Statement of Work, the space shall be sized to accommodate the required function, comply with code requirements, comply with overall gross area limitations and other requirements of the RFP (for example, area requirements for corridors, stairs, and mechanical rooms will typically be left to the discretion of the Offeror).

3.1.4. Handicapped Access

COFs are intended for use by able-bodied military personnel only, therefore, are not required to meet handicapped accessible requirements.

3.1.5. Site Design and Functional Area

Site features include service yard and service yard drives, utilities, and site improvements.

3.1.6. Adapt-Build Model

An Adapt-Build Model for a COF, which contains a fully developed design, including a Building Information Model (BIM), 2-D CADD files, and specifications, can be downloaded from the following FTP site: ttp://ftp.usace.army.mil/pub/sas/COF/. This design is provided as a guide that exemplifies a technically suitable

Section: 01 10 00 [Not Supplied]
Page 7 of 151

product and incorporates mandatory functional/operational requirements for a similar (although perhaps not an exact) facility to be constructed under this solicitation. It will be left to the offerors' discretion if, and how, they will use the sample design provided to satisfy the requirements of this Request for Proposal. This model is not intended to modify or over-ride specific requirements of this RFP and, under all circumstances, it will be incumbent upon the successful offeror to adhere to the site specific scope and functional/operational requirements specified within the RFP. Neither this statement of work, nor the adapt-build model, are intended to diminish the offeror's responsibilities under the clauses titled "Responsibility of the Contractor for Design," "Warranty of Design," and "Construction Role During Design." The successful offeror shall be the designer-of-record and shall be responsible for the final design and construction product, including but not limited to, adherence to the installation architectural theme, building code compliance and suitability of the engineering systems provided. The government assumes no liability for the model design provided and, to the extent it is used by an offeror, the offeror will be responsible for all aspects of the design as designer-of-record.

3.2. FUNCTIONAL AND OPERATIONAL REQUIREMENTS

3.2.1. General

COF functional layout and adjacency requirements are as indicated on drawings. The extent to which the drawings represent required or preferred layouts and the allowable latitude for changes to them is as noted on the drawings. COFs should be easily adaptable to accommodate variations in size and number of companies in the Army's future force. The design objective of the basic battalion level COF complex is to provide a flexible facility suitable to a mix of battalions of varying composition while utilizing a modular approach.

3.2.2. Functional Areas

The COF is comprised of three vertical construction components consisting of an Administrative Module, Readiness Module, and exterior covered hardstand. In conjunction with this, each site-specific project shall include necessary site amenities, such as vehicle service yards, access drives, equipment wash stations, and exterior utilities. These components are more fully described below.

- (1) Administration Module. Space shall be provided for the following administration and support functions:
- (a) Private offices for the Commander, First Sergeant, Executive Officer and Training Room
- (b) Space for printer and fax machines, waste and paper recycling receptacles, and supply closet for storage
- (c) Shared office space for platoon leaders and platoon sergeants
- (d) Conference space for meetings and/or training
- (e) Showers, locker room, and latrines to serve both the administrative personnel assigned to the company and for off post personnel a place for commuters to shower and change after PT
- (f) Consolidated utility spaces to serve the entire facility including a mechanical room, electrical room, telecommunication rooms (including SIPRNet), janitor's closet, vending area to also accommodate recycling receptacles and recycling storage closet. Accommodation for Secure Internet Protocol Routing Network (SIPRNet) shall be constructed in accordance with AR 380-5, Chapter 7.
- (2) Readiness Module. Space will be provided for the following operational and supply functions:
- (a) Readiness Bays to provide accommodation for individual combat equipment (TA-50) lockers (CFCI) for all unit personnel, plus co-located area for equipment maintenance, training, and pre-deployment preparations. Interior equipment maintenance area will be nominally sized so that up to 50 percent of the unit personnel can layout TA-50 gear simultaneously, based on providing 40 square feet (5-foot by 8-foot plus a circulation factor) for each layout space. Each company area shall accommodate forklift access from the readiness bay to the exterior loading areas. The bay floor shall be capable of supporting forklift movement throughout the area. Slab shall be designed for forklift truck maximum axle load of 5 kips and maximum load capacity of 2 kips. Interior mud wash utility sinks shall be provided in the Readiness Areas. Sinks shall be allocated on the basis of one utility sink for every 50 soldiers in the company.
- (b) Supply Bays to provide storage space for company supplies and equipment Tables of Equipment (TOE) and Common Tables of Allowance (CTA), weapons, and consumable supplies (including items awaiting issue, turnin, or repair). Also, it provides accommodation for the supply sergeant, supply clerk(s) and the armorer in performing shipping and receiving functions. Specific storage areas included in the supply bay include:

Section: 01 10 00 [Not Supplied]
Page 8 of 151

- Weapons vault for storage of arms, ammunition, and explosives (AA&E)
- Secure storage room for non-sensitive items (high value items, other than AA&E, for which accountability is a concern)
- Nuclear, biological, and chemical (NBC) equipment storage
- Communications equipment storage
- Consumable unit storage
- (c) Accommodation for overflow/expansion from either admin or storage spaces. This provision shall be accomplished by the utilization of a mezzanine over the entire open area of the Readiness Module, within the area limitations of IBC and NFPA 101. The drawings indicate preferred overflow/expansion arrangements that meet user operability requirements. The expansion space indicated on the drawings shall be provided at the time of initial project construction.
- (3) Exterior Covered Hardstand. Outside sheltered space for equipment maintenance, weapons cleaning, and pre-deployment preparation. This area shall be sized in accordance with Paragraph 2.0 SCOPE. The preference is to provide a column free interior to the greatest extent possible to allow for the greatest flexibility in use. The minimum canopy height shall be 14'-0" or such height as required to allow for operational truck access. The minimum clear depth shall be 30'-0".

3.2.3. COF Army Standards

The following items are the Army mandatory features for the COFs.

- (1) Battalion Centric Design. Design that consolidates COFs for an entire battalion in a single building. The design standard is intended to create a facility that consolidates between three and eight companies of a battalion in a single building. This single building can be reconfigured internally without changing the footprint of the building if the battalion structure changes.
- (2) Open, Flexible Design for Admin and Readiness Modules. Open, flexible design for both admin and readiness modules, easy to reconfigure in response to changes in force structure, equipment, and doctrine. Consistent with the battalion centric focus, both the admin and the readiness (supply) modules will employ design features that are durable but reconfigurable without altering the structural design of the building. The goal is to allow ready adaptability in response to changes in force structure, equipment, and doctrine. The addition of internal load bearing structures that limit design flexibility will not be permitted.
- (3) TA-50 Lockers. Individual combat equipment (TA-50) lockers in sufficient quantity to meet the upper limit of the design capacity of the facility (100 percent of maximum personnel in each company). Provide permanently installed, individual steel lockable lockers sized 42" (w) x 24" (d) x 78" (h) to allow each soldier to securely store current TA-50 as well as future Soldier Systems equipment.
- (4) Interior Operations and Maintenance Area. The interior space of the readiness module is intended to provide space for equipment maintenance and pre/post-deployment checks, as well as other unit preparatory and training requirements. The space includes the provision for individual TA-50 and other equipment storage, and future fielding of Soldier Systems equipment. The space is to be nominally sized to provide 40 SF layout areas for 50 percent of the upper limit of the design capacity of the facility (50 percent of the maximum personnel). Variations to the locker arrangement shown in the drawings are permitted, but may result in a reduced number of layout spaces. Revised configurations that reduce the available layout area to less than 25 percent of the design capacity of the readiness module will not be permitted. The readiness module will be designed to accommodate the use of fork lifts. In addition to the above, wire mesh cage storage shall be provided for unit supply, NBC, and communications equipment located at the supply bay area.
- (5) Exterior Covered Hardstand. Exterior covered hardstand adjacent to the Readiness Module will be provided for each company to accommodate outside equipment maintenance, weapons cleaning, pre/post-deployment preparation, vehicle loading, close formation, etc. This space is to be nominally sized to provide 40 SF layout areas for 25 percent of the upper limit of the design capacity of the facility (25 percent of the maximum personnel). Water, lighting, and electrical connections shall be provided.
- (6) Arms Vaults. Arms vaults to accommodate storage of arms, ammunition and explosives (AA&E) shall be provided for each company. These vaults shall be designed in accordance with physical security requirements contained in AR 190-11, Appendix G. An option exists for use of prefabricated, modular vaults conforming to Fed. Spec. AA-V-2737 requirements. Provide a GSA approved Class 5 Armory vault door with lock in accordance with Fed. Spec. AA-D-600D and a Dutch style day gate with issue port.

Section: 01 10 00 [Not Supplied]
Page 9 of 151

(7) Non-Sensitive Secure Storage (other than AA&E). Intent is to provide secure storage of items with a high dollar value or items for which command accountability is required. The room shall be constructed of material to prevent forcible entry. The minimum acceptable construction is expanded steel fabric behind impact resistant gypsum board at both walls and ceiling. The door should provide an equivalent degree of security, and as a minimum, should be constructed of sheet metal material not less than 16 gauge in thickness and be equipped with a hasp to accommodate a high security padlock

- (8) Consolidated Showers and Latrines. A single set of shower/latrine facilities will be provided for each combined COF (UNICOF). The design layout shall allow adjustment for the ratio of males and females in any unit by repositioning the dividing wall between their facilities at the time of initial construction. The facilities will have Interior access to these facilities. Lockers with benches will be provided on a 3:1 ratio of lockers/shower. Minimum locker size shall be 12"(w)x18"(d)x36"(h).
- (9) Economy of Construction to Suit Function. Designers shall consider economy of construction to suit the function, i.e. warehouse or light industrial type facilities.
- (10) Operational Site Orientation. Operational facility relationships require locating COFs within a complex with direct access to the unit motor pool or other corresponding work areas. The intent is to provide a single battalion centric complex containing facilities to support company operations and vehicle maintenance in a single fenced compound. When site conditions do not permit this configuration, COFs should be placed adjacent to the vehicle maintenance complex to facilitate the movement of personnel and equipment between the two facilities.

3.3. TECHNICAL REQUIREMENTS

3.3.1. Site Design

The following site design requirements are applicable to the design of COFs:

(1) Exterior Covered Hardstand

Provide an exterior covered hardstand adjacent to the readiness module. Provide weatherproof lighting and weatherproof general purposes receptacles with ground fault protection. Lighting control shall be provided with local switches with photocell override. Provide one duplex receptacle for every two columns. The concrete pavement under the Covered Hardstand shall have a slope of no more than 2%.

(2) Service Yard

Provide a rigid concrete pavement for the service yard from the Readiness Module/Exterior Covered Hardstand (depending on site layout) to the project demarcation line. The service yard shall be a minimum of 80' deep in order to accommodate up to a 35-foot long vehicle with a 45-foot turning radius along the entire length of the Readiness Module/Exterior Covered Hardstand. The service yard shall be sloped to drain away from the Readiness Module/Exterior Covered Hardstand area with a slope of no more than 2%. Provide accommodation for boot/TA-50 gear equipment washing, drainage, and grit removal. Provide one boot/TA-50 gear washing station per company. Each wash station shall include four freeze proof hose bibb and drying rack (handrail).

(3) Entrance Drive into Service Yard

Provide two 28-foot wide rigid concrete pavement entrance drives from the Service Yard to an adjacent roadway. Service drives shall be located on opposite sides of the service yard.

(4) Bollards

Provide 6-inch diameter by 5-foot high, concrete-filled, schedule 80 galvanized steel pipe bollards, 5-foot O.C. spacing, painted safety yellow for each column of the exterior covered hardstand located adjacent to the service yard where frequent vehicle movement increases the risk of damage by vehicle impact. Also, provide bollards 5 feet from the edge of electrical and mechanical equipment, and to protect the corners of Admin/Readiness buildings. Bollard footings shall be designed to withstand vehicular impact.

(5) Privately Owned Vehicles (POV) Parking

POV parking to be provided by others.


3.3.2. Architectural Design

[Not Supplied] Page 10 of 151

(1) Exterior architectural features of the building shall be designed based on the following and in accordance with the established Installation architectural theme.

- (2) The Readiness Module shall be constructed to meet the requirements of a Risk Level II analysis in accordance with AR 190-51 and AR 190-13. In conjunction with this, it has been determined that a minimum exterior wall construction consisting of 26 gauge metal wall panels with insulation and an interior metal liner panel extended to a height 8' above the finished floor will satisfy the minimum Risk Level II requirements of AR 190-51, Appendix B-2, paragraph c. The minimum interior wall construction for dividing walls between company readiness areas shall consist of a stud wall with impact resistant gypsum wall board each side.
- (3) Natural Lighting. Provide windows for natural lighting and ventilation in all office areas wherever possible. All operable windows provided shall have locks and insect screens. Preference is for natural lighting to be provided at Readiness Areas to the greatest extent possible.
- (4) Sound Insulation. Provide sound insulation in all administration areas to meet a minimum rating of STC 42 at walls and floor/ceiling assemblies, and a rating of STC 33 for doors, which are to be solid core wood in a metal frame. In addition to the sound insulation required, conference areas shall meet a Noise Criteria (NC) 30 rating in accordance with ASHRAE Fundamentals Handbook.
- (5) Office and Administrative Areas. The preference is to provide maximum flexibility for future change within office and administration areas. The command section offices shall be constructed to provide privacy and sound control in accordance with SOUND INSULATION paragraph above. The intent for these areas is to minimize load-bearing walls to the greatest extent possible so as to accommodate future reconfiguration of spaces. This same construction requirement is also applicable to walls between companies in the readiness areas.
- (6) TA-50 Storage Lockers. TA-50 lockers shall be provided as indicated in Paragraph 3.2.3 (3), with size and appearance similar to that shown below. TA-50 lockers shall be single tier, heavy duty, all welded ventilated type and meet the following minimum requirements:
- (a) All tops, bottoms and shelves shall be constructed of minimum 16 gauge thick cold rolled sheet steel. All sides, intermediate partitions and backs shall be constructed of minimum 14 gauge flattened expanded metal or perforated metal with a minimum free area of 50%, welded to angle iron frames. Frames shall be constructed of minimum 1" X 1" X 1/8" angle iron steel. Thickness of metal and details of assembly and supports shall provide strength and stiffness.
- (b) Double doors shall have a three-point three-sided cremone latch and shall be padlockable. Doors shall be hinged with minimum five knuckle heavy duty steel pin butt hinges welded to both door and locker frame provide three hinges per single tier door.
- (c) Each locker shall include: one aluminum number plate (numbered in sequential order), one full width shelf located 12" from the top with clothes hangar rod and three locker hooks mounted below.
- (d) Lockers shall be galvanized and coated with a high quality durable finish with color to be manufacturer's standard tan or gray.
- (e) Locker shall be anchored to concrete floor in accordance with manufacturer's recommendations.

Section: 01 10 00 [Not Supplied]
Page 11 of 151



3.3.3. Fire Protection

(1) Standards and Codes

All fire protection and life safety features shall be in accordance with UFC 3-600-01 and the criteria referenced therein. COFs shall be classified as mission essential and shall be provided with sprinkler protection.

(2) Fire Protection and Life Safety Analysis

A fire protection and life safety design analysis shall be provided for all buildings in the project. The analysis shall be submitted with the interim design submittal. The analysis shall include classification of occupancy (both per the IBC and NFPA 101); type of construction; height and area limitations (include calculations for allowable area increases); life safety provisions (exit travel distances, common path distances, dead end distances, exit unit width required and provided); building separation or exposure protection; specific compliance with NFPA codes and the IBC; requirements for fire-rated walls, doors, fire dampers, etc.; analysis of automatic suppression systems and protected areas; water supplies; smoke control systems; fire alarm system, including connection to the base-wide system; fire detection system; standpipe systems; fire extinguishers; interior finish ratings; and other pertinent fire protection data. The submittal shall include a life safety floor plan for all buildings in the project showing occupant loading, occupancy classifications and construction type, egress travel distances, exit capacities, areas with sprinkler protection, fire extinguisher locations, ratings of fire-resistive assemblies, and other data necessary to exhibit compliance with life safety code requirements.

(3) Sprinkler System

Provide complete sprinkler protection for Company Operations Facilities, including both Administrative Modules and Readiness Modules, designed in accordance with UFC 3-600-01 and NFPA 13. Wet pipe sprinkler systems shall be provided in areas that are heated and dry pipe sprinkler systems shall be provided in areas subject to freezing. The Covered Hardstand, if not separated by adequate distance per the IBC, Table 602, shall be considered to be part of the COF facility and shall require sprinkler protection. The sprinkler system design shall be in accordance with UFC 3-600-01 and NFPA 13. The sprinkler hazard classifications shall be in accordance with UFC 3-600-01, NFPA 13, and other applicable criteria. Design densities, design areas and exterior hose streams shall be in accordance with UFC 3-600-01. The sprinkler systems shall be designed and all piping sized with computer generated hydraulic calculations. The exterior hose stream demand shall be included in the hydraulic calculations. A complete sprinkler system design, including sprinklers, branch lines, floor mains and risers, shall be shown on the drawings. The sprinkler system plans shall include node and pipe identification used in the hydraulic calculations. All sprinkler system drains, including main drains, test drains, and auxiliary drains, shall be routed to a 2-foot by 2-foot splash block at exterior grade.

(a) Sprinkler Service Main and Riser

Section: 01 10 00 [Not Supplied]
Page 12 of 151

The sprinkler service main shall be a dedicated line from the distribution main. Sprinkler service and domestic service shall not be combined. The sprinkler service main shall be provided with an exterior post indicator valve with tamper switch reporting to the fire alarm control panel (FACP). The ground floor entry penetration shall be sleeved per NFPA 13 requirements for seismic protection. The sprinkler entry riser shall include a double check backflow preventer, a fire department connection, and a wall hydrant for testing of backflow preventer. The sprinkler system shall include an indicating control valve for each sprinkler system riser, a flow switch reporting to the FACP, and an exterior alarm bell. All control valves shall be OS&Y gate type and shall be provided with tamper switches connected to the FACP. Facilities with multiple floors shall be provided with floor control valves for each floor. The floor control valve assembly shall be in accordance with UFC 3-600-01, Figure 4-1.

(b) Exterior Hose Stream

Exterior hose stream demand shall be in accordance with UFC 3-600-01. Exterior hose stream demand shall be included in the sprinkler system hydraulic calculations.

(c) Backflow Preventer

A double check backflow preventer shall be provided on the fire water main serving each building. This shall be located within the building. An exterior wall hydrant with dual hose connections with OS&Y valve shall be provided to allow testing of backflow preventer at design flow as required by NFPA 13.

(d) Fire Department Connection

A fire department connection shall be provided for each building with sprinkler protection. These shall be located to be directly accessible to the fire department.

(4) System Components and Hardware

Materials for the sprinkler system, fire pump system, and hose standpipe system shall be in accordance with NFPA 13 and NFPA 20.

(5) Protection of Piping Against Earthquake Damage

Sprinkler and fire pump piping systems shall be protected against damage from earthquakes. Seismic protection shall include flexible and rigid couplings, sway bracing, seismic separation assemblies where piping crosses building seismic separation joints, and other features as required by NFPA 13 for protection of piping against damage from earthquakes.

(6) Fire Water Supply

Fire flow test data is provided in Appendix D.

(7) Fire Pump

The requirement for a fire pump installation shall be determined by the Contractor based on fire flow test data from the project site and fire protection system design requirements for the project. If required a complete fire pump installation shall be provided for the facility. It shall comply with the requirements of UFC 3-600-01, NFPA 13 and NFPA 20. The Contractor shall submit fire pump design analysis and drawings in the design requirements.

(8) Fire Detection and Alarm

Refer to Paragraph 3.3.7, Electrical and Communication Systems, for requirements.

(9) Building Construction

Construction shall comply with requirements of UFC 3-600-01, the International Building Code and NFPA 101.

(a) Fire Extinguisher Cabinets and Brackets

Fire Extinguisher cabinets and brackets shall be provided when fire extinguishers are required by UFC 3-600-01 and NFPA 101. Placement of cabinets and brackets shall be in accordance with NFPA 10. Semi-recessed cabinets shall be provided in finished areas and brackets shall be provided in non-finished areas (such as utility rooms, storage rooms, shops, and vehicle bays). Fire extinguishers shall not be provided in this contract.

Section: 01 10 00 [Not Supplied]
Page 13 of 151

(b) Interior Wall and Ceiling Finishes

Interior wall and ceiling finishes and movable partitions shall conform to the requirements of UFC 3-600-01 and NFPA 101.

3.3.4. Thermal Performance

See Paragraph 5.

3.3.5. Plumbing

(1) Exterior Wall Hydrants

In addition to wall hydrants provided around perimeter of building(s), one additional freeze-proof exterior wall hydrant or wall faucet per company shall be provided at the hardstand.

(2) Domestic Hot Water System

The main water heating equipment shall be located within a mechanical room, and also located on the ground floor level only. Instantaneous water heaters are not allowed to be used for hot water serving all COF areas except Readiness Area. System storage and recovery shall be sized to deliver sufficient capacity for all showers, for a continuous duration of ninety (90) minutes. Usage diversity factor for the showers shall be one. Minimum system total storage of water heater(s) shall be 400 gallons for 1- and 2-company COFs, and 600 gallons for 3-company and larger COFs.

3.3.6. Heating, Ventilating, and Air Conditioning

(1) Administrative Areas

See Paragraph 5 for heating and cooling of administrative areas. The admin building's HVAC system design should include flexibility in zoning to where it can address future changes in occupant densities (e.g., a platoon office suite converted to a conference room). Administrative areas shall be temperature-controlled by the DDC system. Temperature setpoint adjustment shall be accomplished via DDC System by authorized personnel.

(a) Communications and SIPRNet rooms will each be served by an independent and dedicated air-handling system. Air handling unit system(s) shall not be floor-space mounted within the actual space served. Rooms shall be maintained at 72 degrees F and 50 percent relative humidity year-round. Assume 1775 BTU per hour for the equipment heat dissipation. Contractor shall verify this load during the design stage.

(2) Readiness Areas

The readiness module shall be heated and air conditioned. Separate air side equipment (heating, ventilation and air conditioning units) shall be provided for each readiness module. Indoor design temperature for heating shall be 55 degrees F, and for cooling the indoor design conditions shall be 80 degrees F dry bulb with a maximum 60 percent relative humidity. Whenever the indoor dry bulb temperature and/or the maximum relative humidity is exceeded, the air conditioning unit shall run, and shall continue to run until the design dry bulb temperature and the relative humidity requirements are satisfied. The air conditioning unit serving the readiness area shall be capable of providing outside air quantities, in accordance with ASHRAE 62.1, for the design people load of the readiness area. Arms vaults shall be cooled to 80 degrees F with room air to be 100% exhausted. Ventilation for Arms Vaults shall be provided in accordance with ASHRAE 62.1 requirements for storage rooms. Communication rooms located in Readiness Building will be served by an independent and dedicated air-handling system and shall be conditioned per Administrative Areas paragraph requirements. Administrative-type areas located within the Readiness Building shall be conditioned per Paragraph 5 requirements.

(3) HVAC Controls

HVAC Controls shall be in accordance with paragraph 5.8.3. See Appendix for HVAC Controls for typical control system points schedules. These schedules identify as a minimum points to be monitored and controlled by the building automation system (BAS). See paragraph 6 for any additional installation specific points. The points schedule drawings convey a great deal of information critical to the design, installation, and subsequent performance of the control system. It includes hardware input/output information, device ranges and settings, ANSI 709.1 communication protocol data, and information about data that is to be used at the operator workstation by the

Section: 01 10 00 [Not Supplied]
Page 14 of 151

Monitoring and Control software. These schedules are available as an excel spread sheet and as AutoCAD drawings on the Engineering Knowledge Online (EKO) website https://eko.usace.army.mil/fa/bas/. Point schedule of system types not addressed in the appendix shall be developed by the Contractor, and shall be sufficiently detailed to a level consistent to a similar listed system in the appendix. It is recommended that all of the guidance and instruction documents be reviewed prior to using any of the info, as the documents provide necessary and critical information to the use of the website drawings and other information.

3.3.7. Electrical and Communications

See Paragraph 6 for clarifications and additional requirements for the electrical and communication systems.

- (1) Interior Electrical and Communications
- (a) Electrical
- 1. Characteristics. Select electrical characteristics of the power system to provide a safe, efficient, and economical distribution of power, based upon the size and types of loads to be served. Use distribution and utilization voltages of the highest level that is practical for the load to be served.
- 2. Nonlinear Loads. The effect of nonlinear loads such as computers and other electronic devices shall be considered and accommodated as necessary. These loads generate harmonics, which can overload conventionally sized conductors or equipment and thereby cause safety hazards and premature failures. Circuits serving such devices shall be equipped with a separate neutral conductor not shared with other circuits. Panelboards and any dry type transformers shall be rated accordingly.
- 3. Lightning Protection System and Transient Voltage Surge Protection. Design shall be in accordance with NFPA 780 and other referenced criteria. Provide transient voltage surge protection.
- 4. Receptacles. Power receptacles shall be provided per NFPA 70 and in conjunction with the proposed equipment and furniture layouts. Provide power connectivity to each workstation. Power poles shall not be used. Provide duplex receptacles adjacent to each duplex (voice/data) outlet and CATV outlet.
- (b) Lighting. Lighting and lighting controls shall comply with the recommendations of the Illumination Engineering Society of North America (IESNA) and the requirements of ASHRAE 90.1.
- 1. Interior Lighting. Interior ambient illumination shall provide a generally glare free, high quality lighting environment and conform to IESNA RP-1-04.
- (c) Telecommunication
- 1. Telecommunications Rooms. Telecommunications Rooms shall be provided for voice and data as shown on the standard design layouts. The telecommunications rooms shall be designed in accordance with the I3A Criteria.
- 2. Telecommunications Outlets. Telecommunications outlets shall be provided per the I3A Technical Criteria based on functional purpose of the various spaces with the facility as modified by user special operational requirements. All COF workstations\desks shall have voice and data connection capability. All conference rooms shall have voice and data connection capability (minimum fouroutlets). A wall telephone outlet with a single jack shall be provided in each mechanical room, electrical room, arms vault and communications room and entrances/exits in the Readiness Modules. Provide a duplex outlet (voice/data) for a network printer/copier in the vending area, in the storage room adjacent to each suite and in the corridor to the offices. Provide a duplex (voice/data) outlet at the desk in each of the Storage Rooms and Arms Vault in the Readiness Module. Telecommunications infrastructure shall meet the Installation Information Infrastructure Architecture (I3A) Criteria and ANSI/TIA/EIA requirements.
- 3. Cable Trays. Provide cable tray pathways through-out the facility (Admin and Readiness Modules) to support the systems required for the construction of the facility as well as user's computer networks, video integration system, telecommunication systems and other specialized electronic systems.
- 4. For Detached Readiness Modules, provide a separate communication room on the mezzanine as shown with the integrated Admin Option of the floor plans. The telecommunications rooms shall be designed in accordance with the I3A Criteria and ANSI/EIA/TIA-569-B. Where copper cable runs exceed 295 feet, provide additional telecommunication rooms on the mezzanine as required. The incoming telephone service (voice and data) shall be from the nearest manhole or from the main telephone communication room in the Admin Module, size the cables and conduits as per I3A Criteria.

Section: 01 10 00 [Not Supplied]
Page 15 of 151

a. All copper cabling leaving one building to go to another shall be treated as OSP cable and follow OSP cable requirements as stated in section 3.5.4 of the I3A and I3MP Grounding and Bonding Guide; this includes use of protector blocks and other grounding requirements as necessary to avoid lightning issues resulting in damaging of IT equipment.

b. Option to use fiber cable via OSP cable is authorized from the main TR and will be terminated inside the next building on a fiber distribution panel, rack, or cabinet as required, with a minimum of 6-strands.

(d) SIPRNET

- 1. The SIPRNET room and infrastructure shall be designed and constructed in accordance with the "Building SIPRNET Communication Room New Construction Guidance", paragraph of the Technical Guide for the Integration of SIPRNET (Secret Internet Protocol Router Network). The SIPRNET building infrastructure design and installation shall be coordinated with the local NEC.
- 2. In the NSTISSI 7003 and the Technical Guide for Integration of SIPRNET, paragraph "Protective Distribution System", the word "shall" shall be substituted for the word "should" or "will" in this paragraph.
- 3. Install one SIPRNET outlet with one drop in each Company Commander's office. Install one SIPRNET outlets with four drops in each unit conference room. The SIPRNET building infrastructure shall use Category 6 UTP copper cables with red cable jacket and red outlet modules unless otherwise directed by the local NEC. Cables shall be terminated in the SPIRNET room and at the outlet in accordance with the I3A Technical Criteria for data cables. Where copper cable runs exceed 295 feet, see guidance in paragraph "Building SIPRNET Communication Room New Construction Guidance".
- 4. Specifications Section 27 05 28.39, "SURFACE RACEWAYS FOR COMMUNICATION SYSTEMS" for the SIPRNET Communications System shall be incorporated into the project. Copy of the specifications can be obtained at the following URL: (ftp://ftp.usace.army.mil/pub/sas/Surface_Raceways/). The surface mounted raceway shall be used instead of the surface mounted conduit unless otherwise indicated by the local NEC.
- (e) Cable Television. CATV shall be provided in all offices, conference rooms (minimum two outlets), and one in each of the readiness areas. The cable television system shall consist of cabling, pathways, and outlets. All building CATV systems shall conform to APPLICABLE CRITERIA to include I3A Technical Criteria and the UFC 3-580-01 Telecommunications Bldg Cabling Systems Planning/Design.
- (f) Audio/Visual Systems. Provisions (consisting of a power receptacle and conduit for signal wiring) for a Government-furnished Government-installed projector shall be provided in each conference room.
- (g) Intrusion Detection System. Contractor shall install the necessary conduit, electrical power, and wiring, to support installation of an ICIDS system in each of the Arms Room and SIPRNET Room. The Government shall install the signal devices and equipment necessary to activate the system.
- (h) Mass Notification System. A mass notification system shall be provided for each facility and throughout the complex in accordance with UFC 4-010-01. The system shall be fully compatible with and integrated with the local Installation wide Mass Notification System.
- (i) Grounding. The ground counterpoise shall be provided around the building perimeter and shall be utilized for grounding incoming service, building steel, telephone service, piping, lightning protection, and internal grounding requirements. Ground straps shall be provided where required by function and will be connected to the building grounding system. Additional grounding may be provided based on project requirements. Systems shall conform to NFPA 70 National Electrical Code, NFPA 780 Lightning Protection Code, local codes, and the US Army I3A Criteria.
- (j) Fire Detection and Alarm
- 1. A fire alarm and detection system shall be provided for this facility. It shall comply with the requirements of UFC 3-600-01 and NFPA 72. The system shall be addressable and fully compatible with and integrated with the local Installation wide Fire Alarm System.
- 2. All initiating devices shall be connected, Class A, Style 6, to signal line circuits (SLC). All alarm appliances shall be connected to notification appliance circuits (NAC), Class A. A looped conduit system shall be provided so that if the conduit and all conductors within are severed at any point, all NAC and SLC shall remain functional.
- 3. Breakglass manual fire alarm stations shall not be used.
- 4. Over-voltage and surge protection shall be provided at the input power of all panels.

(k) Future Soldier LAN Warrior System. Provide a disconnect switch (208/120V, 3 phase, 4 wire) in each of the Secure Non-Sensitive Storage Room in the Readiness Module. Size the disconnect switch(s) and the circuit breaker(s), conductors and conduit(s) from a 208 volt, 3 phase, 4 wire distribution panel to the disconnect switch(s) based on a 200 VA continuous demand load for 100 percent of the maximum personnel in each Company Readiness Area.

3.3.8. Energy Conservation

- (1) Energy Performance. The building, including the building envelope, HVAC systems, service water heating, power, and lighting systems shall be designed to achieve a non-plug load energy consumption that is at least 40% below the consumption of a baseline building meeting the minimum requirements of ANSI/ASHRAE/IESNA Standard 90.1 (see paragraph 5.9 Energy Conservation). (Note: Plug loads shall be included in building energy modeling but are subtracted in the final calculation of Energy Performance. See section "Design After Award" for additional guidance.)
- (2) Required Energy Conservation Features. All items listed in the required energy conservation features table shall be provided as a minimum. Additional energy conservation features may be required to meet the above energy performance. The contractor is responsible for determining and providing additional energy conservation features to meet the energy performance requirements. Where equipment types are indicated, only minimum efficiencies apply.
- (3) Compliance Documentation. The required energy conservation features shown in the table above contributes to the achievement of the above energy performance and are life cycle cost effective for a COF. Use of the required energy conservation features does not eliminate the requirement for energy analysis calculations documenting compliance. The D-B contractor must document compliance with the above energy performance utilizing the methodology described in ASHRAE 90.1, Appendix G as discussed in section 01 33 16 Design After Award. The design analysis shall document each of the features selected to achieve the specified energy performance.
- (4) Schedules. The following facility schedules must be used in all facility energy simulations for purposes of documenting compliance with energy performance requirements.

COF Climate Zone 4A, Energy	Conservation	Features	Table ₍₈₎
-----------------------------	--------------	----------	----------------------

Item	Component		Minimum Requirements
		Assembly Max (2)	Min R-Value (2)
Roof	Insulation Entirely Above Deck	U-0.0388	R-25ci
	Attic and Other		R-38
	Solar Reflectance (3)		Cool Roof for Low Slope & Light color all others
	Mass		R-13
Walls	Steel Framed	- U-0.0676	R-13 + R-7.5ci
VVuiis	Wood Framed and Other	0-0.0070	R-13 + R-3.8ci
5 1	Mass		R-10.4ci.
Floors Over Unconditioned	Steel Joist	0.0739	R-13
Space	Wood Framed and Other	0.0700	R-13
Slob on Crado	Unheated	F-0.520	R-15.0 for 24 in.
Slab-on-Grade	Heated	F-0.843	R-20.0 for 24 in.
Doors	Swinging	U-0.50	Insulated
Doors	Non-Swinging	U-0.50	Insulated
Infiltration		0.25 cfm/ft ² @	75 Pa ₍₅₎
Vertical Glazing	Window to Wall Ratio (WWR)	< 15%	
	Thermal transmittance	U-0.42	

Item	Component	N	linimum Requirements
		Assembly	
		Max (2)	Min R-Value (2)
	Solar heat gain coefficient (SHGC)	0.39	
	South Overhangs	Yes; Projection	on Factor = 0.4
	Lighting Power Density (LPD)	See Lighting F	Power Table Below ₍₆₎
Interior	Occupancy Controls	Manual On/Au spaces)	uto Off (all periodically occupied
Lighting	Daylighting Controls	NR	
	Plug Load Lighting	Compact Fluo	rescent (CFL) with electronic ballast
	All Ballasts	Electronic	
	Friction rate	0.08 in. w.c./1	00 feet
Duete	Sealing	Seal class B	
Ducts	Location	Interior only	
	Insulation level	R-6 ₍₇₎	
Service Water	Gas hot water storage	90% Et	
Heating	Pipe Insulation(d < 1.5in. / d ≥ 1.5 in.)	1 in. / 1.5 in. ₍₇	')

Notes:

- 1. Omitted.
- 2. **U-values and R-values** for assemblies and their definitions, requirements, and determinations can be found in ANSI/ASHRAE/IESNA Standard 90.1.
- 3. Light colored and cool roofs: reflect and emit the sun's heat back to the sky instead of transferring it to the building below. "Coolness" is measured by two properties, solar reflectance and thermal emittance. Both properties are measured from 0 to 1 and the higher the value, the "cooler" the roof. A high reflectance keeps much of the sun's energy from being absorbed, while a high thermal emittance radiates away any solar energy that is absorbed, allowing the roof to cool more rapidly. Cool roofs are typically white and have a smooth surface. Commercial roof products that qualify as cool roofs fall into three categories: single-ply, liquid-applied, and metal panels. The solar reflectance and thermal emittance property values represent initial conditions as determined by a laboratory accredited by the Cool Roof Rating Council.

Cool roofs are cost effective over air-conditioned spaces for buildings located in climate zones 1 - 5. In these locations, a minimum of 75% of the entire roof surface not used for roof penetrations shall be covered with roofing products that comply with one or more of the following:

- Have a minimum initial SRI of 78 for a low-sloped roof (a slope less than or equal to 2:12) and a minimum initial SRI of 29 for a steep-sloped roof (a slope of more than 2:12).
- Comply with the criteria for the US EPA's Energy Star Program Requirements for Roof Products Eligibility Criteria.

For industrial buildings with only heating and ventilation, cool roofs can improve the comfort conditions (and hence productivity) in the space.

In order to be considered a cool roof, a solar reflectance of 0.67 when tested in accordance with ASTM C1549, ASTM E903, or ASTM E1918 and, in addition, a minimum thermal emittance of 0.75 when tested in accordance with ASTM C1371 or ASTM E408, or a minimum Solar Reflective Index of 78 when determined in accordance with the Solar Reflectance Index method in ASTM E1980 where standard white is SRI = 100 and standard black has SRI = 0. An SRI can be determined by the following equations:

$$SRI = 123.97 - 141.35(x) + 9.655(x^2)$$

Where

Section: 01 10 00 [Not Supplied]
Page 18 of 151

$$x = \frac{20.797 \times \alpha - 0.603 \times \varepsilon}{9.5205 \times \varepsilon + 12.0}$$

Where α is the solar absorptance (= 1 – solar reflectance) and ϵ is the thermal emissivity, which were derived from ASTM E1980 assuming a medium wind speed.

The limited color choices available for cool roofs may not be acceptable to the installation. When this conflict cannot be resolved, the designer shall use the highest reflectance available in the roofing type/color acceptable to the installation.

Characteristics of reflective roofing materials.

Roofing Type	Color	New Solar Reflectance	Aged Solar Reflectance	New Thermal Emittance	SRI (ASTM E1980
Roof Coatings	White	0.70 - 0.85	0.50 -0.65	0.85	84 – 106
Roof Coatings	Grey or Tan	0.70	0.50	0.85	84
Roof Coatings	Terra Cotta or Brown	0.40	0.30	0.85	43
Roof Coatings	Aluminized	0.50	0.40	0.50	42
Metal Paint	Red	0.25	0.25	0.83	22
Metal Paint	Terra Cotta	0.35	0.35	0.83	36
Metal Paint	Bright Red	0.35	0.35	0.83	36
Metal Paint	Beige/Off White	0.55	0.55	0.83	63
Metal Paint	Tan	0.45	0.45	0.83	49
Metal Paint	Dark Blue	0.25	0.25	0.83	22
Metal Paint	Medium to Light Blue	0.32	0.32	0.83	32
Metal Paint	Dark Brown	0.25	0.25	0.83	22
Metal Paint	Medium to Light Brown	0.32	0.32	0.83	32
Metal Paint	Dark Green	0.25	0.25	0.83	22
Metal Paint	Medium to Light Green	0.32	0.32	0.83	32
Metal Paint	White	0.65	0.65	0.83	77
Metal Paint	Bright White	0.70	0.70	0.83	84
Metal Paint	Black	0.25	0.25	0.83	22
Metal Paint	Dark Grey	0.25	0.25	0.83	22
Metal Paint	Medium to Light Grey	0.35	0.35	0.83	36
Metal Paint	Pearlescent Colors	0.35	0.35	0.75	32
Galvalume	Unpainted	0.65	0.55	0.05	45
Copper Metal	Unpainted	0.85	0.18	0.03	89
Galvanized Steel	Unpainted	0.40	0.20	0.50	26
EPDM Membrane	Black	0.05	0.10	0.85	0
TPO Membrane	White	0.80	0.60	0.85	99
TPO Membrane	Grey	0.50	0.40	0.85	57
PVC Membrane	White	0.80	0.60	0.85	99
PVC Membrane	Grey	0.50	0.40	0.85	57
Asphalt Shingle	Dark Color	0.10	0.10	0.85	4
Asphalt Shingle	Light Color	0.25	0.25	0.85	23
Modified Bitumen Cap Sheet	Dark Color	0.10	0.10	0.85	4
Modified Bitumen Cap Sheet	Light Color	0.25	0.25	0.85	23
Modified Bitumen Cap Sheet	White	0.50-0.60	0.40 – 0.45	0.85	57 - 71

4. **NR** means there is no requirement or recommendation for a component in this climate zone.

- 5. Increased building air tightness. Building air leakage (measured in cfm/ft²) is the average volume of air(measured in cubic feet per minute) that passes through a unit area of the building envelope (measured in square feet) when the building is maintained at a specified internal pressure (measured in Pascals). ASHRAE has proposed a building air tightness requirement of 0.4 cfm/ft² @ 75 Pa as an addendum to Standard 90.1. ASHRAE has also proposed an approach to complying with the new requirement with a pressurization test to show that the building leakage does not exceed 0.4 cfm/ft² at 75 Pa. This air tightness requirement provides a number that can be used for the energy simulations and was assumed to be the baseline leakage rate. The air tightness requirement adopted by the U.S. Army for new construction is more stringent than the one proposed by ASHRAE and requires that the leakage rate must not exceed 0.25 cfm/ft² at 75 Pa, and was assumed for the energy efficient building models. To convert the values used for building leakage tests at the pressure difference of 75Pa to the values which can be used to calculate required excessive outdoor air supply rates, the following equation can be used ΔQ = Q75 * (5/75)^{0.65} = 0.172 * Q75. The excessive airflow rate for the building complying with the new ASHRAE 90.1 Standard air leakage requirement is 0.069 cfm/ft². Respective number for the building built to the Army model RFP requirement is 0.043cfm/ft².
- 6. Lighting Power Density:

	Bas	seline	Efficien	t Model
Zone	W/ft²	W	W/ft ²	W
Office1	1.00	4,947	0.90	4,452
Office2	1.00	4,947	0.90	4,452
Lockers	0.60	888	0.50	740
Utilities	1.50	2,219	1.00	1,479
Corridor	0.50	1,456	0.40	1,165
ReadiBay				
(x4)	0.90	4,787	0.70	3,723
Arms (x4)	1.40	765	1.10	601
Storage (x4)	0.90	1,325	0.70	1,031
		41,967.5		33,710

- 7. **Duct and pipe insulation**, values are from the ASHRAE Advanced Energy Design Guide for Small Offices.
- 8. **Energy Conservation Features Tables**. These tables are applicable to both the integrated and the detached Admin configurations of COFs.
- 9. **HVAC system**. The recommended PVAV system is for the Admin module. The Readiness building requires a separate HVAC unit for each company's module. High efficiency PSZ units may be used in these areas in lieu of PVAV units.

	Day of																								
Schedule	Week	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
ALWAYS_ON	All	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
ALWAYS_OFF	All	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	WD, SDD	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.3	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.9	0.5	0.3	0.3	0.2	0.2	0.1	0.1
	Sat, Sun, WDD.																							ı /	
BLDG_LIGHT	Hol	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1
	WD, SDD	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.9	0.9	0.9	0.9	0.8	0.9	0.9	0.9	0.9	0.5	0.3	0.3	0.3	0.3	0.3	0.3
	WDD	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
BLDG_EQUIP	Sat, Sun, Hol	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3	0.3
	WD	0	0	0	0	0	0	0	0.2	0.9	0.9	0.9	0.9	0.5	0.9	0.9	0.9	0.9	0.3	0	0	0	0	0	0
	SDD	0	0	0	0	0	0	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	0	0
BLDG OCC	Sat, Sun, WDD, Hol	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
BEBG_OCC	WD	0	0	0	0	0	0	0	0	0.1	0.8	0.1	0	0	0	0	0	0	0	0	0	0	0	0	0
	SDD	0	0	0	0	0	0	0	0	0.1	0.0	0.1	0	0	1	0	0	0	0	0	0	0	0	0	0
	Sat, Sun, WDD,	0		0	0	0	0		0	0	0	0	0	0				0	0	0		0	0		
ReadiBay_OCC	Hol	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
	WD, SDD	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	Sat, WDD	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
HVACOperation	Sun, Hol	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	WD, SDD, WDD	0	0	0	0	0	0	1	1	1	1	1	1	1	1	1	1	1	1	1	0	0	0	0	0
	Sat	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
ExhFan	Sun, Hol	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
ACTIVITY	All	12 0																							
WORK_EFF	All	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
AIR_VELO	All	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
	All	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	All	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5	0.5
CLOTHING	All	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	WD, SDD	1	1	1	1	1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	1	1
	WDD	1	1	1	1	1	1	1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	1	1	1	1	1	1
INFIL	Sat, Sun, Hol	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
PlantOn	All	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1

Schedule	Day of Week	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
FAN	All	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
	WD, WDD	13	13	13	13	13	13	22	22	22	22	22	22	22	22	22	22	22	22	22	13	13	13	13	13
	SDD	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13
DI DO LITOSET	Sat	13	13	13	13	13	13	22	22	22	22	22	22	22	13	13	13	13	13	13	13	13	13	13	13
BLDG_HTGSET P	Sun, Hol	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13
	WD, SDD	32	32	32	32	32	32	24	24	24	24	24	24	24	24	24	24	24	24	24	24	24	24	32	32
	Sat	32	32	32	32	32	32	24	24	24	24	24	24	24	24	24	24	24	24	32	32	32	32	32	32
BLDG_CLGSET	WDD	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32
P	Sun, Hol	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32
	WD, WDD	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13
	SDD	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13
ReadiBay HTGS	Sat	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13
ETP	Sun, Hol	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13	13
	WD, SDD	32	32	32	32	32	32	28	28	28	28	28	28	28	28	28	28	28	28	28	28	28	28	32	32
	Sat	32	32	32	32	32	32	28	28	28	28	28	28	28	28	28	28	28	28	32	32	32	32	32	32
ReadiBay CLGS	WDD	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32
ETP	Sun, Hol	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32	32
	WD, SDD	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50
Humidity	Sat, WDD	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50
Setpoint	Sun, Hol	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50	50
MinOA	All	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1	1
Dual Zone Control Type	All	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4	4
	WD, SDD	0	0	0				0	0.5										0.5	0	0	0		0	
	Sat, WDD	0	0	0	0	0	0	0	0.5	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.5	0	0	0	0	0	0
BLDG SHW	Sun, Hol	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
SHW Latent fract	All	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
SHW Sensible fract	All	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1
SHW Temp	All	43	43	43	43	43	43	43	43	43	43	43	43	43	43	43	43	43	43	43	43	43	43	43	43
SHW Supply Temp	All	55	43 55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	<u>43</u> 55	55	55	<u>43</u> 55	55	55	55
Lockers sub cat Latent fract	All	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1	0.1

Schedule	Day of Week	1	2	3	4	5	6	7	8	9	10	11	12	13	14	15	16	17	18	19	20	21	22	23	24
Lockers sub cat Sensible fract	All	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2	0.2
Lockers sub cat Temp	All	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60
Lockers sub catHot Supply Temp	All	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55	55
SHWSys1-Loop- Temp	All	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0	0
SHWSys1 Water Heater Setpoint	All	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60	60
SHWSys1 Water Heater Ambient	All	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22	22

Section: 01 10 00 [Not Supplied]
Page 23 of 151

3.3.9. Furniture Systems

The following criterion describes the furnishing requirements for all room types. Furnishings, other than installed equipment, are to be Government-furnished and Government-installed (GFGI) unless otherwise specified in this document. The following furnishings list is provided for coordination of room and office layouts to ensure suitability for their intended function.

Table 1: Room Size and Furnishing Chart

Room	Description	NSF	Comments	Furniture Required
со	Commander	150	PRIVATE OFFICE	U-shaped executive desk with two pedestals, dbl pedestal credenza, hutch, two 4-drawer lateral files, one conference table, four conference chairs, one executive chair.
хо	Executive Officer	150	PRIVATE OFFICE	L-shaped double pedestal desk unit, hutch, two 4-drawer lateral files, two guest chairs, one task chair.
1SG	1 st Sergeant	150	PRIVATE OFFICE	L-shaped double pedestal desk unit, double pedestal credenza, hutch, two 4-drawer lateral files, four guest chairs, one executive chair.
TRAINING	Training Room	150	PRIVATE OFFICE	L-shaped double pedestal desk unit, hutch, two 4-drawer lateral files, two guest chairs, one task chair.
PLATOON	Platoon Offices	150x4	SEMI-PRIVATE OFFICES	For each 150 SF office, 2 desks to accommodate computers, 2 task chairs, 2 bookcases for manuals, two 4-drawer file cabinets.
CONF. ROOM	Conference Room	Varies	CONFERENCE ROOM	Conference Table with 10 chairs and 6 side chairs.
ARMS VAULT	Arms Vault	Varies	CONSTRUCTED IN ACCORDANCE WITH AR 190-11, APP G.	1 desk to accommodate a computer, 1 task chair, 1 bookcase for manuals, one 4-drawer file cabinet, and 1 work bench.
UNIT STOR.	Unit Storage	Varies	STORAGE ROOM	1 desk to accommodate a computer, 1 task chair, 1 bookcase for manuals, 4 lockable metal cabinets with shelves, two 4-drawer file cabinets, industrial shelving approximately 10'wx4'dx6'h each - 2 for 1st 100PN, 2 additional for every 50PN thereafter.
COMM. STOR.	Communications Storage	Varies	STORAGE ROOM	1 desk to accommodate a computer, 1 task chair, one 4-drawer file cabinet, and 4 lockable metal cabinets with shelves.
NBC STOR.	NBC Storage	Varies	STORAGE ROOM	1 desk to accommodate a computer, 1 task chair, one 4-drawer file cabinet, and 4 lockable metal cabinets with shelves.
SECURE STOR.	Secure Storage	Varies	STORAGE ROOM	4 lockable metal cabinet with shelves and industrial shelving approximately 10'wx4'dx6'h each - 1 for 1st 100PN, 1 additional for every 50PN thereafter.

3.3.10. References

- (1) Army Regulation 190-11 Physical Security of Arms, Ammunition and Explosives
- (2) Army Regulation 190–13 The Army Physical Security Program
- (3) Army Regulation 190-51, Security of Unclassified Army Property (Sensitive and Nonsensitive)
- (4) Army Regulation 380–5 Information Security Program
- (5) Army Regulation 380–19 Information Systems Security

Section: 01 10 00 [Not Supplied]
Page 24 of 151


- (6) Fed Spec AA-V-2737, Modular Vault Systems
- (7) Uniform Federal Accessibility Standards (UFAS)

3.4. PROGRAM REQUIREMENTS

The following table (COF Table 2) provides the space allocations for the various standard modules for COFs:

Table 2: Space Criteria for Company Operations Facilities

ADMIN MODULE MINIMUM REQUIRED NET AREAS (REQUIRED PER SPACE)	ADMIN (TYPICAL)			
ADMIN MODULE				
Office Areas				
Command/Platoon Storage	40			
XO	150			
1SG	150			
со	150			
Training Room	150			
Conference Room	310			
Platoon Offices	150			
READINESS MODULE VARIANTS - MINIMUM REQUIRED NET AREAS (BASED ON PERSONNEL	N N	N N	Q N	L 50 N
PER COMPANY)	100	150	200 PN	ADD'L PN
· ·	100	150	200	ADD'
PER COMPANY)	100	150	200	ADD'
PER COMPANY) READINESS MODULE Supply Bay Secure Storage for Non-Sensitive Items	166	306	504	169
PER COMPANY) READINESS MODULE Supply Bay Secure Storage for Non-Sensitive Items Vault	166 400	306 500	504 600	169 100
PER COMPANY) READINESS MODULE Supply Bay Secure Storage for Non-Sensitive Items Vault NBC Storage	166 400 94	306 500 152	504 600 198	169 100 52
PER COMPANY) READINESS MODULE Supply Bay Secure Storage for Non-Sensitive Items Vault	166 400	306 500	504 600	169 100
PER COMPANY) READINESS MODULE Supply Bay Secure Storage for Non-Sensitive Items Vault NBC Storage Communications Storage	166 400 94 94	306 500 152 152	504 600 198 198	169 100 52 52
PER COMPANY) READINESS MODULE Supply Bay Secure Storage for Non-Sensitive Items Vault NBC Storage Communications Storage Unit Storage	166 400 94 94	306 500 152 152	504 600 198 198	169 100 52 52
PER COMPANY) READINESS MODULE Supply Bay Secure Storage for Non-Sensitive Items Vault NBC Storage Communications Storage Unit Storage Readiness Bay	166 400 94 94 367	306 500 152 152 595	504 600 198 198 764	169 100 52 52 199
PER COMPANY) READINESS MODULE Supply Bay Secure Storage for Non-Sensitive Items Vault NBC Storage Communications Storage Unit Storage Readiness Bay TA-50 Lockers/Equipment Layout Area	166 400 94 94 367	306 500 152 152 595	504 600 198 198 764	169 100 52 52 199



Section: 01 10 00 [Not Supplied]
Page 26 of 151

4.0 APPLICABLE CRITERIA

Unless a specific document version or date is indicated, use criteria from the most current references as of the date of issue of the contract or task order, including any applicable addenda, unless otherwise stated in the task order. In the event of conflict between References and/or Applicable Military Criteria, apply the most stringent requirement, unless otherwise specifically noted in the contract or task order.

4.1. INDUSTRY CRITERIA

Applicable design and construction criteria references are listed in Table 1 below. This list is not intended to include all criteria that may apply or to restrict design and construction to only those references listed. See also Paragraph 3 for additional facility-specific applicable criteria.

Table 1: Industry Criteria

Air Conditioning and Refrigeration Institute (ARI)	
ARI 310/380	Packaged Terminal Air-Conditioners and Heat Pumps
ARI 440	Room Fan-Coil and Unit Ventilator
ANSI/ARI 430-99	Central Station Air Handling Units
ARI 445	Room Air-Induction Units
ARI 880	Air Terminals
Air Movement and Control Association (AMCA)	
AMCA 210	Laboratory Methods of Testing Fans for Rating
American Architectural Manufacturers Association (AAMA)	
AAMA 605	Voluntary Specification Performance Requirements and Test Procedures for High Performance Organic Coatings on Aluminum Extrusions and Panels
AAMA 607.1	Voluntary Guide Specifications and Inspection Methods for Clear Anodic Finishes for Architectural Aluminum
AAMA 1503	Voluntary Test Method for Thermal Transmittance and Condensation Resistance of Windows, Doors, and Glazed Wall Sections
American Association of State Highway and Transportation Officials (AASHTO)	
	Roadside Design Guide [guardrails, roadside safety devices]
	Standard Specifications for Transportation Materials and Methods of Sampling and Testing [Road Construction Materials]

	Standard Specifications for Structural Supracts for Highway Signa
	Standard Specifications for Structural Supports for Highway Signs, Luminaires and Traffic Signals
	Guide for Design of Pavement Structures, Volumes 1 and 2 [pavement design guide]
	A Policy of Geometric Design of Highways and Streets
American Bearing	Manufacturers Association (AFBMA)
AFBMA Std. 9	Load Ratings and Fatigue Life for Ball Bearings
AFBMA Std. 11	Load Ratings and Fatigue Life for Roller Bearings
American Boiler M	lanufacturers Association (ABMA)
ABMA ISEI	Industry Standards and Engineering Information
American Concrete Institute	
ACI 302.2R	Guide for Concrete Slabs that Receive Moisture-Sensitive Flooring Materials
ACI 318	Building Code Requirements for Structural Concrete
ACI SP-66	ACI Detailing Manual
ACI 530	Building Code Requirements for Masonry Structures
ADA Standards fo	r Accessible Design
See US Access Board	ADA and ABA Accessibility Guidelines for Buildings and Facilities,
	Chapters 3-10.
American Institute of Steel Construction (AISC)	
	Manual of Steel Construction – 13 th Edition (or latest version)
American Iron and Steel Institute	
AISI S100	North American Specification for the Design of Cold-Formed Steel Structural Members
American National Standards Institute 11 (ANSI)	

ANSI Z21.10.1	Gas Water Heaters Vol. 1, Storage water Heaters with Input Ratings of 75,000 Btu per Hour or less
ANSI Z124.3	American National Standard for Plastic Lavatories
ANSI Z124.6	Plastic Sinks
ANSI Z21.45	Flexible Connectors of Other Than All-Metal Construction for Gas Appliances
ANSI/IEEE C2-2007	National Electrical Safety Code
ANSI/AF&PA NDS-2001	National Design Specification for Wood Construction
American Society o	of Civil Engineers (ASCE)
ASCE 7	Minimum Design Loads for Buildings and Other Structures
ASCE 37	Design and Construction of Sanitary and Storm Sewers, Manuals and Reports on Engineering Practice [sanitary sewer and storm drain design criteria]
ASCE/SEI 31-03	Seismic Evaluation of Existing Buildings [Existing Building Alteration/Renovation]
ASCE/SEI 41-06	Seismic Rehabilitation of Existing Buildings [Existing Building Alteration/Renovation]
American Society o	of Heating, Refrigerating and Air Conditioning Engineers (ASHRAE)
ASHRAE 90.1	ANSI/ASHRAE/IESNA 90.1, Energy Standard for Buildings Except Low-Rise Residential Buildings
ASHRAE Guideline 0	The Commissioning Process
ASHRAE Guideline 1.1	The HVAC Commissioning Process
ASHRAE Handbooks	Fundamentals, HVAC Applications, Systems and Equipment, Refrigeration (Applicable, except as otherwise specified)
ASHRAE Standard 15	Safety Standard for Refrigeration Systems
ASHRAE Standard 62.1	Ventilation for Acceptable Indoor Air Quality
ASHRAE Standard 55	Thermal Environmental Conditions for Human Occupancy (Design portion is applicable)

American Society of Mechanical Engineers International (ASME)	
ASME BPVC SEC VII	Boiler and Pressure Vessel Code: Section VII Recommended Guidelines for the Care of Power Boilers
ASME A17.1	Safety Code for Elevators and Escalators
ASME B 31 (Series)	Piping Codes
American Water W	Vorks Association (AWWA)
	Standards [standards for water line materials and construction]
American Welding	Society
	Welding Handbook
	Welding Codes and Specifications (as applicable to application, see International Building Code for example)
Architectural Woo	dwork Institute (AWI)
Version 1.2	AWI Quality Standards 7th Edition
Associated Air Balance Council (AABC)	
AABC MN-1	National Standards for Testing and Balancing Heating, Ventilating, and Air Conditioning Systems
	AABC Associated Air Balance Council Testing and Balance Procedures
ASTM Internationa	ıl
ASTM C1060-90(1997)	Standard Practice for Thermographic Inspection of Insulation Installations in Envelope Cavities of Frame Buildings
ASTM E 779 (2003)	Standard Test Method for Determining Air Leakage Rate by Fan Pressurization
ASTM E1827-96(2002)	Standard Test Methods for Determining Airtightness of Buildings Using an Orifice Blower Door
Builders Hardware Manufacturers Association (BHMA)	
ANSI/BHMA	American National Standards for Builders Hardware

Building Industry Consulting Service International	
	Telecommunications Distribution Methods Manual (TDMM)
	Customer-Owned Outside Plant Design Manual (CO-OSP)
Code of Federal Reg	ulations (CFR)
49 CFR 192	Transportation of Natural and Other Gas by Pipeline: Minimum Federal Safety Standards
10 CFR 430	Energy Conservation Program for Consumer Products
Consumer Electronics Association	
CEA 709.1B	Control Network Protocol Specification
CEA 709.3	Free-Topology Twisted-Pair Channel Specification
CEA 852	Tunneling Component Network Protocols Over Internet Protocol Channels
Electronic Industries Association (EIA)	
ANSI/EIA/TIA 568	Structured Cabling Series
ANSI/EIA/TIA 569	Commercial Building Standard for Telecommunications Pathways and Spaces (includes ADDENDA)
ANSI/TIA/EIA-606	Administrative Standard for the Telecommunications Infrastructure of Commercial Buildings
J-STD EIA/TIA 607	Commercial Building Grounding and Bonding Requirements for Telecommunications
Federal Highway Administration (FHWA)	
	Manual on Uniform Traffic Control Devices for Streets and Highways [signage and pavement markings for streets and highways]
FHWA-NHI-01-021	Hydraulic Engineering Circular No. 22, Second Edition, URBAN DRAINAGE DESIGN MANUAL
Illuminating Engineering Society of North America (IESNA)	
IESNA RP-1	Office Lighting

IESNA RP-8	Roadway Lighting
IESNA Lighting Handbook	Reference and Application
Institute of Electrical	and Electronics Engineers Inc. (IEEE)
	Standard for Use of the International System of Units (SI): the Modern Metric System
Standard 1100	Recommended Practice for Powering and Grounding Sensitive Electronic Equipment
International Code Co	ouncil (ICC)
IBC	International Building Code
	Note: All references in the International Building Code to the International Electrical Code shall be considered to be references to NFPA 70.
	All references in the International Building Code to the International Fuel Gas Code shall be considered to be references to NFPA 54 and NFPA 58.
	All references in the International Building Code to the International Fire Code and Chapter 9 shall be considered to be references to Unified Facilities Criteria (UFC) 3-600-01.
IMC	International Mechanical Code –
	Note: For all references to "HEATING AND COOLING LOAD CALCULATIONS", follow ASHRAE 90.1
	Note: For all references to "VENTILATION", follow ASHRAE 62.1
IRC	International Residential Code
IPC	International Plumbing Code
IEC	Energy Conservation Code (IEC) –Applicable only to the extent specifically referenced herein. Refer to Paragraph 5, ENERGY CONSERVATION requirements.
IGC	International Gas Code - not applicable. Follow NFPA 54, National Fuel Gas Code and NFPA 58, Liquified Petroleum Gas Code.
International Organization for Standardization (ISO)	
ISO 6781:1983	Qualitative detection of thermal irregularities in building envelopes –

	infrared method
LonMark Internatio	nal (LonMark)
LonMark Interoperability Guidelines	(available at www.lonmark.org), including: Application Layer Guidelines, Layer 1-6 Guidelines, and External Interface File (XIF) Reference Guide
LonMark Resource Files	(available at www.lonmark.org), including Standard Network Variable Type (SNVT) definitions
Metal Building Man	nufacturers Association (MBMA)
	Metal Building Systems Manual
Midwest Insulation	Contractors Association (MICA)
	National Commercial and Industrial Insulation Standards Manual
National Association	on of Corrosion Engineers International (NACE)
NACE RP0169	Control of External Corrosion on Underground or Submerged Metallic Piping Systems
NACE RP0185	Extruded, Polyolefin Resin Coating Systems with Adhesives for Underground or Submerged Pipe
NACE RP0285	Corrosion Control of Underground Storage Tank Systems by Cathodic Protection
NACE RP0286	Electrical Isolation of Cathodically Protected Pipelines
National Electrical	Manufacturers Association (NEMA)
National Environme	ental Balancing Bureau (NEBB)
	Procedural Standards Procedural Standards for Testing Adjusting Balancing of Environmental Systems
National Fire Prote	ction Association (NFPA)
NFPA 10	Standard for Portable Fire Extinguishers
NFPA 13	Installation of Sprinkler Systems
NFPA 13R	Residential Occupancies up to and Including Four Stories in Height Sprinkler Systems

NFPA 14	Standard for the Installation of Standpipes and Hose Systems
NFPA 20	Installation of Centrifugal Fire Pumps
NFPA 24 NFPA 25	Standard for the Installation of Private Fire Service Mains and Their Appurtenances [underground fire protection system design] Inspection, Testing And Maintenance Of Water-Based Fire Protection Systems
NFPA 30	Flammable and Combustible Liquids Code
NFPA 30A	Motor Fuel Dispensing Facilities and Repair Garages
NFPA 31	Installation of Oil Burning Equipment
NFPA 54	National Fuel Gas Code
NFPA 58	Liquefied Petroleum Gas Code
NFPA 70	National Electrical Code
NFPA 72	National Fire Alarm Code
NFPA 76	Fire Protection of Telecommunications Facilities
NFPA 80	Standard for Fire Doors and Fire Windows
NFPA 90a	Installation of Air Conditioning and Ventilating Systems
NFPA 96	Standard for Ventilation Control and Fire Protection of Commercial Cooking Operations
NFPA 101	Life Safety Code
NFPA 780	Standard for the Installation of Lightning Protection Systems
National Roofing Contractor's Association (NRCA)	
	Roofing and Waterproofing Manual
National Sanitation Foundation, International	
NSF/ANSI Std. 2, 3, 4, 5, 6, 7, 8, 12, 13, 18, 20, 21, 25, 29, 35, 36, 37, 51, 52, 59,	Food Equipment Standards

Section: 01 10 00 [Not Supplied]
Page 34 of 151

169	
ANSI/UL Std. 73, 197, 471, 621, 763	Food Equipment Standards
CSA Std. C22.2 No. 109, 120, 195	Food Equipment Standards
Occupational Safety	and Health Administration (OSHA)
Title 29, Part 1926	OSHA Construction Industry Standards, Title 29, Code of Federal Regulations, Part 1926, Safety and Health Regulations for Construction
Plumbing and Drain	age Institute (PDI)
PDI G 101	Testing and Rating Procedure for Grease Interceptors with Appendix of Sizing and Installation Data
PDI WH201	Water Hammer Arrestors
Precast Concrete Ins	stitute
PCI Design Handbook	Precast and Prestressed Concrete
Sheet Metal and Air	Conditioning Contractor's National Association (SMACNA)
SMACNA HVAC Duct Construction Standards	HVAC Duct Construction Standards - Metal and Flexible
SMACNA Architectural Manual	Architectural Sheet Metal Manual
SMACNA HVAC TAB	HVAC Systems - Testing, Adjusting and Balancing
State/Local Regulations	
	State Department of Transportation Standard Specifications for Highway and Bridge Construction
	Sedimentation and Erosion Control Design Requirements
	Environmental Control Requirements
	Storm Water Management Requirements
Steel Door Institute ((SDI)

Section: 01 10 00 [Not Supplied]
Page 35 of 151

ANSI A250.8/SDI 100	Standard Steel Doors and Frames
Steel Deck Institute	
	SDI Diaphragm Design Manual
Steel Joist Institute	
	Catalog of Standard Specifications and Load Tables for Steel Joists and Joist Girders
Underwriters Labora	tories (UL)
UL 96A	Installation Requirements for Lightning Protection Systems
UL 300	Standard for Safety for Fire Testing of Fire Extinguishing Systems for Protection of Restaurant Cooking Areas
UNITED STATES ACC	CESS BOARD: U.S. ARCHITECTURAL AND TRANSPORTATION ANCE BOARD
ADA and ABA Accessibility Guidelines for Buildings and Facilities	ABA Accessibility Standard for DoD Facilities Derived from the ADA and ABA Accessibility Guidelines: Specifically includes: ABA Chapters 1 and 2 and Chapters 3 through 10. Use this reference in lieu of IBC Chapter 11. Excluded are: (a) Facilities, or portions of facilities, on a military installation that are designed and constructed for use exclusively by able-bodied military personnel (See Paragraph 3 for any reference to this exclusion). (b) Reserve and National Guard facilities, or portions of such facilities, owned by or under the control of the Department of Defense, that are designed and constructed for use exclusively by able-bodied military personnel. (See paragraph 3 for any reference to this exclusion).
U.S. DEPARTMENT OF HEALTH AND HUMAN SERVICES	
	FDA National Food Code
U.S. GREEN BUILDING COUNCIL (USGBC)	
LEED-NC	Green Building Rating System for New Construction & Major Renovations
	Application Guide for Multiple Buildings and On-Campus Building Projects

4.2. MILITARY CRITERIA

Section: 01 10 00 [Not Supplied]
Page 36 of 151

The project shall conform to the following criteria. Certain design impacts and features due to these criteria are noted for the benefit of the offeror. However, all requirements of the referenced criteria will be applicable, whether noted or not, unless otherwise specified herein.

- 4.2.1. Energy Policy Act of 2005 (Public Law 109-58) (applies only to the extent specifically implemented in the contract, which may or may not directly cite or reference EPACT)
- 4.2.2. Executive Order 12770: Metric Usage In Federal Government
- (a) Metric design and construction is required except when it increases construction cost. Offeror to determine most cost efficient system of measurement to be used for the project.
- 4.2.3. TB MED 530: Occupational and Environmental Health Food Sanitation
- 4.2.4. Unified Facilities Criteria (UFC) 3-410-01FA: Heating, Ventilating, and Air Conditioning applicable only to the extent specified in paragraph 5, herein.
- 4.2.5. Deleted.
- 4.2.6. UFC 3-600-01 Design: Fire Protection Engineering for Facilities. Use the latest edition of the IBC in coordination with this UFC. Use Chapters 3, 6, 7, 33 and UFC 3-600-01. If any conflict occurs between these Chapters and UFC 3-600-01, the requirements of UFC 3-600-01 take precedence. Use UFC 3-600-01 in lieu of IBC Chapters 4, 8,9,10.
- 4.2.7. UFC 4-010-01 DoD Minimum Antiterrorism Standards for Buildings
- 4.2.8. UFC 4-023-03 Design of Buildings to Resist Progressive Collapse (Use most recent version, regardless of references thereto in other publications)
- (a) Note the option to use tie force method or alternate path design for Occupancy Category II.
- 4.2.9. UFC 4-021-01 Design and O&M: Mass Notification Systems
- 4.2.10. Technical Criteria for Installation Information Infrastructure Architecture (I3A)
- (a) Email: <u>DetrickISECI3Aguide@conus.army.mil</u>
- 4.2.11. <u>U.S. Army Information Systems Engineering Command (USAISEC)</u> TG for the Integration of SECRET Internet Protocol (IP) Router Network (SIPRNET). See Paragraph 3 for applicability to specific facility type. May not apply to every facility. This is mandatory criteria for those facilities with SIPRNET.

Section: 01 10 00 [Not Supplied]
Page 37 of 151

5.0 GENERAL TECHNICAL REQUIREMENTS

This paragraph contains general technical requirements. See also Paragraph 3 for facility-specific technical requirements. Residential or similar grade finishes and materials are not acceptable for inclusion in these buildings, unless otherwise specifically allowed.

5.1. SITE PLANNING AND DESIGN

- 5.1.1. STANDARDS AND CODES: The site planning and design shall conform to APPLICABLE CRITERIA and to paragraph 6, PROJECT SPECIFIC REQUIREMENTS.
- 5.1.2. SITE PLANNING OBJECTIVES: Group buildings in configurations that create a sense of community and promote pedestrian use. See paragraph 3 for additional site planning requirements relating to building functions.
- 5.1.2.1. Provide enclosures and or visual screening devices for Outdoor Utility such as dumpsters, emergency generators, transformers, heating, ventilation, and air conditioning units from streetscape and courtyard views to limit visual impact. Enclosures shall be compatible with the building they serve and accessible by vehicle. The location of dumpsters can have a significant visual impact and should be addressed as part of an overall building design and incorporated in site planning.
- 5.1.2.2. Where included in the project, dumpster pads shall be concrete (minimum of 8 inches thick on 4 inch base course, unless site conditions dictate more conservative requirements) and directly accessible by way of a paved service drive or parking lot with adequate overhead clearance for collection vehicles. Provide space at dumpster areas for recycling receptacles. Coordinate with Installation on recycling receptacle types, sizes and access requirements and provide space at dumpster areas to accommodate them.
- 5.1.2.3. Vehicular Circulation. Apply design vehicle templates provided by the American Association of State Highway and Transportation Officials (AASHTO) to the site design. The passenger car class includes passenger cars and light trucks, such as vans and pick-ups. The passenger car template is equivalent to the non-organizational privately owned vehicle (POV). The truck class template includes single-unit trucks, recreation vehicles, buses, truck tractor-semi-trailer combinations, and trucks or truck tractors with semi-trailers in combination with full trailers. Provide vehicle clearances required to meet traffic safety for emergency vehicles, service vehicles, and moving vans. Provide required traffic control signage Site entrances and site drive aisles shall maximize spacing between drives, incorporate right-angle turns, and limit points of conflict between traffic. Design Services Drives to restrict access to unauthorized vehicles by removable bollards, gates, or other barriers to meet Anti-Terrorism/Force Protection (ATFP) requirements. Orient service drives to building entrances other than the primary pedestrian entry at the front of the building.
- 5.1.2.4. Provide Emergency Vehicle Access around the facility and shall be in accordance with AT/FP requirements. Maintain a 33-foot clear zone buffer for emergency vehicles, designed to prevent other vehicles from entering the AT/FP standoff to the building.
- 5.1.2.5. Clear and grub all trees and vegetation necessary for construction; but, save as many trees as possible. Protect trees to be saved during the construction process from equipment.
- 5.1.2.6. Stormwater Management. Employ design and construction strategies (Best Management Practices) that reduce stormwater runoff, reduce discharges of polluted water offsite and maintain or restore predevelopment hydrology with respect to temperature, rate, volume and duration of flow to the maximum extent practicable. See paragraph 6, PROJECT SPECIFIC requirements for additional information.
- 5.1.3. EXTERIOR SIGNAGE: Provide exterior signage in accordance with Appendix H, Exterior Signage. Provide exterior NO SMOKING signage that conveys building and grounds smoking policy.
- 5.1.4. EXISTING UTILITIES: Base utilities maps and capacities for this site are included as part of this RFP. See paragraph 6 for more detailed information.

5.2. SITE ENGINEERING

Section: 01 10 00 [Not Supplied]
Page 38 of 151

5.2.1. STANDARDS AND CODES: The site engineering shall conform to APPLICABLE CRITERIA.

5.2.2. SOILS:

- 5.2.2.1. A report has been prepared to characterize the subsurface conditions at the project site and is **appended to these specifications**. The report provides a general overview of the soil and geologic conditions with detailed descriptions at discrete boring locations. The Contractor's team shall include a licensed geotechnical engineer to interpret the report and develop earthwork and foundation recommendations and design parameters in which to base the contractor's design. If any additional subsurface investigation or laboratory analysis is required to better characterize the site or develop the final design, the Contractor shall perform it under the direction of a licensed geotechnical engineer. There will be no separate payment for the cost of additional tests. If differences between the Contractor's additional subsurface investigation and the government provided soils report or the reasonably expected conditions require material revisions in the design, an equitable adjustment may be made, in accordance with the provisions of the Differing Site Conditions clause. The basis for the adjustment would be the design and construction appropriate for the conditions described in the Government furnished report or the reasonably expected conditions, in comparison with any changes required by material differences in the actual conditions encountered, in accordance with the terms of contract clause Differing Site Conditions.
- 5.2.2.2. The contractor's licensed geotechnical engineer shall prepare a final geotechnical evaluation report, to be submitted along with the first foundation design submittal, as described in Section 01 33 16, *Design After Award*.
- 5.2.3. VEHICLE PAVEMENTS: (as applicable to the project)
- 5.2.3.1. Design procedures and materials shall conform to one of the following: 1) the USACE Pavement Transportation Computer Assisted Structural Engineering (PCASE) program, 2) American Association of State Highway and Transportation Officials (AASHTO) or, 3) the applicable state Department of Transportation standards in which the project is located. See paragraph 5.2.2.2 and Section 01 33 16 for required information for the Contractor's geotechnical evaluation report. The minimum flexible pavement section shall consist of 2 inches of asphalt and 6 inches of base or as required by the pavement design, whichever is greater, unless specifically identified by the Government to be a gravel road. Design roads and parking areas for a life expectance of 25 years with normal maintenance. Parking area for tactical vehicles (as applicable to the project) shall be Portland Cement Concrete (PCC) rigid pavement design. For concrete pavements, submit joint layout plan for review and concurrence. Design pavements for military tracked vehicles (as applicable to the project) IAW USACE PCASE. Traffic estimates for each roadway area will be as shown on the drawings or listed in Section 01 10 00 Paragraph 6.4.4. Pavement markings and traffic signage shall comply with the Installation requirements and with the Manual on Uniform Traffic Control Devices.
- 5.2.3.2. Parking Requirements.
- (a) All handicap POV parking lots (where applicable in the facility specific requirements) shall meet the ADA and ABA Accessibility Guidelines for accessible parking spaces.
- (b) Design POV parking spaces for the type of vehicles anticipated, but shall be a minimum of 9 ft by 18 ft for POVs, except for two wheel vehicles.
- 5.2.3.3. Sidewalks. Design the network of walks throughout the complex (where applicable) to facilitate pedestrian traffic among facilities, and minimize the need to use vehicles. Incorporate sidewalks to enhance the appearance of the site development, while creating a sense of entry at the primary patron entrances to the buildings. Minimum sidewalk requirements are in Paragraph 3, where applicable.
- 5.2.4. CATHODIC PROTECTION: Provide cathodic protection systems for all underground metallic systems and metallic fittings/portions of non-metallic, underground systems, both inside and outside the building 5 foot line that are subject to corrosion. Coordinate final solutions with the installation to insure an approach that is consistent with installation cathodic protection programs.
- 5.2.5. UTILITIES: See paragraph 6.4.6 for specific information on ownership of utilities and utility requirements. Meter all utilities (gas, water, and electric, as applicable) to each facility. For Government owned utilities, install meters that are wireless data transmission capable as well as have a continuous manual reading option. All meters will be capable of at least hourly data logging and transmission and provide consumption data for gas, water, and electricity. Gas and electric meters will also provide demand readings based on consumption over a maximum of

Section: 01 10 00 [Not Supplied]
Page 39 of 151

any 15 minute period. Configure all meters to transmit at least daily even if no receiver for the data is currently available at the time of project acceptance. For privatized utilities, coordinate with the privatization utility(ies) for the proper meter base and meter installation.

- 5.2.6. PERMITS: The CONTRACTOR shall be responsible for obtaining all permits (local, state and federal) required for design and construction of all site features and utilities.
- 5.2.7. IRRIGATION. Landscape irrigation systems, if provided, shall comply with the following:
- 5.2.7.1. Irrigation Potable Water Use Reduction. Reduce irrigation potable water use by 100 percent using LEED credit WE1.1 baseline (no potable water used for irrigation), except where precluded by other project requirements.
- 5.2.8. EPA WaterSense Products and Contractors. Except where precluded by other project requirements, use EPA WaterSense labeled products and irrigation contractors that are certified through a WaterSense labeled program where available.
- 5.3. ARCHITECTURE AND INTERIOR DESIGN:

This element will be evaluated per APPLICABLE CRITERIA under the quality focus.

- 5.3.1. STANDARDS AND CODES: The architecture and interior design shall conform to APPLICABLE CRITERIA.
- 5.3.2. GENERAL: Overall architectural goal is to provide a functional, quality, visually appealing facility that is a source of pride for the installation and delivered within the available budget and schedule.
- 5.3.3. COMPUTATION OF AREAS: See APPENDIX Q for how to compute gross and net areas of the facility(ies).
- 5.3.4. BUILDING EXTERIOR: Design buildings to enhance or compliment the visual environment of the Installation. Where appropriate, reflect a human scale to the facility. Building entrance should be architecturally defined and easily seen. When practical, exterior materials, roof forms, and detailing shall be compatible with the surrounding development and adjacent buildings on the Installation and follow locally established architectural themes. Use durable materials that are easy to maintain. Exterior colors shall conform to the Installation requirements. See paragraph 6.
- 5.3.4.1. Building Numbers: Each building shall have exterior signage permanently attached on two faces of the building indicating the assigned building number or address. Building number signage details and locations shall conform to Appendix H, Exterior Signage.

5.3.5. BUILDING INTERIOR

- 5.3.5.1. Space Configuration: Arrange spaces in an efficient and functional manner in accordance with area adjacency matrices.
- 5.3.5.2. Surfaces: Appearance retention is the top priority for building and furniture related finishes. Provide low maintenance, easily cleaned room finishes that are commercially standard for the facility occupancy specified, unless noted otherwise.
- 5.3.5.3. Color: The color, texture and pattern selections for the finishes of the building shall provide an aesthetically pleasing, comfortable, easily maintainable and functional environment for the occupants. Coordination of the building colors and finishes is necessary for a cohesive design. Color selections shall be appropriate for the building type. The use of color, texture and pattern shall be used to path or way find through the building. Trendy colors that will become dated shall be limited to non-permanent finishes such as carpet and paint. Finishes should be selected with regards to aesthetics, maintenance, durability, life safety and image. Limit the number of similar colors for each material. Color of Ceramic and porcelain tile grout shall be medium range color to help hide soiling. Plastic laminate and solid surface materials shall have patterns that are mottled, flecked or speckled. Finish colors of fire extinguisher cabinets, receptacle bodies and plates, fire alarms / warning lights, emergency lighting, and other miscellaneous items shall be coordinated with the building interior. Color of equipment items on ceilings (speakers, smoke detectors, grills, etc.) shall match the ceiling color.

Section: 01 10 00 [Not Supplied]
Page 40 of 151

- 5.3.5.4. Circulation: Circulation schemes must support easy way finding within the building.
- 5.3.5.5. Signage: Provide interior signage for overall way finding and life safety requirements. A comprehensive interior plan shall be from one manufacturer. Include the following sign types: (1) Lobby Directory, (2) Directional Signs; (3) Room Identification Signs; (4) Building Service Signs; (5) Regulatory Signs; (6) Official and Unofficial Signs (7) Visual Communication Boards (8) NO SMOKING signage that conveys building smoking policy. Use of emblems or logos may also be incorporated into the signage plan.
- 5.3.5.6. Window Treatment: Interior window treatments with adjustable control shall be provided in all exterior window locations for control of day light coming in windows or privacy at night. Uniformity of treatment color and material shall be maintained to the maximum extent possible within a building.

5.3.6. COMPREHENSIVE INTERIOR DESIGN

5.3.6.1. Comprehensive Interior Design includes the integration of a Structural Interior Design (SID) and a Furniture, Fixtures and Equipment (FF&E) design and package. SID requires the design, selection and coordination of interior finish materials that are integral to or attached to the building structure. Completion of a SID involves the selection and specification of applied finishes for the building's interior features including, but not limited to, walls, floors, ceilings, trims, doors, windows, window treatments, built-in furnishings and installed equipment, lighting, and signage. The SID package includes finish schedules, finish samples and any supporting interior elevations, details or plans necessary to communicate the building finish design and build out. The SID also provides basic space planning for the anticipated FF&E requirements in conjunction with the functional layout of the building and design issues such as life safety, privacy, acoustics, lighting, ventilation, and accessibility. See Section 01 33 16 for SID design procedures.

The FF&E design and package includes the design, selection, color coordination and of the required furnishing items necessary to meet the functional, operational, sustainability, and aesthetic needs of the facility coordinated with the interior finish materials in the SID. The FF&E package includes the specification, procurement documentation, placement plans, ordering and finish information on all freestanding furnishings and accessories, and a cost estimate. Coordinate the selection of furniture style, function and configuration with the defined requirements. Examples of FF&E items include, but are not limited to workstations, seating, files, tables, beds, wardrobes, draperies and accessories as well as marker boards, tack boards, and presentation screens. Criteria for furniture selection include function and ergonomics, maintenance, durability, sustainability, comfort and cost. See Section 01 33 16 for FFE design procedures.

5.4. STRUCTURAL DESIGN

- 5.4.1. STANDARDS AND CODES: The structural design shall conform to APPLICABLE CRITERIA.
- GENERAL: The structural system needs to be compatible with the intended functions and components that allows for future flexibility and reconfigurations of the interior space. Select an economical structural system based upon facility size, projected load requirements and local availability of materials and labor. Base the structural design on accurate, site specific geotechnical information and anticipated loads for the building types and geographical location. Consider climate conditions, high humidity, industrial atmosphere, saltwater exposure, or other adverse conditions when selecting the type of cement and admixtures used in concrete, the concrete cover on reinforcing steel, the coatings on structural members, expansion joints, the level of corrosion protection, and the structural systems. Analyze, design and detail each building as a complete structural system. Design structural elements to preclude damage to finishes, partitions and other frangible, non-structural elements to prevent impaired operability of moveable components; and to prevent cladding leakage and roof ponding. Limit deflections of structural members to the allowable of the applicable material standard, e.g., ACI, AISC, Brick Industry Association, etc. When modular units or other pre-fabricated construction is used or combined with stick-built construction, fully coordinate and integrate the overall structural design between the two different or interfacing construction types. If the state that the project is located in requires separate, specific licensing for structural engineers (for instance, such as in Florida, California and others), then the structural engineer designer of record must be registered in that state.
- 5.4.3. LOADS: See paragraph 3 for facility specific (if applicable) and paragraph 6 for site and project specific structural loading criteria. Unless otherwise specified in paragraph 6, use Exposure Category C for wind. If not specified, use Category C unless the Designer of Record can satisfactorily justify another Exposure Category in its

Section: 01 10 00 [Not Supplied]
Page 41 of 151

design analysis based on the facility Master Plan. Submit such exceptions for approval as early as possible and prior to the Interim Design Submittal in Section "Design After Award". In addition to gravity, seismic and lateral loads, design the ancillary building items, e.g. doors, window jambs and connections, overhead architectural features, equipment bracing, for the requirements of UFC 4-010-01, DOD Minimum Antiterrorism Standards for Buildings. Ensure and document that the design of glazed items includes, but is not limited to, the following items under the design loads prescribed in UFC 4-010-01:

- (a) Supporting members of glazed elements, e.g. window jamb, sill, header
- (b) Connections of glazed element to supporting members, e.g. window to header
- (c) Connections of supporting members to each other, e.g. header to jamb
- (d) Connections of supporting members to structural system, e.g. jamb to foundation.
- 5.4.4. TERMITE TREATMENT: (Except Alaska) Provide termite prevention treatment in accordance with Installation and local building code requirements, using licensed chemicals and licensed applicator firm.
- 5.5. THERMAL PERFORMANCE
- 5.5.1. STANDARDS AND CODES: Building construction and thermal insulation for mechanical systems shall conform to APPLICABLE CRITERIA.
- 5.5.2. BUILDING ENVELOPE SEALING PERFORMANCE REQUIREMENT. Design and construct the building envelope for office buildings, office portions of mixed office and open space (e.g., company operations facilities), dining, barracks and instructional/training facilities with a continuous air barrier to control air leakage into, or out of, the conditioned space. Clearly identify all air barrier components of each envelope assembly on construction documents and detail the joints, interconnections and penetrations of the air barrier components. Clearly identify the boundary limits of the building air barriers, and of the zone or zones to be tested for building air tightness on the drawings.
- 5.5.2.1. Trace a continuous plane of air-tightness throughout the building envelope and make flexible and seal all moving joints.
- 5.5.2.2. The air barrier material(s) must have an air permeance not to exceed 0.004~cfm / sf at 0.3" wg (0.02~L/s.m2 @ 75 Pa) when tested in accordance with ASTM E 2178
- 5.5.2.3. Join and seal the air barrier material of each assembly in a flexible manner to the air barrier material of adjacent assemblies, allowing for the relative movement of these assemblies and components.
- 5.5.2.4. Support the air barrier so as to withstand the maximum positive and negative air pressure to be placed on the building without displacement, or damage, and transfer the load to the structure.
- 5.5.2.5. Seal all penetrations of the air barrier. If any unavoidable penetrations of the air barrier by electrical boxes, plumbing fixture boxes, and other assemblies are not airtight, make them airtight by sealing the assembly and the interface between the assembly and the air barrier or by extending the air barrier over the assembly.
- 5.5.2.6. The air barrier must be durable to last the anticipated service life of the assembly.
- 5.5.2.7. Do not install lighting fixtures with ventilation holes through the air barrier
- 5.5.2.8. Provide a motorized damper in the closed position and connected to the fire alarm system to open on call and fail in the open position for any fixed open louvers such as at elevator shafts.
- 5.5.2.9. Damper and control to close all ventilation or make-up air intakes and exhausts, atrium smoke exhausts and intakes, etc when leakage can occur during inactive periods.
- 5.5.2.10. Compartmentalize garages under buildings by providing air-tight vestibules at building access points.

Section: 01 10 00 [Not Supplied]
Page 42 of 151

5.5.2.11. Compartmentalize spaces under negative pressure such as boiler rooms and provide make-up air for combustion.

- 5.5.2.12. Performance Criteria and Substantiation: Submit the qualifications and experience of the testing entity for approval. Demonstrate performance of the continuous air barrier for the opaque building envelope by the following tests:
- (a) Test the completed building and demonstrate that the air leakage rate of the building envelope does not exceed 0.25cfm/ft2 at a pressure differential of 0.3" w.g.(75 Pa) in accordance with ASTM's E 779 (2003) or E-1827-96 (2002). Accomplish tests using either pressurization or depressurization or both. Divide the volume of air leakage in cfm @ 0.3" w.g. (L/s @ 75 Pa) by the area of the pressure boundary of the building, including roof or ceiling, walls and floor to produce the air leakage rate in cfm/ft2 @ 0.3" w.g. (L/s.m2 @ 75 Pa). Do not test the building until verifying that the continuous air barrier is in place and installed without failures in accordance with installation instructions so that repairs to the continuous air barrier, if needed to comply with the required air leakage rate, can be done in a timely manner.
- (b) Test the completed building using Infrared Thermography testing. Use infrared cameras with a resolution of 0.1deg C or better. Perform testing on the building envelope in accordance with ISO 6781:1983 and ASTM C1060-90(1997). Determine air leakage pathways using ASTM E 1186-03 Standard Practices for Air Leakage Site Detection in Building Envelopes and Air Barrier Systems, and perform corrective work as necessary to achieve the whole building air leakage rate specified in (a) above.
- (c) Notify the Government at least three working days prior to the tests to provide the Government the opportunity to witness the tests. Provide the Government written test results confirming the results of all tests.
- 5.6. PLUMBING
- 5.6.1. STANDARDS AND CODES: The plumbing system shall conform to APPLICABLE CRITERIA.
- 5.6.2. PRECAUTIONS FOR EXPANSIVE SOILS: Where expansive soils are present, the design for underslab piping systems and underground piping serving chillers, cooling towers, etc, shall include features to control forces resulting from soil heave. Some possible solutions include, but are not necessarily limited to, features such as flexible expansion joints, slip joints, horizontal offsets with ball joints, or multiple bell and spigot gasketed fittings. For structurally supported slabs, piping should be suspended from the structure with adequate space provided below the pipe for the anticipated soil movement.
- 5.6.3. HOT WATER SYSTEMS: For Hot Water heating and supply, provide a minimum temp of 140 Deg F in the storage tank and a maximum of 110 Deg F at the fixture, unless specific appliances or equipment specifically require higher temperature water supply.
- 5.6.4. SIZING HOT WATER SYSTEMS: Unless otherwise specified or directed in paragraph 3, design in accordance with ASHRAE Handbook Series (appropriate Chapters), ASHRAE Standard 90.1, and the energy conservation requirements of the contract. Size and place equipment so that it is easily accessible and removable for repair or replacement.
- 5.6.5. JANITOR CLOSETS: In janitor spaces/room/closets, provide at minimum, a service sink with heavy duty shelf and wall hung mop and broom rack(s).
- 5.6.6. FLOOR DRAINS: As a minimum, provide floor drains in mechanical rooms and areas, janitor spaces/rooms/closets and any other area that requires drainage from fixtures or equipment, drain downs, condensate, as necessary.
- 5.6.7. URINALS: Urinals shall be vitreous china, wall-mounted, wall outlet, non-water using, with integral drain line connection, and with sealed replaceable cartridge or integral liquid seal trap. Either type shall use a biodegradable liquid to provide the seal and maintain a sanitary and odor-free environment. Install, test and maintain in accordance with manufacturer's recommendations. Slope the sanitary sewer branch line for non-water use urinals a minimum of 1/4 inch per foot. Do not use copper tube or pipe for drain lines that connect to the urinal. Manufacturer shall provide an operating manual and on-site training to installation operations personnel for the proper care and maintenance of the urinal. For complexes, non-water using urinals are not required for barracks type spaces.

Section: 01 10 00 [Not Supplied]
Page 43 of 151

5.6.8. BUILDING WATER USE REDUCTION. Reduce building potable water use in each building 30 percent using IPC fixture performance requirements baseline.

- 5.6.9. Do not use engineered vent or Sovent® type drainage systems.
- 5.6.10. Where the seasonal design temperature of the cold water entering a building is below the seasonal design dew point of the indoor ambient air, and where condensate drip will cause damage or create a hazard, insulate plumbing piping with a vapor barrier type of insulation to prevent condensation. Do not locate water or drainage piping over electrical wiring or equipment unless adequate protection against water (including condensation) damage is provided. Insulation alone is not adequate protection against condensation. Follow ASHRAE Fundamentals Chapter 23, Insulation for Mechanical Systems, IMC paragraph 1107 and International Energy Conservation Code for pipe insulation requirements.
- 5.7. ELECTRICAL AND TELECOMMUNICATIONS SYSTEMS
- 5.7.1. STANDARDS AND CODES: The electrical systems for all facilities shall conform to APPLICABLE CRITERIA.
- 5.7.2. MATERIALS AND EQUIPMENT: Materials, equipment and devices shall, as a minimum, meet the requirements of Underwriters Laboratories (UL) where UL standards are established for those items. Wiring for branch circuits shall be copper. Motors larger than one-half horsepower shall be three phase. All electrical systems shall be pre-wired and fully operational unless otherwise indicated. Wall mounted electrical devices (power receptacles, communication outlets and CATV outlets) shall have matching colors, mounting heights and faceplates.
- 5.7.3. POWER SERVICE: Primary service from the base electrical distribution system to the pad-mounted transformer and secondary service from the transformer to the building service electrical equipment room shall be underground. See paragraph 6 for additional site electrical requirements.
- 5.7.3.1. Spare Capacity: Provide 10% space for future circuit breakers in all panelboards serving residential areas of buildings and 15% spaces in all other panelboards.
- 5.7.4. TELECOMMUNICATION SERVICE: The project's facilities must connect to the Installation telecommunications (voice and data) system through the outside plant (OSP) telecommunications underground infrastructure cabling system per the I3A Criteria. Connect to the OSP cabling system from each facility main cross connect located in the telecommunications room.
- 5.7.5. LIGHTING: Comply with the recommendations of the Illumination Engineering Society of North America (IESNA), the National Energy Policy Act and Energy Star requirements for lighting products..
- 5.7.5.1. Interior Lighting:
- (a) Reflective Surfaces: Coordinate interior architectural space surfaces and colors with the lighting systems to provide the most energy-efficient workable combinations.
- (b) High Efficiency Fluorescent Lighting: Utilize NEMA premium electronic ballasts and energy efficient fluorescent lamps with a Correlated Color Temperature (CCT) of 4100K. Linear fluorescent and compact fluorescent fixtures shall have a Color Rendering Index of (CRI) of 87 or higher. Fluorescent lamps shall be the low mercury type qualifying as non-hazardous waste upon disposal. Do not use surface mounted fixtures on acoustical tile ceilings. Provide an un-switched fixture with emergency ballast shall be provided at each entrance to the building.
- (c) Solid State Lighting: Fixtures shall provide lighting with a minimum Correlated Color Temperature (CCT) of 4100K and shall have a Color Rendering Index of (CRI) of 75 or higher. Verify performance of the light producing solid state components by a test report in compliance with the requirements of IESNA LM 80. Verify performance of the solid state light fixtures by a test report in compliance with the requirements of IESNA LM 79. Provide lab results by a NVLAP certified laboratory. The light producing solid state components and drivers shall have a life expectancy of 50,000 operating hours while maintaining at least 70% of original illumination level. Provide a complete five year warranty for fixtures.

Section: 01 10 00 [Not Supplied]
Page 44 of 151

(d) Metal Halide Lighting (where applicable): Metal Halide lamp fixtures in the range of 150-500 Watts shall be pulse start type and have a minimum efficiency rating of 88%.

- (e) Lighting Controls: ANSI/ASHRAE/IESNA 90.1 has specific lighting controls requirements. Provide a high level of lighting system control by individual occupants or by specific groups in multi-occupant spaces (classrooms, conference rooms) to promote the productivity, comfort and well being of the building occupants. In office spaces, the preferred lighting should be a 30 FC ambient lighting level with occupancy sensor controlled task lighting in the work spaces to provide a composite lighting level of 50 FC on the working surfaces. Consider incorporating daylighting techniques for the benefit of reducing lighting energy requirements while improving the quality of the indoor spaces. If daylight strategies are used, additional coordination is required with the architect and mechanical engineer. Additionally, incorporate electric lighting controls to take advantage of the potential energy savings.
- (f) Exterior Lighting: See paragraph 6.9 for site specific information, if any, on exterior lighting systems. Minimize light pollution and light trespass by not over lighting and use <u>cutoff type</u> exterior luminaries.
- 5.7.6. TELECOMMUNICATION SYSTEM: All building telecommunications cabling systems (BCS) and OSP telecommunications cabling system shall conform to APPLICABLE CRITERIA to include I3A Technical Criteria. An acceptable BCS encompasses, but is not limited to, copper and fiber optic (FO) entrance cable, termination equipment, copper and fiber backbone cable, copper and fiber horizontal distribution cable, workstation outlets, racks, cable management, patch panels, cable tray, cable ladder, conduits, grounding, and labeling.. Items included under OSP infrastructure encompass, but are not limited to, manhole and duct infrastructure, copper cable, fiber optic cable, cross connects, terminations, cable vaults, and copper and FO entrance cable.
- 5.7.6.1. Design, install, label and test all telecommunications systems in accordance with the I3A Criteria and ANSI/TIA/EIA 568, 569, and 606 standards. A Building Industry Consulting Services International (BICSI) Registered Communications Distribution Designer (RCDD) with at least 2 yrs related experience shall develop and stamp telecommunications design, and prepare the test plan. See paragraph 5.8.2.5 for design of environmental systems for Telecommunications Rooms.
- 5.7.6.2. The installers assigned to the installation of the telecommunications system or any of its components shall be regularly and professionally engaged in the business of the application, installation and testing of the specified telecommunications systems and equipment. Key personnel; i.e., supervisors and lead installers assigned to the installation of this system or any of its components shall be BICSI Registered Cabling Installers, Technician Level. Submit documentation of current BICSI certification for each of the key personnel. In lieu of BICSI certification, supervisors and installers shall have a minimum of 5 years experience in the installation of the specified copper and fiber optic cable and components. They shall have factory or factory approved certification from each equipment manufacturer indicating that they are qualified to install and test the provided products.
- 5.7.6.3. Perform a comprehensive end to end test of all circuits to include all copper and fiber optic cables upon completion of the BCS and prior to acceptance of the facility. The BCS circuits include but are not limited to all copper and fiber optic(FO) entrance cables, termination equipment, copper and fiber backbone cable, copper and fiber horizontal distribution cable, and workstation outlets. Test in accordance with ANSI/EIA/TIA 568 standards. Use test instrumentation that meets or exceeds the standard. Submit the official test report to include test procedures, parameters tested, values, discrepancies and corrective actions in electronic format. Test and accomplish all necessary corrective actions to ensure that the government receives a fully operational, standards based, code compliant telecommunications system.
- 5.7.7. LIGHTNING PROTECTION SYSTEM: Provide a lightning protection system where recommended by the Lightning Risk Assessment of NFPA 780, Annex L.
- 5.8. HEATING, VENTILATING, AND AIR CONDITIONING
- 5.8.1. STANDARDS AND CODES: The HVAC system shall conform to APPLICABLE CRITERIA.
- 5.8.2. DESIGN CONDITIONS.
- 5.8.2.1. Outdoor and indoor design conditions shall be in accordance with UFC 3-410-01FA. Outdoor air and exhaust ventilation requirements for indoor air quality shall be in accordance with ASHRAE 62.1. All Buildings with minimum LEED Silver requirement (or better) will earn LEED Credit EQ 7.1, Thermal Comfort-Design.

Section: 01 10 00 [Not Supplied]
Page 45 of 151

5.8.2.2. Design systems in geographical areas that meet the definition for high humidity in UFC 3-410-01FA in accordance with the special criteria for humid areas therein.

- 5.8.2.3. Cooling equipment may be oversized by up to 15 percent to account for recovery from night setforward. Heating equipment may be oversized by up to 30 percent to account for recovery from night setback. Design single zone systems and multi-zone systems to maintain an indoor design condition of 50% relative humidity for cooling only. For heating only where the indoor relative humidity is expected to fall below 20% for extended periods, add humidification to increase the indoor relative humidity to 30%. Provide ventilation air from a separate dedicated air handling unit (DOAU) for facilities using multiple single zone fan-coil type HVAC systems. Do not condition outside air through fan coil units. Avoid the use of direct expansion cooling coils in air handling units with constant running fans that handle outside air.
- 5.8.2.4. Locate all equipment so that service, adjustment and replacement of controls or internal components are readily accessible for easy maintenance.
- 5.8.2.5. Environmental Requirements for Telecommunications Rooms, (including SIPRNET ROOMS, where applicable for specific facility type). Comply with ANSI/EIA/TIA 569 and the I3A.
- 5.8.2.6. Fire dampers: dynamic type with a dynamic rating suitable for the maximum air velocity and pressure differential to which the damper is subjected. Test each fire damper with the air handling and distribution system running.
- 5.8.3. BUILDING AUTOMATION SYSTEM. Provide a Building Automation System consisting of a building control network, and integrate the building control network into the UMCS as specified.

The building control network shall be a single complete non-proprietary Direct Digital Control (DDC) system for control of the heating, ventilating and air conditioning (HVAC) systems as specified herein. The building control network shall be an Open implementation of LonWorks® technology using ANSI/EIA 709.1B as the only communications protocol and use only LonMark Standard Network Variable Types (SNVTs), as defined in the LonMark® Resource Files, for communication between DDC Hardware devices to allow multi-vendor interoperability.

- 5.8.3.1. The building automation system shall be open in that it is designed and installed such that the Government or its agents are able to perform repair, replacement, upgrades, and expansions of the system without further dependence on the original Contractor. This includes, but is not limited to the following:
- (a) Install hardware such that individual control equipment can be replaced by similar control equipment from other equipment manufacturers with no loss of system functionality.
- (b) Necessary documentation (including rights to documentation and data), configuration information, configuration tools, programs, drivers, and other software shall be licensed to and otherwise remain with the Government such that the Government or its agents are able to perform repair, replacement, upgrades, and expansions of the system without subsequent or future dependence on the Contractor.

5.8.3.2. All DDC Hardware shall:

- (a) Be connected to a TP/FT-10 ANSI/EIA 709.3 control network.
- (b) Communicate over the control network via ANSI/EIA 709.1B exclusively.
- (c) Communicate with other DDC hardware using only SNVTs
- (d) Conform to the LonMark® Interoperability Guidelines.
- (e) Be locally powered; link power (over the control network) is not acceptable.
- (f) Be fully configurable via standard or user-defined configuration parameter types (SCPT or UCPT), standard network variable type (SNVT) network configuration inputs (*nci*), or hardware settings on the controller itself to support the application. All settings and parameters used by the application shall be configurable via standard or user-defined configuration parameter types (SCPT or UCPT), standard network variable type (SNVT) network configuration inputs (*nci*), or hardware settings on the controller itself

Section: 01 10 00 [Not Supplied]
Page 46 of 151

(g) Provide input and output SNVTs required to support monitoring and control (including but not limited to scheduling, alarming, trending and overrides) of the application. Required SNVTs include but are not limited to: SNVT outputs for all hardware I/O, SNVT outputs for all setpoints and SNVT inputs for override of setpoints.

- (h) To the greatest extent practical, not rely on the control network to perform the application...
- 5.8.3.3. Controllers shall be Application Specific Controllers whenever an ASC suitable for the application exists. When an ASC suitable for the application does not exist use programmable controllers or multiple application specific controllers.
- 5.8.3.4. Application Specific Controllers shall be LonMark Certified whenever a LonMark Certified ASC suitable for the application exists. For example, VAV controllers must be LonMark certified.
- 5.8.3.5. Application Specific Controllers (ASCs) shall be configurable via an LNS plug-in whenever t an ASC with an LNS plug-in suitable for the application exists.
- 5.8.3.6. Each scheduled system shall accept a network variable of type SNVT_occupancy and shall use this network variable to determine the occupancy mode. If the system has not received a value to this network variable for more than 60 minutes it shall default to a configured occupancy schedule.
- 5.8.3.7. Gateways may be used provided that each gateway communicates with and performs protocol translation for control hardware controlling one and only one package unit.
- 5.8.3.8. Not Used
- 5.8.3.9. Perform all necessary actions needed to fully integrate the building control system. These actions include but are not limited to:
- Configure M&C Software functionality including: graphical pages for System Graphic Displays including overrides, alarm handling, scheduling, trends for critical values needing long-term or permanent monitoring via trends, and demand limiting.
- Install IP routers or ANSI/CEA-852 routers as needed to connect the building control network to the UMCS IP network. Routers shall be capable of configuration via DHCP and use of an ANSI/CEA-852 configuration server but shall not rely on these services for configuration. All communication between the UMCS and building networks shall be via the ANSI/CEA-709.1B protocol over the IP network in accordance with ANSI/CEA-852.
- 5.8.3.10. Provide the following to the Government for review prior to acceptance of the system:
- The latest version of all software and user manuals required to program, configure and operate the system.
- Points Schedule drawing that shows every DDC Hardware device. The Points Schedule shall contain the following information as a minimum:
 - Device address and NodelD.
 - o Input and Output SNVTs including SNVT Name, Type and Description.
 - Hardware I/O, including Type (AI, AO, BI, BO) and Description.
 - o Alarm information including alarm limits and SNVT information.
 - Supervisory control information including SNVTs for trending and overrides.
 - o Configuration parameters (for devices without LNS plug-ins) Example Points Schedules are available at https://eko.usace.army.mil/fa/besc/
- Riser diagram of the network showing all network cabling and hardware. Label hardware with ANSI.CEA-709.1 addresses, IP addresses, and network names.
- Control System Schematic diagram and Sequence of Operation for each HVAC system.
- Operation and Maintenance Instructions including procedures for system start-up, operation and shut-down, a routine maintenance checklist, and a qualified service organization list.
- LonWorks® Network Services (LNS®) database for the completed system.
- Quality Control (QC) checklist (below) completed by the Contractor's Chief Quality Control (QC)
 Representative

Table 5-1: QC Checklist

Section: 01 10 00

[Not Supplied] Page 47 of 151

LNS Database is up-to-date and accurately represents the final installed syster All software has been licensed to the Government M&C software monitoring displays have been created for all building systems, override and display points indicated on Points Schedule drawings. Final As-built Drawings accurately represent the final installed system. O&M Instructions have been completed and submitted. Connections between the UMCS IP network and ANSI/CEA-709.1B building not through ANSI/CEA-852 Routers.	TI-	nitials
Communication between DDC Hardware is only via EIA 709.1B using SNVTs. and network variables other than SNVTs have not been used. All sequences are performed using DDC Hardware. LNS Database is up-to-date and accurately represents the final installed system All software has been licensed to the Government M&C software monitoring displays have been created for all building systems, override and display points indicated on Points Schedule drawings. Final As-built Drawings accurately represent the final installed system. O&M Instructions have been completed and submitted. Connections between the UMCS IP network and ANSI/CEA-709.1B building net through ANSI/CEA-852 Routers.	,,,	
and network variables other than SNVTs have not been used. All sequences are performed using DDC Hardware. LNS Database is up-to-date and accurately represents the final installed system All software has been licensed to the Government M&C software monitoring displays have been created for all building systems, override and display points indicated on Points Schedule drawings. Final As-built Drawings accurately represent the final installed system. O&M Instructions have been completed and submitted. Connections between the UMCS IP network and ANSI/CEA-709.1B building not through ANSI/CEA-852 Routers.		
All sequences are performed using DDC Hardware. LNS Database is up-to-date and accurately represents the final installed system All software has been licensed to the Government M&C software monitoring displays have been created for all building systems, override and display points indicated on Points Schedule drawings. Final As-built Drawings accurately represent the final installed system. O&M Instructions have been completed and submitted. Connections between the UMCS IP network and ANSI/CEA-709.1B building not through ANSI/CEA-852 Routers.	Other protocols	
LNS Database is up-to-date and accurately represents the final installed syster All software has been licensed to the Government M&C software monitoring displays have been created for all building systems, override and display points indicated on Points Schedule drawings. Final As-built Drawings accurately represent the final installed system. O&M Instructions have been completed and submitted. Connections between the UMCS IP network and ANSI/CEA-709.1B building not through ANSI/CEA-852 Routers.		
All software has been licensed to the Government M&C software monitoring displays have been created for all building systems, override and display points indicated on Points Schedule drawings. Final As-built Drawings accurately represent the final installed system. O&M Instructions have been completed and submitted. Connections between the UMCS IP network and ANSI/CEA-709.1B building not through ANSI/CEA-852 Routers.		
All software has been licensed to the Government M&C software monitoring displays have been created for all building systems, override and display points indicated on Points Schedule drawings. Final As-built Drawings accurately represent the final installed system. O&M Instructions have been completed and submitted. Connections between the UMCS IP network and ANSI/CEA-709.1B building not through ANSI/CEA-852 Routers.	m	
override and display points indicated on Points Schedule drawings. Final As-built Drawings accurately represent the final installed system. O&M Instructions have been completed and submitted. Connections between the UMCS IP network and ANSI/CEA-709.1B building network ANSI/CEA-852 Routers.		
Final As-built Drawings accurately represent the final installed system. O&M Instructions have been completed and submitted. Connections between the UMCS IP network and ANSI/CEA-709.1B building network.	including all	
8 O&M Instructions have been completed and submitted. 9 Connections between the UMCS IP network and ANSI/CEA-709.1B building no through ANSI/CEA-852 Routers.		
9 Connections between the UMCS IP network and ANSI/CEA-709.1B building network ANSI/CEA-852 Routers.		
through ANSI/CEA-852 Routers.		
	etworks are	
By signing below I verify that all requirements of the contract, including but not limited to t		
By signing below I verify that all requirements of the contract, including but not limited to t		
	the above, been r	met.
Signature: Date:		

- 5.8.3.11. Perform a Performance Verification Test (PVT) under Government supervision prior to system acceptance. During the PVT demonstrate that the system performs as specified, including but not limited to demonstrating that the system is Open and correctly performs the Sequences of Operation.
- 5.8.3.12. Provide a 1 year unconditional warranty on the installed system and on all service call work. The warranty shall include labor and material necessary to restore the equipment involved in the initial service call to a fully operable condition.
- 5.8.3.13. Provide training at the project site on the installed building system Upon completion of this training each student, using appropriate documentation, should be able to start the system, operate the system, recover the system after a failure, perform routine maintenance and describe the specific hardware, architecture and operation of the system.

•

- 5.8.4. TESTING, ADJUSTING AND BALANCING. Test and balance air and hydronic systems, using a firm certified for testing and balancing by the Associated Air Balance Council (AABC), National Environmental Balancing Bureau (NEBB), or the Testing Adjusting, and Balancing Bureau (TABB). The prime contractor shall hire the TAB firm directly, not through a subcontractor. Perform TAB in accordance with the requirements of the standard under which the TAB Firm's qualifications are approved, i.e., AABC MN-1, NEBB TABES, or SMACNA HVACTAB unless otherwise specified herein. All recommendations and suggested practices contained in the TAB Standard shall be considered mandatory. Use the provisions of the TAB Standard, including checklists, report forms, etc., as nearly as practicable to satisfy the Contract requirements. Use the TAB Standard for all aspects of TAB, including qualifications for the TAB Firm and Specialist and calibration of TAB instruments. Where the instrument manufacturer calibration recommendations are more stringent than those listed in the TAB Standard, adhere to the manufacturer's recommendations. All quality assurance provisions of the TAB Standard such as performance guarantees shall be part of this contract. For systems or system components not covered in the TAB Standard, the TAB Specialist shall develop TAB procedures. Where new procedures, requirements, etc., applicable to the Contract requirements have been published or adopted by the body responsible for the TAB Standard used (AABC, NEBB, or TABB), the requirements and recommendations contained in these procedures and requirements are mandatory.
- 5.8.5. COMMISSIONING: Commission all HVAC systems and equipment, including controls, and all systems requiring commissioning for LEED Enhanced commissioning, in accordance with ASHRAE Guideline 1.1, ASHRAE Guideline 0 and LEED. Do not use the sampling techniques discussed in ASHRAE Guideline 1.1 and in ASHRAE Guideline 0. Commission 100% of the HVAC controls and equipment. Hire the Commissioning Authority (CA), certified as a CA by AABC, NEBB, or TABB, as described in Guideline 1.1. The CA will be an independent

Section: 01 10 00 [Not Supplied]
Page 48 of 151

subcontractor and not an employee of the Contractor nor an employee or subcontractor of any other subcontractor on this project, including the design professionals (i.e., the DOR or their firm(s)). The CA will communicate and report directly to the Government in execution of commissioning activities. The Contracting Officer's Representative will act as the Owner's representative in performance of duties spelled out under OWNER in Annex F of ASHRAE Guideline 0. All buildings with Minimum LEED Silver (or better) requirement will earn LEED Credit EA3 Enhanced Commissioning.

5.9. ENERGY CONSERVATION

- 5.9.1. The building including the building envelope, HVAC systems, service water heating, power, and lighting systems shall meet the Mandatory Provisions and the Prescriptive Path requirements of ASHRAE 90.1. Substantiation requirements are defined in Section 01 33 16, Design After Award.
- 5.9.2. Design all building systems and elements to meet the minimum requirements of ANSI/ASHRAE/IESNA 90.1. Design the buildings, including the building envelope, HVAC systems, service water heating, power, and lighting systems to achieve an energy consumption that is at least 40% below the consumption of a baseline building meeting the minimum requirements of ANSI/ASHRAE/IESNA Standard 90.1. Energy calculation methodologies and substantiation requirements are defined in Section 01 33 16, Design After Award.
- 5.9.3. Purchase Energy Star products, except use FEMP designated products where FEMP is applicable to the type product. The term "Energy Star product" means a product that is rated for energy efficiency under an Energy Star program. The term "FEMP designated product" means a product that is designated under the Federal Energy Management Program of the Department of Energy as being among the highest 25 percent of equivalent products for energy efficiency. When selecting integral sized electric motors, choose NEMA PREMIUM type motors that conform to NEMA MG 1, minimum Class F insulation system. Motors with efficiencies lower than the NEMA PREMIUM standard may only be used in unique applications that require a high constant torque speed ratio (e.g., inverter duty or vector duty type motors that conform to NEMA MG 1, Part 30 or Part 31).
- 5.9.4. Solar Hot Water Heating. Provide at least 30% of the domestic hot water requirements through solar heating methodologies, unless the results of a Life Cycle Cost Analysis (LCCA) developed utilizing the Building Life Cycle Cost Program (BLCC) which demonstrates that the solar hot water system is not life cycle cost effective in comparison with other hot water heating systems. The type of system will be established during the contract or task order competition and award phase, including submission of an LCCA for government evaluation to justify non-selection of solar hot water heating. The LCCA uses a study period of 25 years and the Appendix K utility cost information. The LCCA shall include life cycle cost comparisons to a baseline system to provide domestic hot water without solar components, analyzing at least two different methodologies for providing solar hot water to compare against the baseline system.
- 5.9.5. Process Water Conservation. When potable water is used to improve a building's energy efficiency, employ lifecycle cost effective water conservation measures, except where precluded by other project requirements.
- 5.9.6. Renewable Energy Features. The Government's goal is to implement on-site renewable energy generation for Government use when lifecycle cost effective. See Paragraph 6, PROJECT SPECIFIC REQUIREMENTS for renewable energy requirements for this project.
- 5.10. FIRE PROTECTION
- 5.10.1. STANDARDS AND CODES Provide the fire protection system conforming to APPLICABLE CRITERIA.
- 5.10.2. Inspect and test all fire suppression equipment and systems, fire pumps, fire alarm and detection systems and mass notification systems in accordance with the applicable NFPA standards. The fire protection engineer of record shall witness final tests. The fire protection engineer of record shall certify that the equipment and systems are fully operational and meet the contract requirements. Two weeks prior to each final test, the contractor shall notify, in writing, the installation fire department and the installation public work representative of the test and invite them to witness the test.
- 5.10.3. Fire Extinguisher Cabinets: Provide fire extinguisher cabinets and locations for hanging portable fire extinguishers in accordance with NFPA 10 Standard for Portable Fire Extinguishers.

Section: 01 10 00 [Not Supplied]
Page 49 of 151

5.10.4. Fire alarm and detection system: Required fire alarm and detection systems shall be the addressable type. Fire alarm initiating devices, such as smoke detectors, heat detectors and manual pull stations shall be addressable. When the system is in alarm condition, the system shall annunciate the type and location of each alarm initiating device. Sprinkler water flow alarms shall be zoned by building and by floor. Supervisory alarm initiating devices, such as valve supervisory switches, fire pump running alarm, low-air pressure on dry sprinkler system, etc. shall be zoned by type and by room location.

5.10.5. Fire Protection Engineer Qualifications: In accordance with UFC 3-600-01, FIRE PROTECTION ENGINEERING FOR FACILITIES, the fire protection engineer of record shall be a registered professional engineer (P.E.) who has passed the fire protection engineering written examination administered by the National Council of Examiners for Engineering and Surveys (NCEES), or a registered P.E. in a related engineering discipline with a minimum of 5 years experience, dedicated to fire protection engineering that can be verified with documentation.

5.11. SUSTAINABLE DESIGN

- 5.11.1. STANDARDS AND CODES: Sustainable design shall conform to APPLICABLE CRITERIA. See paragraph 6, PROJECT-SPECIFIC REQUIREMENTS for which version of LEED applies to this project. The LEED-NC Application Guide for Multiple Buildings and On-Campus Building Projects (AGMBC) applies to all projects. Averaging may be used for LEED compliance as permitted by the AGMBC but is restricted to only those buildings included in this project. Each building must individually comply with the requirements of paragraphs ENERGY CONSERVATION and BUILDING WATER USE REDUCTION.
- 5.11.2. LEED RATING, REGISTRATION, VALIDATION AND CERTIFICATION: See Paragraph PROJECT-SPECIFIC REQUIREMENTS for project minimum LEED rating/achievement level, for facilities that are exempt from the minimum LEED rating, for LEED registration and LEED certification requirements and for other project-specific information and requirements.
- 5.11.2.1. Innovation and Design Credits. LEED Innovation and Design (ID) credits are acceptable only if they are supported by formal written approval by GBCI (either published in USGBC Innovation and Design Credit Catalog or accompanied by a formal ruling from GBCI). LEED ID credits that require any Owner actions or commitments are acceptable only when Owner commitment is indicated in paragraph PROJECT-SPECIFIC REQUIREMENTS or Appendix LEED Project Credit Guidance
- 5.11.3. OPTIMIZE ENERGY PERFORMANCE.: Project must earn, as a minimum, the points associated with compliance with paragraph ENERGY CONSERVATION. LEED documentation differs from documentation requirements for paragraph ENERGY CONSERVATION and both must be provided. For LEED-NC v2.2 projects you may substitute ASHRAE 90.1 2007 Appendix G in its entirety for ASHRAE 90.1 2004 in accordance with USGBC Credit Interpretation Ruling dated 4/23/2008.
- 5.11.4. COMMISSIONING. See paragraph 5.8.5 COMMISSIONING for commissioning requirements. USACE templates for the required Basis of Design document and Commissioning Plan documents are available at http://en.sas.usace.army.mil (click on Engineering Criteria) and may be used at Contractor's option.
- 5.11.5. DAYLIGHTING. Except where precluded by other project requirements, do the following in at least 75 percent of all spaces occupied for critical visual tasks: achieve a 2 percent glazing factor (calculated in accordance with LEED credit EQ8.1) OR earn LEED Daylighting credit, provide appropriate glare control and provide either automatic dimming controls or occupant-accessible manual lighting controls.
- 5.11.6. LOW-EMITTING MATERIALS. Except where precluded by other project requirements, use materials with low pollutant emissions, including but not limited to composite wood products, adhesives, sealants, interior paints and finishes, carpet systems and furnishings,
- 5.11.7. CONSTRUCTION INDOOR AIR QUALITY MANAGEMENT. Except where precluded by other project requirements, earn LEED credit EQ 3.1 Construction IAQ Management Plan, During Construction and credit EQ 3.2 Construction IAQ Management Plan, Before Occupancy.
- 5.11.8. RECYCLED CONTENT. In addition to complying with section RECYCLED/RECOVERED MATERIALS, earn LEED credit MR4.1, Recycled Content, 10 percent except where precluded by other project requirements.

Section: 01 10 00 [Not Supplied]
Page 50 of 151

5.11.9. BIOBASED AND ENVIRONMENTALLY PREFERABLE PRODUCTS. Except where precluded by other project requirements, use materials with biobased content, materials with rapidly renewable content, FSC certified wood products and products that have a lesser or reduced effect on human health and the environment over their lifecycle to the maximum extent practicable.

- 5.11.10. FEDERAL BIOBASED PRODUCTS PREFERRED PROCUREMENT PROGRAM (FB4P). The Farm Security and Rural Investment Act (FSRIA) of 2002 required the U.S. Department of Agriculture (USDA) to create procurement preferences for biobased products that are applicable to all federal procurement (to designate products for biobased content). For all designated products that are used in this project, meet USDA biobased content rules for them except use of a designated product with USDA biobased content is not required if the biobased product (a) is not available within a reasonable time, (b) fails to meet performance standard or (c) is available only at an unreasonable price. For biobased content product designations, see http://www.biopreferred.gov/ProposedAndFinalItemDesignations.aspx.
- 5.12. CONSTRUCTION AND DEMOLITION (C&D) WASTE MANAGEMENT: Achievement of 50% diversion, by weight, of all non-hazardous C&D waste debris is required. Reuse of excess soils, recycling of vegetation, alternative daily cover, and wood to energy are not considered diversion in this context, however the Contractor must tracked and report it. A waste management plan and waste diversion reports are required, as detailed in Section 01 57 20.00 10, ENVIRONMENTAL PROTECTION.
- 5.13. SECURITY (ANTI-TERRORISM STANDARDS): Unless otherwise specified in Project Specific Requirements, only the minimum protective measures as specified by the current Department of Defense Minimum Antiterrorism Standards for Buildings, UFC 4-010-01, are required for this project. The element of those standards that has the most significant impact on project planning is providing protection against explosives effects. That protection can either be achieved using conventional construction (including specific window requirements) in conjunction with establishing relatively large standoff distances to parking, roadways, and installation perimeters or through building hardening, which will allow lesser standoff distances. Even with the latter, the minimum standoff distances cannot be encroached upon. These setbacks will establish the maximum buildable area. All standards in Appendix B of UFC 4-010-01 must be followed and as many of the recommendations in Appendix C that can reasonably be accommodated should be included. The facility requirements listed in these specifications assume that the minimum standoff distances can be met, permitting conventional construction. Lesser standoff distances (with specific minimums) are not desired, however can be provided, but will require structural hardening for the building. See Project Specific Requirements for project specific siting constraints. The following list highlights the major points but the detailed requirements as presented in Appendix B of UFC 4-010-01 must be followed.
- (a) Standoff distance from roads, parking and installation perimeter; and/or structural blast mitigation
- (b) Blast resistant windows and skylights, including glazing, frames, anchors, and supports
- (c) Progressive collapse resistance for all facilities 3 stories or higher
- (d) Mass notification system (shall also conform to UFC 4-021-01, Mass Notification Systems)
- (e) For facilities with mailrooms (see paragraph 3 for applicability) mailrooms have separate HVAC systems and are sealed from rest of building

Section: 01 10 00 [Not Supplied]
Page 51 of 151

6.0 PROJECT SPECIFIC REQUIREMENTS

6.1. GENERAL

The requirements of this paragraph augment the requirements indicated in Paragraphs 3 through 5.

6.2. APPROVED DEVIATIONS

The following are approved deviations from the requirements stated in Paragraphs 3 through 5 that only apply to this project.

[Not Supplied - PS_Deviations : DEVIATIONS]

6.3. SITE PLANNING AND DESIGN

6.3.1. General:

[Not Supplied - PS_SitePlanningGeneral : SITE_PLANNING]

6.3.2. Site Structures and Amenities

[Not Supplied - PS_SitePlanningStructures : SITE_STRUCTURES_AMENITIES]

6.3.3. Site Functional Requirements:

6.3.3.1. Stormwater Management (SWM) Systems.

[Not Supplied - PS SitePlanningSiteFunctional SWM: STORMWATER MANAGEMENT]

6.3.3.2. Erosion and Sediment Control

[Not Supplied - PS_SitePlanningSiteFunctional_ES : EROSION_CONTROL]

6.3.3.3. Vehicular Circulation.

[Not Supplied - PS SitePlanningSiteFunctional VC: VEHICULAR CIRCULATION]

6.4. SITE ENGINEERING

6.4.1. Existing Topographical Conditions

[Not Supplied - PS_SiteEngineering_Topo : SITE_EXIST_TOPO]

6.4.2. Existing Geotechnical conditions: See Appendix A for a preliminary geotechnical report.

[Not Supplied - PS SiteEngineering Geo : SITE EXIST GEO]

6.4.3. Fire Flow Tests See Appendix D for results of fire flow tests to use for basis of design for fire flow and domestic water supply requirements.

[Not Supplied - PS SiteEngineering Fire : SITE FIREFLOW]

6.4.4. Pavement Engineering and Traffic Estimates:

[Not Supplied - PS_SiteEngineering_Pavement : SITE_PAVEMENT_ENGINEERING_AND_TRAFFIC]

6.4.5. Traffic Signage and Pavement Markings

Section: 01 10 00 [Not Supplied]
Page 52 of 151

[Not Supplied - PS SiteEngineering TrafficSignage : SITE TRAFFIC SIGNAGE]

6.4.6. Base Utility Information

[Not Supplied - PS_SiteEngineering_BaseUtilIty : SITE_BASE]

[Not Supplied - PS SiteEngineering BaseUtility: SITE ELEC]

[Not Supplied - PS SiteEngineering BaseUtility: SITE WATER]

[Not Supplied - PS_SiteEngineering_BaseUtility : SITE_SEWER]

[Not Supplied - PS_SiteEngineering_BaseUtility : SITE_GAS]

[Not Supplied - PS_SiteEngineering_BaseUtility : SITE_CABLE_TV]

6.4.7. Cut and Fill

[Not Supplied - PS_SiteEngineering_CutFill : SITE_CUT]

6.4.8. Borrow Material

[Not Supplied - PS_SiteEngineering_BorrowMaterial : BORROW_MATERIAL]

6.4.9. Haul Routes and Staging Areas

[Not Supplied - PS_SiteEngineering_HaulRoutes : SITE_HAUL_ROUTES]

6.4.10. Clearing and Grubbing:

[Not Supplied - PS SiteEngineering ClearGrub: SITE CLEAR GRUB]

6.4.11. Landscaping:

[Not Supplied - PS SiteEngineering Landscape : LANDSCAPING]

6.4.12. Turf:

[Not Supplied - PS_SiteEngineering_Turf : TURF]

6.5. ARCHITECTURE

6.5.1. General: To the maximum extent possible within the contract cost limitation, the buildings shall conform to the look and feel of the architectural style and shall use the same colors as adjacent facilities as expressed herein. The Government will evaluate the extent to which the proposal is compatible with the architectural theme expressed in the RFP during the contract or task order competition. The first priority in order of importance is that the design provides comparable building mass, size, height, and configuration compared to the architectural theme expressed herein. The second priority is that design is providing compatible exterior skin appearance based upon façade, architectural character (period or style), exterior detailing, matching nearby and installation material/color pallets, as described herein.

6.5.2. **Design**

6.5.2.1. Appendix F is provided "For Information Only", to establish the desired site and architectural themes for the area. Appendix F identifies the desired project look and feel based on Fort Lee's Installation Architectural Theme from existing and proposed adjacent building forms; i.e. building exterior skin, roof lines, delineation of entrances, proportions of fenestration in relation to elevations, shade and shadow effects, materials, textures, exterior color schemes, and organizational layout.

Section: 01 10 00 [Not Supplied]
Page 53 of 151

6.5.2.2. The design should address Fort Lee's identified preferences. Implement these preferences considering the following:

- (a) Achievable within the Construction Contract Cost Limitation (CCL)
- (b) Meets Milestones within Maximum Performance Duration.
- (c) Achieves Full Scope indentified in this Solicitation
- (d) Best Life-Cycle Cost Design
- (e) Meets the Specified Sustainable Design and LEED requirements
- (f) Complies with Energy Conservation Requirements Specified in this RFP.
- 6.5.2.3. Priority #1. Visual Compatibility: Facility Massing (Size, Height, Spacing, Architectural Theme, etc.) Exterior Aesthetic Considerations: The buildings massing, exterior functional aesthetics, and character shall create a comprehensive and harmonious blend of design features that are sympathetic to the style and context of the Installation. The Installation's intent for this area is:

[Not Supplied - PS Architecture: THEME DESCRIPTION]

- 6.5.2.4. Priority #2. Architectural Compatibility: Exterior Design Elements (Materials, Style, Construction Details, etc.) Roofs, Exterior Skin, and Windows & Door Fenestrations should promote a visually appealing compatibility with the desired character while not sacrificing the integrity and technical competency of building systems.
- 6.5.2.5. See Appendix F for exterior colors that apply to Architectural character at Fort Lee. The manufacturers and materials referenced are intended to establish color only, and are not intended to limit manufacturers and material selections.
- 6.5.2.6. Additional architectural requirements:
- (a) Install fall protection anchor points on all roofs with a slope greater than 2:12

[Not Supplied - PS Architecture : ARCHITECTURE]

6.5.3. Programmable Electronic Key Card Access Systems:

[Not Supplied - PS Architecture : PROGRAMMABLE KEY CARD]

6.5.4. INTERIOR DESIGN

[Not Supplied - PS_Architecture : INTERIORS]

Interior building signage requirements:

[Not Supplied - PS Architecture : INTERIOR SIGNAGE]

6.6. STRUCTURAL DESIGN

[Not Supplied - PS_Structural : STRUCT_DESIGN]

6.7. THERMAL PERFORMANCE

[Not Supplied - PS_ThermalPerformance : THERMAL_PERFORMANCE]

6.8. PLUMBING

[Not Supplied - PS_Plumbing : PLUMBING]

6.9. SITE ELECTRICAL AND TELECOMMUNICATIONS SYSTEMS

Section: 01 10 00 [Not Supplied]
Page 54 of 151

[Not Supplied - PS SiteElectrical: SITE ELECTRICAL]

[Not Supplied - PS_SiteElectrical_Telecom : SITE_TELECOM]

6.10. FACILITY ELECTRICAL AND TELECOMMUNICATIONS SYSTEMS

[Not Supplied - PS_Facility_Electrical : FACILITY_ELECTRICAL]

[Not Supplied - PS Facility Telecom : FACILITY TELECOM]

6.11. HEATING, VENTILATING, AND AIR CONDITIONING

[Not Supplied - PS HVAC : HVAC]

Integrate the control system to the installation's existing UMCS. The existing UMCS is [Not Supplied - PS_HVAC : UMCS_DESCRIPTION]

6.12. ENERGY CONSERVATION

6.12.1. General

[Not Supplied - PS EnergyConservation : ENERGY CONSERVATION]

6.12.2. Inclusion of Renewable Energy Features. The following renewable energy features have been determined lifecycle cost effective, are included in the project budget and shall be provided:

[Not Supplied - PS_EnergyConservation : RENEWABLE_ENERGY_FEATURES]

6.13. FIRE PROTECTION

[Not Supplied - PS FireProtection: FIRE PROTECTION]

- 6.14. SUSTAINABLE DESIGN
- 6.14.1. LEED Rating Tool Version. This project shall be executed using LEED-NC Version 2.2.
- 6.14.2. The minimum requirement for this project is to achieve LEED Silver level. Each non-exempt facility (building plus sitework) must achieve this level. In addition to any facilities indicated as exempt in paragraph 3, the following facilities are exempt from the minimum LEED achievement requirement: [Not Supplied PS SustainableDesignGeneral: SD EXEMPT FACILITIES].
- 6.14.3. Credit Validation: LEED registration, compiling of documentation at LEED OnLine and use of the LEED Letter Templates is required. Registration and payment of registration fees will be by the Government. Administration/team management of the online project will be by the Contractor. Validation of credits will be accomplished by the Government. LEED certification of the project by the Contractor is not required. The Government may choose to seek LEED certification of the project, in which case the Government will pay certification fees and coordinate with the GBCI and the Contractor will furnish audit data as requested at no additional cost.
- 6.14.4. Commissioning: See Appendix M for Owner's Project Requirements document(s).
- 6.14.5. LEED Credits Coordination. The following information is provided relative to Sustainable Sites and other credits.

SS Credit 1 Site Selection:

Project site IS NOT considered prime farmland.

Delineation of 100-year flood elevation is shown on site drawings provided in this CONTRACT.

Section: 01 10 00 [Not Supplied]
Page 55 of 151

Delineation of threatened or endangered species habitat is shown on site drawings provided in this CONTRACT.

Delineation of water, wetlands and areas of special concern is shown on site drawings provided in this CONTRACT.

Project site WAS NOT previously used as public parkland.

SS Credit 2 Development Density & Community Connectivity.

Project site DOES NOT meets the criteria for this credit.

SS Credit 3 Brownfield Redevelopment.

Project site DOES NOT meets the criteria for this credit.

SS Credit 4.1 Public Transportation Access.

Project site DOES NOT meets the criteria for this credit.

EA Credit 6 Green Power.

35% of the project's electricity WILL NOT will be provided through an Installation renewable energy contract. Do not purchase Renewable Energy Credits (REC's) to earn this credit.

MR Credit 2 Construction Waste Management.

The Installation does not have an on-post recycling facility available for Contractor's use.

6.14.6. LEED Credit Preferences, Guidance and Resources. See Appendix L LEED Project Credit Guidance for supplemental information relating to individual credits.

6.14.7. Not Used

6.14.8. Additional Information

[Not Supplied - PS_SustDesign_Additional : MR2]

6.15. ENVIRONMENTAL

[Not Supplied - PS Environmental: ENVIRONMENTAL]

6.16. PERMITS

[Not Supplied - PS_Permits : PERMITS]

6.17. DEMOLITION

[Not Supplied - PS_Demolition : DEMOLITION]

6.18. ADDITIONAL FACILITIES

[Not Supplied - PS_AdditionalFacilities : ADDITIONAL_FACILITIES]

End of Section 01 10 00.[Not Supplied - ProjectInfo : TONUM]

Section: 01 33 00 [Not Supplied]
Page 56 of 151

SECTION 01 33 00.[Not Supplied - ProjectInfo : TONUM] SUBMITTAL PROCEDURES (DESIGN-BUILD TASK ORDERS)

- 1.0 GENERAL
- 1.13. GOVERNMENT APPROVED OR CONCURRED WITH SUBMITTALS
- 1.14. INFORMATION ONLY SUBMITTALS

Section: 01 33 00 [Not Supplied]
Page 57 of 151

1.0 GENERAL

1.1.1. This section contains requirements specifically applicable to this task order. The requirements of Base ID/IQ contract Section 01 33 30 apply to this task order, except as otherwise specified herein.

1.13. GOVERNMENT APPROVED OR CONCURRED WITH SUBMITTALS

Upon completion of review of submittals requiring Government approval or concurrence, the Government will stamp and date the submittals as approved or concurred. The Government will retain zero(0) copies of the submittal and return zero(0) copy(ies) of the submittal.

1.14. INFORMATION ONLY SUBMITTALS

Normally submittals for information only will not be returned. Approval of the Contracting Officer is not required on information only submittals. The Government reserves the right to require the Contractor to resubmit any item found not to comply with the contract. This does not relieve the Contractor from the obligation to furnish material conforming to the plans and specifications; will not prevent the Contracting Officer from requiring removal and replacement of nonconforming material incorporated in the work; and does not relieve the Contractor of the requirement to furnish samples for testing by the Government laboratory or for check testing by the Government in those instances where the technical specifications so prescribe. The Government will retain zero(0) copies of information only submittals.

End of Section 01 33 00.[Not Supplied - ProjectInfo: TONUM]

Section: 01 33 16 [Not Supplied]
Page 58 of 151

SECTION 01 33 16 DESIGN AFTER AWARD

1.0	GENERAL INFORMATION
1.1.	INTRODUCTION
1.2.	DESIGNER OF RECORD
2.0	PRODUCTS (Not Applicable)
3.0	EXECUTION
3.1.	PRE-WORK ACTIVIES & CONFERENCES
3.1.1.	Design Quality Control Plan
3.1.2.	Post Award Conference
3.1.3.	Partnering & Project Progress Processes
3.1.4.	Initial Design Conference
3.1.5.	Pre-Construction Conference
3.2.	STAGES OF DESIGN SUBMITTALS AND OVER THE SHOULDER PROGRESS REVIEWS
3.2.1.	Site/Utilities
3.2.2.	Interim Design Submittals
3.2.3.	Over-the-Shoulder Progress Reviews
3.2.4.	Final Design Submissions
3.2.5.	Design Complete Submittals
3.2.6.	Holiday Periods for Government Review or Actions
3.2.7.	Late Submittals and Reviews
3.3.	DESIGN CONFIGURATION MANAGEMENT
3.3.1.	Procedures
3.3.2.	Tracking Design Review Comments
3.3.3.	Design and Code Checklists
3.4.	INTERIM DESIGN REVIEWS AND CONFERENCES
3.4.1.	General
3.4.2.	Procedures
3.4.3.	Conference Documentation

3.5.	INTERIM DESIGN REQUIREMENTS	
3.5.1.	Drawings	
3.5.2.	Design Analyses	
3.5.3.	Geotechnical Investigations and Reports	
3.5.4.	LEED Documentation	
3.5.5.	Energy Conservation	
3.5.6.	Specifications	
3.5.7.	Building Rendering	
3.5.8.	Interim Building Design Contents	
3.6.	FINAL DESIGN REVIEWS AND CONFERENCES	
3.7.	FINAL DESIGN REQUIREMENTS	
3.7.1.	Drawings	
3.7.2.	Design Analysis	
3.7.3.	Specifications	
3.7.4.	Submittal Register	
3.7.5.	Preparation of DD Form 1354 (Transfer of Real Property)	
3.7.6.	Acceptance and Release for Construction	
3.8.	DESIGN COMPLETE CONSTRUCTION DOCUMENT REQUIREMENTS	
3.9.	SUBMITTAL DISTRIBUTION, MEDIA AND QUANTITIES	
3.9.1.	Submittal Distribution and Quantities	
3.9.2.	Web based Design Submittals	
3.9.3.	Mailing of Design Submittals	
3.10.	AS-BUILT DOCUMENTS	
ATTACHMENT A STRUCTURAL INTERIOR DESIGN (SID) REQUIREMENTS		
ATTACHMENT B FURNITURE, FIXTURES AND EQUIPMENT REQUIREMENTS		
ATTACHMENT C TRACKING COMMENTS IN DRCHECKS		
ATTACHMENT D SAMPLE FIRE PROTECTION AND LIFE SAFETY CODE REVIEW		
ATTACHMENT E LEED SUBMITTALS		

ATTACHMENT F BUILDING INFORMATION MODELING REQUIREMENTS

Section: 01 33 16

Section: 01 33 16 [Not Supplied] Page 60 of 151

ATTACHMENT G DESIGN SUBMITTAL DIRECTORY AND SUBDIRECTORY FILE ARRANGEMENT

Section: 01 33 16 [Not Supplied] Page 61 of 151

1.0 GENERAL INFORMATION

1.1. INTRODUCTION

- 1.1.1. The information contained in this section applies to the design required after award. After award, the Contractor will develop the accepted proposal into the completed design, as described herein.
- 1.1.2. The Contractor may elect to fast track the design and construction that is, proceed with construction of parts of the sitework and facilities prior to completion of the overall design. To facilitate fast tracking, the Contractor may elect to divide the design into no more than ten (10) design packages per major facility type and no more than three (3) design packages for site and associated work. Designate how it will package the design, consistent with its overall plan for permitting (where applicable) and construction of the project. See Sections 01 33 00 SUBMITTAL PROCEDURES and 01 32 01.00 10 PROJECT SCHEDULE for requirements for identifying and scheduling the design packaging plan in the submittal register and project schedule. See also Sections 01 10 00 STATEMENT OF WORK and 01 57 20.00 10 ENVIRONMENTAL PROTECTION for any specified permit requirements. If early procurement of long-lead item construction materials or installed equipment, prior to completion of the associated design package, is necessary to facilitate the project schedule, also identify those long-lead items and how it will assure design integrity of the associated design package to meet the contract requirements (The Contract consists of the Solicitation requirements and the accepted proposal). Once the Government is satisfied that the long-lead items meet the contract requirements, the Contracting Officer will allow the Contractor to procure the items at its own risk.
- 1.1.3. The Contractor may proceed with the construction work included in a separate design package after the Government has reviewed the final (100%) design submission for that package, review comments have been addressed and resolved to the Government's satisfaction and the Contracting Officer (or the Administrative Contracting Officer) has agreed that the design package may be released for construction.
- 1.1.4. INTEGRATED DESIGN. To the maximum extent permitted for this project, use a collaborative, integrated design process for all stages of project delivery with comprehensive performance goals for siting, energy, water, materials and indoor environmental quality and ensures incorporation of these goals. Consider all stages of the building lifecycle, including deconstruction.

1.2. DESIGNER OF RECORD

Identify, for approval, the Designer of Record ("DOR") that will be responsible for each area of design. One DOR may be responsible for more than one area. Listed, Professional Registered, DOR(s) shall account for all areas of design disciplines shall be accounted for by a listed. The DOR's shall stamp, sign, and date each design drawing and other design deliverables under their responsible discipline at each design submittal stage (see contract clause Registration of Designers). If the deliverables are not ready for release for construction, identify them as "preliminary" or "not for release for construction" or by using some other appropriate designation. The DOR(s) shall also be responsible for maintaining the integrity of the design and for compliance with the contract requirements through construction and documentation of the as-built condition by coordination, review and approval of extensions of design, material, equipment and other construction submittals, review and approval or disapproval of requested deviations to the accepted design or to the contract, coordination with the Government of the above activities, and by performing other typical professional designer responsibilities.

2.0 PRODUCTS (Not Applicable)

3.0 EXECUTION

- 3.1. PRE-WORK ACTIVITIES & CONFERENCES
- 3.1.1. Design Quality Control Plan

Submit for Government acceptance, a Design Quality Control Plan in accordance with Section 01 45 04.00 10 CONTRACTOR QUALITY CONTROL before design may proceed.

3.1.2. Post Award Conference

Section: 01 33 16 [Not Supplied]
Page 62 of 151

3.1.2.1. The government will conduct a post award contract administration conference at the project site, as soon as possible after contract award. This will be coordinated with issuance of the contract notice to proceed (NTP). The Contractor and major sub-contractor representatives shall participate. All designers need not attend this first meeting. Government representatives will include COE project delivery team members, facility users, facility command representatives, and installation representatives. The Government will provide an agenda, meeting goals, meeting place, and meeting time to participants prior to the meeting.

- 3.1.2.2. The post award conference shall include determination and introduction of contact persons, their authorities, contract administration requirements, discussion of expected project progress processes, and coordination of subsequent meetings for quality control (see Section 01 45 04.00 10 CONTRACTOR QUALITY CONTROL), Partnering (see below and SCR: Partnering), and the initial design conference (see below).
- 3.1.2.3. The government will introduce COE project delivery team members, facility users, facility command representatives, and installation representatives. The DB Contractor shall introduce major subcontractors, and other needed staff. Expectations and duties of each person shall be defined for all participants. A meeting roster shall be developed and distributed by the government with complete contact information including name, office, project role, phone, mailing and physical address, and email address.

3.1.3. Partnering & Project Progress Processes

- 3.1.3.1. The initial Partnering conference may be scheduled and conducted at any time with or following the post award conference. The Government proposes to form a partnership with the DB Contractor to develop a cohesive building team. This partnership will involve the COE project delivery team members, facility users, facility command representatives, installation representatives, Designers of Record, major subcontractors, contractor quality control staff, and contractor construction management staff. This partnership will strive to develop a cooperative management team drawing on the strengths of each team member in an effort to achieve a quality project within budget and on schedule. This partnership will be bilateral in membership and participation will be totally voluntary. All costs, excluding labor and travel expenses, shall be shared equally between the Government and the Contractor. The Contractor and Government shall be responsible for their own labor and travel costs. Normally, partnering meetings will be held at or in the vicinity of the project installation.
- 3.1.3.2. As part of the partnering process, the Government and Contractor shall develop, establish, and agree to comprehensive design development processes including conduct of conferences, expectations of design development at conferences, fast-tracking, design acceptance, Structural Interior Design (SID)/ Furniture, Fixtures & Equipment (FF&E) design approval, project closeout, etc. The government will explain contract requirements and the DB Contractor shall review their proposed project schedule and suggest ways to streamline processes.

3.1.4. Initial Design Conference

The initial design conference may be scheduled and conducted at the project installation any time after the post award conference, although it is recommended that the partnering process be initiated with or before the initial design conference. Any design work conducted after award and prior to this conference should be limited to site and is discouraged for other items. All Designers of Record shall participate in the conference. The purpose of the meeting is to introduce everyone and to make sure any needs the contractor has are assigned and due dates established as well as who will get the information. See also Attachment F, BUILDING INFORMATION MODELING REQUIREMENTS for discussion concerning the BIM Implementation Plan demonstration at this meeting. The DB Contractor shall conduct the initial design conference.

3.1.5. Pre-Construction Conference

Before starting construction activities, the Contractor and Government will jointly conduct a pre-construction administrative conference to discuss any outstanding requirements and to review local installation requirements for start of construction. It is possible there will be multiple Pre-Construction Conferences based on the content of the design packages selected by the Contractor. The Government will provide minutes of this meeting to all participants.

3.2. STAGES OF DESIGN SUBMITTALS AND OVER THE SHOULDER PROGRESS REVIEWS

The stages of design submittals described below define Government expectations with respect to process and content. The Contractor shall determine how to best plan and execute the design and review process for this project, within the parameters listed below. As a minimum, the Government expects to see at least one interim design submittal, at least one final design submittal before construction of a design package may proceed and at least one Design Complete submittal that documents the accepted design. The Contractor may sub-divide the design into separate packages for each stage of design and may proceed with construction of a package after the Government accepts the final design for that package. See discussion on waivers to submission of one or more intermediate design packages where the parties partner during the design process. See also Attachment F, BUILDING INFORMATION MODELING REQUIREMENTS for discussion concerning BIM and the various stages of design submittals and over-the-shoulder progress reviews.

3.2.1. Site/Utilities

To facilitate fast-track design-construction activities the contractor may submit a final (100%) site and utility design as the first design submittal or it may elect to submit interim and final site and utility design submittals as explained below. Following review, resolution, and incorporation of all Government comments, and submittal of a satisfactory set of site/utility design documents, after completing all other pre-construction requirements in this contract and after the pre-construction meeting, the Government will allow the Contractor to proceed with site development activities, including demolition where applicable, within the parameters set forth in the accepted design submittal. For the first site and utility design submission, whether an interim or final, the submittal review, comment, and resolution times from this specification apply, except that the Contractor shall allow the Government a 14 calendar day review period, exclusive of mailing time. No on-site construction activities shall begin prior to written Government clearance to proceed.

3.2.2. Interim Design Submittals

The Contractor may submit either a single interim design for review, representing a complete package with all design disciplines, or split the interim design into smaller, individual design packages as it deems necessary for fast-track construction purposes. As required in Section 01 32 01.00 10 PROJECT SCHEDULE, the Contractor shall schedule its design and construction packaging plan to meet the contract completion period. This submission is the Government's primary opportunity to review the design for conformance to the solicitation and to the accepted contract proposal and to the Building Codes at a point where required revisions may be still made, while minimizing lost design effort to keep the design on track with the contract requirements. The requirements for the interim design review submittals and review conferences are described hereinafter. This is not necessarily a hold point for the design process; the Contractor may designate the interim design submittal(s) as a snapshot and proceed with design development at its own risk. See below for a waiver, where the parties establish an effective over-the-shoulder progress review procedure through the partnering process that would eliminate the need for or expedite a formal intermediate design review on one or more individual design packages.

3.2.3. Over-the-Shoulder Progress Reviews

To facilitate a streamlined design-build process, the Government and the Contractor may agree to one-on-one reviewer or small group reviews, electronically, on-line (if available within the Contractor's standard design practices) or at the Contractor's design offices or other agreed location, when practicable to the parties. The Government and Contractor will coordinate such reviews to minimize or eliminate disruptions to the design process. Any data required for these reviews shall normally be provided in electronic format, rather than in hard copy. If the Government and Contractor establish and implement an effective, mutually agreeable partnering procedure for regular (e.g., weekly) over-the shoulder review procedures that allow the Government reviewers the opportunity to keep fully informed of the progress, contents, design intent, design documentation, etc. of the design package, the Government will agree to waive or to expedite the formal intermediate design review period for that package. The Contractor shall still be required to submit the required intermediate design documentation, however the parties may agree to how that material will be provided, in lieu of a formal consolidated submission of the package. It should be noted that Government funding is extremely limited for non-local travel by design reviewers, so the maximum use of virtual teaming methods must be used. Some possible examples include electronic file sharing, interactive software with on-line or telephonic conferencing, televideo conferencing, etc. The Government must still perform its Code and Contract conformance reviews, so the Contractor is encouraged to partner with the reviewers to find ways to facilitate this process and to facilitate meeting or bettering the design-build schedule. The Contractor shall maintain a fully functional configuration management system as described herein to track design revisions, regardless of whether or not there is a need for a formal intermediate design review. The formal intermediate

Section: 01 33 16 [Not Supplied]
Page 64 of 151

review procedures shall form the contractual basis for the official schedule, in the event that the partnering process determines that the formal intermediate review process to be best suited for efficient project execution. However, the Government pledges to support and promote the partnering process to work with the Contractor to find ways to better the design schedule.

3.2.4. Final Design Submissions

This submittal is required for each design package prior to Government acceptance of that design package for construction. The requirements for the final design submittal review conferences and the Government's acceptance for start of construction are described herein after.

3.2.5. Design Complete Submittals

After the final design submission and review conference for a design package, revise the design package to incorporate the comments generated and resolved in the final review conferences, perform and document a backcheck review and submit the final, design complete documents, which shall represent released for construction documents. The requirements for the design complete submittals are described hereinafter.

3.2.6. Holiday Periods for Government Review or Actions

Do not schedule meetings, Government reviews or responses during the last two weeks of December or other designated Government Holidays (including Friday after Thanksgiving). Exclude such dates and periods from any durations specified herein for Government actions.

3.2.7. Late Submittals and Reviews

If the Contractor cannot meet its scheduled submittal date for a design package, it must revise the proposed submittal date and notify the government in writing, at least one (1) week prior to the submittal, in order to accommodate the Government reviewers' other scheduled activities. If a design submittal is over one (1) day late in accordance with the latest revised design schedule, or if notification of a proposed design schedule change is less than seven (7) days from the anticipated design submission receipt date, the Government review period may be extended up to seven (7) days due to reviewers' schedule conflicts. If the Government is late in meeting its review commitment and the delay increases the Contractor's cost or delays completion of the project, the Suspension of Work and Defaults clauses provide the respective remedy or relief for the delay.

3.3. DESIGN CONFIGURATION MANAGEMENT

3.3.1. Procedures

Develop and maintain effective, acceptable design configuration management (DCM) procedures to control and track all revisions to the design documents after the Interim Design Submission through submission of the As-Built documents. During the design process, this will facilitate and help streamline the design and review schedule. After the final design is accepted, this process provides control of and documents revisions to the accepted design (See Special Contract Requirement: Deviating From the Accepted Design). The system shall include appropriate authorities and concurrences to authorize revisions, including documentation as to why the revision must be made. The DCM data shall be available to the Government reviewers at all times. The Contractor may use its own internal system with interactive Government concurrences, where necessary or may use the Government's "DrChecks Design Review and Checking System" (see below and Attachment C).

3.3.2. Tracking Design Review Comments

Although the Contractor may use its own internal system for overall design configuration management, the Government and the Contractor shall use the DrChecks Design Review and Checking System to initiate, respond to, resolve and track Government design compliance review comments. This system may be useful for other data which needs to be interactive or otherwise available for shared use and retrieval. See Attachment C for details on how to establish an account and set-up the DrChecks system for use on the project.

3.3.3. Design and Code Checklists

Section: 01 33 16 [Not Supplied]
Page 65 of 151

Develop and complete various discipline-specific checklists to be used during the design and quality control of each submittal. Submit these completed checklists with each design submittal, as applicable, as part of the project documentation. See Section 01 45 04.00 10 Contractor Quality Control, Attachment D for a Sample Fire Protection and Life Safety Code review checklist and Attachment E for LEED SUBMITTALS.

3.4. INTERIM DESIGN REVIEWS AND CONFERENCES

3.4.1. General

At least one interim design submittal, review and review conference is required for each design package (except that, per paragraph 3.2.1, the Contractor may skip the interim design submission and proceed directly to final design on the sitework and utilities package). The DB Contractor may include additional interim design conferences or over-the-shoulder reviews, as needed, to assure continued government concurrence with the design work. Include the interim submittal review periods and conferences in the project schedule and indicate what part of the design work is at what percentage of completion. The required interim design conferences shall be held when interim design requirements are reached as described below. See also Paragraph: **Over-the-Shoulder Progress Reviews** for a waiver to the formal interim design review.

3.4.2. Procedures

After receipt of an Interim Design submission, allow the Government fourteen (14) calendar days after receipt of the submission to review and comment on the interim design submittal. For smaller design packages, especially those that involve only one or a few separate design disciplines, the parties may agree on a shorter review period or alternative review methods (e.g., over-the-shoulder or electronic file sharing), through the partnering process. For each interim design review submittal, the COR will furnish, to the Contractor, a single consolidated, validated listing of all comments from the various design sections and from other concerned agencies involved in the review process using the DrChecks Design Review and Checking System. The review will be for conformance with the technical requirements of the solicitation and the Contractor's RFP proposal. If the Contractor disagrees technically with any comment or comments and does not intend to comply with the comment, he/she must clearly outline, with ample justification, the reasons for noncompliance within five (5) days after receipt of these comments in order that the comment can be resolved. Furnish disposition of all comments, in writing, through DrChecks. The Contractor is cautioned that if it believes the action required by any comment exceeds the requirements of this contract, that it should take no action and notify the COR in writing immediately. The Interim Review conference will be held for each design submittal at the installation. Bring the personnel that developed the design submittal to the review conference. The conference will take place the week after the receipt of the comments by the Contractor. For smaller fast-track packages that involve only a few reviewers, the parties may agree to alternative conferencing methods, such as teleconferencing, or televideo, where available, as determined through Partnering.

3.4.3. Conference Documentation

3.4.3.1. In order to facilitate and accelerate the Government code and contract conformance reviews, identify, track resolution of and maintain all comments and action items generated during the design process and make this available to the designers and reviewers prior to the Interim and subsequent design reviews.

3.4.3.2. The DB Contractor shall prepare meeting minutes and enter final resolution of all comments into DrChecks. Copies of comments, annotated with comment action agreed on, will be made available to all parties before the conference adjourns. Unresolved problems will be resolved by immediate follow-on action at the end of conferences. Incorporate valid comments. The Government reserves the right to reject design document submittals if comments are significant. Participants shall determine if any comments are critical enough to require further design development prior to government concurrence. Participants shall also determine how to proceed in order to obtain government concurrence with the design work presented.

3.5. INTERIM DESIGN REQUIREMENTS

Interim design deliverables shall include drawings, specifications, and design analysis for the part of design that the Contractor considers ready for review.

3.5.1. Drawings

Section: 01 33 16 [Not Supplied]
Page 66 of 151

Include comments from any previous design conferences incorporated into the documents to provide an interim design for the "part" submitted.

- 3.5.2. Design Analyses
- 3.5.2.1. The designers of record shall prepare and present design analyses with calculations necessary to substantiate and support all design documents submitted. Address design substantiation required by the applicable codes and references and pay particular attention to the following listed items:
- 3.5.2.2. For parts including sitework, include site specific civil calculations.
- 3.5.2.3. For parts including structural work, include structural calculations.
- (a) Identify all loads to be used for design.
- (b) Describe the method of providing lateral stability for the structural system to meet seismic and wind load requirements. Include sufficient calculations to verify the adequacy of the method.
- (c) Provide calculations for all principal roof, floor, and foundation members and bracing and secondary members.
- (d) Provide complete seismic analyses for all building structural, mechanical, electrical, architectural, and building features as dictated by the seismic zone for which the facility is being constructed.
- (e) Computer generated calculations must identify the program name, source, and version. Provide input data, including loads, loading diagrams, node diagrams, and adequate documentation to illustrate the design. The schematic models used for input must show, as a minimum, nodes/joints, element/members, materials/properties, and all loadings, induced settlements/deflections, etc., and a list of load combinations. Include an output listing for maximum/minimum stresses/forces and deflections for each element and the reactions for each loading case and combination.
- (f) See also the Security (Anti-Terrorism) requirements below for members subject to Anti-Terrorist Force Protection (ATFP) and Progressive Collapse requirements.
- (g) Fully coordinate and integrate the overall structural design between two different or interfacing construction types, such as modular and stick-built or multistory, stacked modular construction. Provide substantiation of structural, consolidation/settlement analysis, etc., as applicable, through the interfaces.
- 3.5.2.4. For Security (Anti-Terrorism): Provide a design narrative and calculations where applicable, demonstrating compliance with each of the 22 standards in UFC 4-010-01, which includes Design of Buildings to Resist Progressive Collapse (use the most recent version of UFC 4-023-03, regardless of references to any specific version in UFC 4-010-01). Where sufficient standoff distance is not being provided, show calculations for blast resistance of the structural system and building envelope. Show complete calculations for members subjected to ATFP loads, e.g., support members of glazed items (jambs, headers, sills) connections of windows to support members and connections of support members to the rest of the structure. For 3 story and higher buildings, provide calculations to demonstrate compliance with progressive collapse requirements.
- 3.5.2.5. For parts including architectural work, include building floor area analysis.
- 3.5.2.6. For parts including mechanical work, include HVAC analysis and calculations. Include complete design calculations for mechanical systems. Include computations for sizing equipment, compressed air systems, air duct design, and U-factors for ceilings, roofs and exterior walls and floors. Contractor shall employ commercially available energy analysis techniques to determine the energy performance of all passive systems and features. Use of hourly energy load computer simulation is required (see paragraph 3.5.5.2 for list of acceptable software). Based on the results of calculations, provide a complete list of the materials and equipment proposed with the manufacturer's published cataloged product installation specifications and roughing-in data.
- 3.5.2.7. For parts including life safety, include building code analysis and sprinkler and other suppression systems. Notwithstanding the requirements of the Codes, address the following:
- (a) A registered fire protection engineer (FPE) must perform all fire protection analyses. Provide the fire protection engineer's qualifications. See Section 01 10 00, paragraph 5 for qualifications.

Section: 01 33 16 [Not Supplied] Page 67 of 151

(b) Provide all references used in the design including Government design documents and industry standards used to generate the fire protection analysis.

- (c) Provide classification of each building in accordance with fire zone, building floor areas and height and number of stories.
- (d) Provide discussion and description of required fire protection requirements including extinguishing equipment, detection equipment, alarm equipment and water supply. Alarm and detection equipment shall interface to requirements of Electronic Systems.
- (e) Provide hydraulic calculations based on water flow test for each sprinkler system to insure that flow and pressure requirements can be met with current water supply. Include copies of Contractor's water flow testing done to certify the available water source.
- 3.5.2.8. For parts including plumbing systems:
- (a) List all references used in the design.
- (b) Provide justification and brief description of the types of plumbing fixtures, piping materials and equipment proposed for use.
- (c) Detail calculations for systems such as sizing of domestic hot water heater and piping; natural gas piping; LP gas piping and tanks, fuel oil piping and tanks, etc., as applicable.
- (d) When the geotechnical report indicates expansive soils are present, indicate in the first piping design submittal how piping systems will be protected against damage or backfall/backflow due to soil heave (from penetration of slab to the 5 foot building line).
- 3.5.2.9. For elevator systems:
- (a) List all criteria codes, documents and design conditions used.
- (b) List any required permits and registrations for construction of items of special mechanical systems and equipment.
- 3.5.2.10. For parts including electrical work, include lighting calculations to determine maintained foot-candle levels, electrical load analysis and calculations, electrical short circuit and protective device coordination analysis and calculations and arc fault calculations.
- 3.5.2.11. For parts including telecommunications voice/data (including SIPRNET, where applicable), include analysis for determining the number and placement of outlets
- 3.5.2.12. For Cathodic Protection Systems, provide the following stamped report by the licensed corrosion engineer or NACE specialist with the first design submission. The designer must be qualified to engage in the practice of corrosion control of buried or submerged metallic surfaces. He/she must be accredited or certified by the National Association of Corrosion Engineers (NACE) as a NACE Accredited Corrosion Specialist or a NACE certified Cathodic Protection Specialist, or must be a registered professional engineer with a minimum of five years experience in corrosion control and cathodic protection, Clearly describe structures, systems or components in soil or water to be protected. Describe methods proposed for protection of each.
- 3.5.3. Geotechnical Investigations and Reports:
- 3.5.3.1. The contractor's licensed geotechnical engineer shall prepare a final geotechnical evaluation report, to be submitted along with the first foundation design submittal. Make this information available as early as possible during the over-the-shoulder progress review process. Summarize the subsurface conditions and provide recommendations for the design of appropriate utilities, foundations, floor slabs, retaining walls, embankments, and pavements. Include compaction requirements for fill and backfill under buildings, sidewalks, other structures and open areas. Recommend foundation systems to be used, allowable bearing pressures for footings, lateral load resistance capacities for foundation systems, elevations for footings, grade beams, slabs, etc. Provide an assessment of post-construction settlement potential including total and differential. Provide recommendations regarding lateral earth pressures (active, at-rest, passive) to be used in the design of retaining walls. Include the recommended spectral accelerations and Site Class for seismic design along with an evaluation of any seismic hazards and recommendations for mitigation, if required. Include calculations to support the recommended

design parameters such as Site Class, shear strength, earth pressure coefficients, friction factors, subgrade modulus, California Bearing Ratio (CBR), etc. Provide earthwork recommendations, expected frost penetration, expected groundwater levels, recommendations for dewatering and groundwater control and the possible presence of any surface or subsurface features that may affect the construction of the project such as sinkholes, boulders, shallow rock, old fill, old structures, soft areas, or unusual soil conditions. Include pH tests, salinity tests, resistivity measurements, etc., required to design corrosion control and grounding systems. Include the raw field data. Arrange a meeting with the Government subsequent to completion and evaluation of the site specific geotechnical exploration to outline any differences encountered that are inconsistent with the Government provided preliminary soils information. Clearly outline differences which require changes in the foundation type, or pavement and earthwork requirements from that possible and contemplated using the Government furnished preliminary soils investigation, which result in a change to the design or construction. Any equitable adjustment is subject to the provisions of the contract's Differing Site Conditions Clause.

- 3.5.3.2. Vehicle Pavements: The Contractor's geotechnical report shall contain flexible and rigid pavement designs, as applicable for the project, including design CBR and modulus of subgrade reaction and the required compaction effort for subgrades and pavement layers. Provide Information on the types of base course materials available in the area and design strengths.
- 3.5.3.3. The Contractor and the professional geotechnical engineer consultant shall certify in writing that the design of the project has been developed consistent with the Contractor's final geotechnical report. The certification shall be stamped by the consulting professional geotechnical engineer and shall be submitted with the first design submission. If revisions are made to the initial design submission, a new certification shall be provided with the final design submission.

3.5.4. LEED Documentation:

Assign a LEED Accredited Professional, responsible to track LEED planning, performance and documentation for each LEED credit through construction closeout. Incorporate LEED credits in the plans, specifications and design analyses. Develop LEED supporting documentation as a separable portion of the Design Analysis and provide with each required design submittal. Include the LEED Project checklist for each non-exempt facility (one checklist may be provided for multiple facilities in accordance with the LEED-NC Application Guide for Multiple Buildings and On-Campus Building Projects and the LEED SUBMITTALS (Attachment E, herein) with each submittal. Final design submittal for each portion of the work must include all required design documentation relating to that portion of work (example - all site credit design documents with final site design). Submittal requirements are as indicated in Attachment E, LEED SUBMITTALS. Submit all documentation indicated on Attachment E as due at final design at final design submittal (for fast-track projects with multiple final design submittals, this shall be at the last scheduled final design submittal). All project documentation related to LEED shall conform to USGBC requirements for both content and format, including audit requirements and be separate from other design analyses. Maintain and update the LEED documentation throughout project progress to construction closeout and shall compile product data, receipts, calculations and other data necessary to substantiate and support all credits claimed. The Government may audit any or all individual credits. Audit documentation is not required to be submitted unless requested. These requirements apply to all projects. If the project requires the Contractor to obtain USGBC certification, the Contractor shall also be responsible for obtaining USGBC certification and shall provide written evidence of certification with the construction closeout LEED documentation submittal. Install the USGBC building plaque at the location indicated by the Government upon receipt. If Contractor obtains USGBC interim design review, submit the USGBC review to the Government within 30 days of receipt for information only.

3.5.4.1. LEED Documentation for Technology Solution Set. If the Solicitation provides a Prescriptive Technology Solution Set, use of the Technology Solution set has no effect on LEED documentation requirements. Provide all required LEED documentation, including energy analysis, in accordance with LEED requirements when using the Technology Solution Set.

3.5.5. Energy Conservation:

3.5.5.1. Refer to Section 01 10 00, Paragraph 5. Interim and Final Design submittals shall demonstrate that each building including the building envelope, HVAC systems, service water heating, power, and lighting systems meet the Mandatory Provisions and the Prescriptive Path requirements of ASHRAE 90.1. Use Compliance Documentation forms available from ASHRAE and included in the ASHRAE 90.1 User's Manual for this purpose. The Architectural Section of the Design Analysis shall include completed forms titled "Building Envelope"

Compliance Documentation Parts I and II". The Heating Ventilating and Air Conditioning (HVAC) Section of the Design Analysis shall include a completed form titled "HVAC Simplified Approach Option - Part I" if this approach is allowed by the Standard. Otherwise, the HVAC Section of the Design Analysis shall include completed forms titled "HVAC Mandatory Provisions - Part II" and "HVAC Prescriptive Requirements - Part III". The Plumbing Section of the Design Analysis shall include a completed form titled "Service Water Heating Compliance Documentation". The Electrical Section of the Design Analysis shall include an explanatory statement on how the requirements of ASHRAE 90.1-2004 Chapter 8 Power were met. The Electrical Section of the Design Analysis shall also include a completed form titled "Lighting Compliance Documentation".

3.5.5.2. Interim and Final Design submittals which address energy consuming systems, (heating, cooling, service hot water, lighting, power, etc.) must also include calculations in a separate Energy Conservation Section of the Design Analysis which demonstrate and document (a) the baseline energy consumption for the facility or facilities under contract, that would meet the requirements of ANSI/ASHRAE/IESNA Standard 90.1 and (b) the energy consumption of the facility or facilities under contract utilizing the materials and methods required by this construction contract. Use the USGBC Energy and Atmosphere (EA) Credit 1 compliance template / form or an equivalently detailed form for documenting compliance with the energy reduction requirements. This template / form is titled PERFORMANCE RATING METHOD and is available when the project is registered for LEED. The calculation methodology used for this documentation and analysis shall follow the guidelines set forth in Appendix G of ASHRAE 90.1, with two exceptions: a) receptacle and process loads may be omitted from the calculation; and b) the definition of the terms in the formula for Percentage Improvement found in paragraph G1.2 are modified as follows: Baseline Building Performance shall mean the annual energy consumption calculated for a building design intended for use as a baseline for rating above standard design meeting the minimum requirements of the energy standard, and Proposed Building Performance shall mean annual energy consumption calculated for the proposed building design intended for construction. This calculation shall address all energy consuming systems in a single integrated methodology. Include laboratory fume hoods and kitchen ventilation loads in the energy calculation. They are not considered process loads. Individual calculations for heating, cooling, power, lighting, power, etc. systems will not be acceptable. The following building simulation software is acceptable for use in calculating building energy consumption: Hourly Analysis Program (HAP) by Carrier Corp., TRACE 700 by Trane Corp., DOE-2 by US Department of Energy, EnergyPlus by DOD/DOE.

3.5.6. Specifications

Specifications may be any one of the major, well known master guide specification sources (use only one source) such as MASTERSPEC from the American Institute of Architects, SPECTEXT from Construction Specification Institute or Unified Facility Guide Specifications (UFGS using MASTERFORMAT 2004 numbering system), etc. (including specifications from these sources). Manufacturers' product specifications, utilizing CSI's Manu-Spec, three part format may be used in conjunction with the selected specifications. The designers of record shall edit and expand the appropriate Specifications to insure that all project design requirements, current code requirements, and regulatory requirements are met. Specifications shall clearly identify, where appropriate, specific products chosen to meet the contract requirements (i.e., manufacturers' brand names and model numbers or similar product information).

3.5.7. Building Rendering

Present and provide a draft color computer, artist, or hand drawn rendering with the conceptual design submittal of the building exterior. Perspective renderings shall include a slightly overhead view of the entire building to encompass elevations and the roof configuration of the building. After Government review and acceptance, provide a final rendering, including the following:

Three (3) 18" x 24" color prints, framed and matted behind glass with project title underneath the print.

One (1) Image file (high resolution) in JPG format on CD for those in the submittal distribution list.

3.5.8. Interim Building Design Contents

The following list represents what the Government considers should be included in the overall completed design for a facility or project. It is not intended to limit the contractor from providing different or additional information as needed to support the design presented, including the require design analyses discussed above. As the Contractor develops individual design packages and submits them for Interim review, include as much of the applicable

Section: 01 33 16 [Not Supplied]
Page 70 of 151

information for an individual design package as is developed at the Interim design level for review purposes. These pieces shall be developed as the design progresses toward the design complete stage.

3.5.8.1. Lawn and Landscaping Irrigation System

3.5.8.2. Landscape, Planting and Turfing

3.5.8.3. Architectural

- (a) Design Narrative
- (b) Architectural Floor Plans, Typical Wall and Roof Sections, Elevations
- (c) Finish schedule
- (d) All required equipment
- (e) Special graphics requirements
- (f) Door and Window Schedules
- (g) Hardware sets using BHMA designations
- (h) Composite floor plan showing all pre-wired workstations
- (i) Structural Interior Design (SID) package: See ATTACHMENT A for specific requirements
- (j) Furniture, Fixtures & Equipment (FF&E) design package: See ATTACHMENT B for specific requirements

3.5.8.4. Structural Systems. Include:

- (a) Drawings showing principal members for roof and floor framing plans as applicable
- (b) Foundation plan showing main foundation elements where applicable
- (c) Typical sections for roof, floor, and foundation conditions

3.5.8.5. Plumbing Systems

- (a) Show locations and general arrangement of plumbing fixtures and major equipment
- (b) Plan and isometric riser diagrams of all areas including hot water, cold water, waste and vent piping. Include natural gas (and meter as required), (natural gas and meter as required), (LP gas), (fuel oil) and other specialty systems as applicable.
- (c) Include equipment and fixture connection schedules with descriptions, capacities, locations, connection sizes and other information as required

3.5.8.6. HVAC Systems

- (a) Mechanical Floor Plans: The floor plans shall show all principle architectural features of the building which will affect the mechanical design. The floor plans shall also show the following:
- (1) Room designations.
- (2) Mechanical legend and applicable notes.
- (3) Location and size of all ductwork and piping.
- (4) Location and capacity of all terminal units (i.e., registers, diffusers, grilles, hydronic baseboards).
- (5) Pre-Fabricated Paint Spray Booth (where applicable to project scope)
- (6) Paint Preparation Area (where applicable to project scope)
- (7) Exhaust fans and specialized exhaust systems.
- (8) Thermostat location.
- (9) Location of heating/cooling plant (i.e., boiler, chiller, cooling tower, etc).
- (10) Location of all air handling equipment.

Section: 01 33 16 [Not Supplied] Page 71 of 151

- (11) Air balancing information.
- (12) Flue size and location.
- (13) Piping diagram for forced hot water system (if used).
- (b) Equipment Schedule: Provide complete equipment schedules. Include:
- (1) Capacity
- (2) Electrical characteristics
- (3) Efficiency (if applicable)
- (4) Manufacturer's name
- (5) Optional features to be provided
- (6) Physical size
- (7) Minimum maintenance clearances
- (a) Details: Provide construction details, sections, elevations, etc., only where required for clarification of methods and materials of design.
- (b) HVAC Controls: Submit complete HVAC controls equipment schedules, sequences of operation, wiring and logic diagrams, Input/Output Tables, equipment schedules, and all associated information. See the Statement of Work for additional specific requirements.
- 3.5.8.7. Fire Protection and Life Safety.
- (a) Provide plan for each floor of each building that presents a compendium of the total fire protection features being incorporated into the design. Include the following types of information:
- (1) The location and rating of any fire-resistive construction such as occupancy separations, area separations, exterior walls, shaft enclosures, corridors, stair enclosures, exit passageways, etc.
- (2) The location and coverage of any fire detection systems
- (3) The location and coverage of any fire suppression systems (sprinkler risers, standpipes, etc.)
- (4) The location of any other major fire protection equipment
- (5) Indicate any hazardous areas and their classification
- (6) Schedule describing the internal systems with the following information: fire hazard and occupancy classifications, building construction type, GPM/square foot sprinkler density, area of operation and other as required
- (b) Working plans and all other materials submitted shall meet NFPA 13 requirements, with respect to required minimum level of detail.
- 3.5.8.8. Elevators. Provide:
- (a) Description of the proposed control system
- (b) Description, approximate capacity and location of any special mechanical equipment for elevators.
- 3.5.8.9. Electrical Systems.
- (a) Electrical Floor Plan(s): Show all principle architectural features of the building which will affect the electrical design. Show the following:
- (1) Room designations.
- (2) Electrical legend and applicable notes.
- (3) Lighting fixtures, properly identified.
- (4) Switches for control of lighting.
- (5) Receptacles.

Section: 01 33 16 [Not Supplied] Page 72 of 151

(6) Location and designation of panelboards. Clearly indicate type of mounting required (flush or surface) and reflect accordingly in specifications.

- (7) Service entrance (conduit and main disconnect).
- (8) Location, designation and rating of motors and/or equipment which requires electrical service. Show method of termination and/or connection to motors and/or equipment. Show necessary junction boxes, disconnects, controllers (approximate only), conduit stubs, and receptacles required to serve the motor and/or equipment.
- (b) Building Riser Diagram(s) (from pad-mounted transformer to unit load center panelboard): Indicate the types and sizes of electrical equipment and wiring. Include grounding and metering requirements.
- (c) Load Center Panelboard Schedule(s): Indicate the following information:
- (1) Panelboard Characteristics (Panel Designation, Voltage, Phase, Wires, Main Breaker Rating and Mounting.
- (2) Branch Circuit Designations.
- (3) Load Designations.
- (4) Circuit Breaker Characteristics. (Number of Poles, Trip Rating, AIC Rating)
- (5) Branch Circuit Connected Loads (AMPS).
- (6) Special Features
- (d) Lighting Fixture Schedule(s): Indicate the following information:
- (1) Fixture Designation.
- (2) General Fixture Description.
- (3) Number and Type of Lamp(s).
- (4) Type of Mounting.
- (5) Special Features.
- (e) Details: Provide construction details, sections, elevations, etc. only where required for clarification of methods and materials of design.
- 3.5.8.10. Electronic Systems including the following responsibilities:
- (a) Fire Detection and Alarm System. Design shall include layout drawings for all devices and a riser diagram showing the control panel, annunciator panel, all zones, radio transmitter and interfaces to other systems (HVAC, sprinkler, etc.)
- (b) Fire Suppression System Control. Specify all components of the Fire Suppression (FS) System in the FS section of the specifications. Clearly describe how the system will operate and interact with other systems such as the fire alarm system. Include a riser diagram on the drawings showing principal components and interconnections with other systems. Include FS system components on drawing legend. Designate all components shown on floor plans "FS system components" (as opposed to "Fire Alarm components"). Show location of FS control panels, HVAC control devices, sensors, and 120V power panel connections on floor plans. Indicate zoning of areas by numbers (1, 2, 3) and detectors sub-zoned for cross zoning by letter designations (A and B). Differentiate between ceiling mounted and under floor detectors with distinct symbols and indicate sub-zone of each.
- (c) Public Address System
- (d) Special Grounding Systems. Completely reflect all design requirements in the specifications and drawings. Specifications shall require field tests (in the construction phase), witnessed by the Government, to determine the effectiveness of the grounding system. Include drawings showing existing construction, if any.
- (e) Cathodic Protection.
- (f) Intrusion Detection, Card Access System
- (g) Central Control and Monitoring System
- (h) Mass Notification System
- (i) Electrical Power Distribution Systems

Section: 01 33 16 [Not Supplied]
Page 73 of 151

3.5.8.11. Separate detailed Telecommunications drawings for Information Systems including the following responsibilities:

- (a) Telecommunications Cabling
- (b) Supporting Infrastructure
- (a) Outside Plant (OSP) Cabling Campus or Site Plans Exterior Pathways and Inter-Building Backbones
- (a) Include a layout of the voice/data outlets (including voice only wall & pay phones) on telecommunication floor plan drawing, location of SIPRNET data outlets (where applicable), and a legend and symbol definition to indicate height above finished floor. Show size of conduit and cable type and size on Riser Diagram. Do not show conduit runs between backboard and outlets on the floor plans. Show underground distribution conduit and cable with sizing from point of presence to entrance facility of building.
- (b) Layout of complete building per floor Serving Zone Boundaries, Backbone Systems, and Horizontal Pathways including Serving Zones Drawings Drop Locations and Cable ID's
- (c) Communication Equipment Rooms Plan Views Tech and AMEP/Elevations Racks and Walls. Elevations with a detailed look at all telecomm rooms. Indicate technology layout (racks, ladder-racks, etc.), mechanical/electrical layout, rack elevation and backboard elevation. They may also be an enlargement of a congested area of T1 or T2 series drawing.

3.6. FINAL DESIGN REVIEWS AND CONFERENCES

A final design review and review conference will be held upon completion of final design at the project installation, or – where equipment is available - by video teleconference or a combination thereof, for any design package to receive Government acceptance to allow release of the design package for construction. For smaller separate design packages, the parties may agree on alternative reviews and conferences (e.g., conference calls and electronic file sharing, etc.) through the Partnering process. Include the final design conference in the project schedule and shall indicate what part of the design work is at 100% completion. The final design conference will be held after the Government has had seven (7) calendar days after receipt of the submission to review the final design package and supporting data. For smaller packages, especially those involving only one or a few design disciplines the parties may agree on a shorter period.

3.7. FINAL DESIGN REQUIREMENTS

Final design deliverables for a design package shall consist of 100% complete drawings, specifications, submittal register and design analyses for Government review and acceptance. The 100% design submission shall consist of drawings, specifications, updated design analyses and any permits required by the contract for each package submitted. In order to expedite the final design review, prior to the conference, ensure that the design configuration management data and all review comment resolutions are up-to-date. Include the 100% SID and 100% FF&E binders for government approval. The Contractor shall have performed independent technical reviews (ITR's) and back-checks of previous comment resolutions, as required by Section 01 45 04.00 10 CONTRACTOR QUALITY CONTROL, including providing documentation thereof.

3.7.1. Drawings

- 3.7.1.1. Submit drawings complete with all contract requirements incorporated into the documents to provide a 100% design for each package submitted.
- 3.7.1.2. Prepare all drawings with the Computer-Aided Design and Drafting (CADD)/Computer-Aided Design (CAD) system, organized and easily referenced electronically, presenting complete construction information.
- 3.7.1.3. Drawings shall be complete. The Contractor is encouraged to utilize graphics, views, notes, and details which make the drawings easier to review or to construct but is also encouraged to keep such materials to those that are necessary.
- 3.7.1.4. Provide detail drawings that illustrate conformance with the contract. Include room finish schedules, corresponding color/finish/special items schedules, and exterior finish schedules that agree with the submitted SID binders.

Section: 01 33 16 [Not Supplied] Page 74 of 151

3.7.1.5. The design documents shall be in compliance with the latest version of the A/E/C CADD Standard, available at https://cadbim.usace.army.mil/CAD. Use the approved vertical Corps of Engineers title blocks and borders on all drawings with the appropriate firm name included within the title block area.

- 3.7.1.6. CAD System and Building Information Modeling (BIM) (NOTE: If this is a Single Award or Multiple Award, Indefinite Delivery/Indefinite Quantity Contract, this information will be provided for each task order.)
- All CAD files shall be fully compatible with MicroStation V8 or higher. Save all design CAD files as MicroStation V8 or higher files. All submitted BIM Models and associated Facility Data shall be fully compatible with Bentley BIM file format and the USACE Bentley BIM v8 Workspace.
- (a) CAD Data Final File Format: During the design development capture geo-referenced coordinates of all changes made to the existing site (facility footprint, utility line installations and alterations, roads, parking areas, etc) as a result of this contract. There is no mandatory methodology for how the geo-referenced coordinates will be captured, however, Engineering and Construction Bulletin No. 2006-15, Subject: Standardizing Computer Aided Design (CAD) and Geographic Information Systems (GIS) Deliverables for all Military Design and Construction Projects identifies the format for final as-built drawings and data sets to be delivered to the government. Close-out requirements at the as-built stage; require final geo-referenced GIS Database of the new facility along with all exterior modifications. The Government will incorporate this data set into the Installation's GIS Masterplan or Enterprise GIS System. See also, Section 01 78 02.00 10 Closeout Submittals.
- (b) Electronic Drawing Files: In addition to the native CAD design files, provide separate electronic drawing files (in editable CAD format and Adobe Acrobat PDF version 7.0 or higher) for each project drawing.
- (c) Each file (both CAD and PDF) shall represent one complete drawing from the drawing set, including the date, submittal phase, and border. Each drawing file shall be completely independent of any data in any other file, including fonts and shapes not included with the basic CAD software program utilized. Drawing files with external references or special fonts are not acceptable. All displayed graphic elements on all levels of the drawing files shall be part of the project drawing image. The drawing files shall not contain any graphic element that is not part of the drawing image.
- (d) Deliver BIM Model and associated Facility Data files in their native format. At a minimum, BIM files shall address major architecture design elements, major structural components, mechanical systems and electrical/communication distribution and elements as defined in Attachment F. See Attachment F for additional BIM requirements.
- (e) Drawing Index: Provide an index of drawings sheet in CAD as part of the drawing set, and an electronic list in Microsoft Excel of all drawings on the CD. Include the electronic file name, the sheet reference number, the sheet number, and the sheet title, containing the data for each drawing.
- (f) Hard Copies: Plot submitted hard copy drawings directly from the "electronic drawing files" and copy for quantities and sizes indicated in the distribution list at the end of this specification section. The Designers of Record shall stamp, sign and date original hard copy sheets as Released For Construction, and provide copies for distribution from this set.

3.7.2. Design Analyses

- 3.7.2.1. The designers of record shall update, finalize and present design analyses with calculations necessary to substantiate and support all design documents submitted.
- 3.7.2.2. The responsible DOR shall stamp, sign and date the design analysis. Identify the software used where, applicable (name, version, vendor). Generally, provide design analyses, individually, in an original (file copy) and one copy for the assigned government reviewer.
- 3.7.2.3. All disciplines review the LEED design analysis in conjunction with their discipline-specific design analysis; include a copy of the separable LEED design analysis in all design analysis submittals.
- 3.7.2.4. Do not combine multi-disciplined volumes of design-analysis, unless multiple copies are provided to facilitate multiple reviewers (one copy per each separate design analysis included in a volume).

3.7.3. Specifications

Section: 01 33 16 [Not Supplied]
Page 75 of 151

Specifications shall be 100% complete and in final form.

3.7.4. Submittal Register

Prepare and update the Submittal Register and submit it with the 100% design specifications (see Specification Section 01 33 00, SUBMITTAL PROCEDURES) with each design package. Include the required submittals for each specification section in a design package in the submittal register.

3.7.5. Preparation of DD Form 1354 (Transfer of Real Property)

This form itemizes the types, quantities and costs of various equipment and systems that comprise the project, for the purpose of transferring the new construction project from the Corps Construction Division to the Installation's inventory of real property. The Government will furnish the DB Contractor's design manager a DD Form 1354 checklist to use to produce a draft Form 1354. Submit the completed checklist and prepared draft Form DD 1354 with the 100% design in the Design Analysis. The Corps will use these documents to complete the final DD 1354 upon completion of construction.

3.7.6. Acceptance and Release for Construction

3.7.6.1. At the conclusion of the Final Design Review (after resolutions to the comments have been agreed upon between DOR and Government reviewers), the Contracting Officer or the ACO will accept the Final Design Submission for the design package in writing and allow construction to start for that design package. The Government may withhold acceptance until all major corrections have been made or if the final design submission requires so many corrections, even though minor, that it isn't considered acceptably complete.

3.7.6.2. Government review and acceptance of design submittals is for contract conformance only and shall not relieve the Contractor from responsibility to fully adhere to the requirements of the contract, including the Contractor's accepted contract proposal, or limit the Contractor's responsibility of design as prescribed under Special Contract Requirement: "Responsibility of the Contractor for Design" or limit the Government's rights under the terms of the contract. The Government reserves the right to rescind inadvertent acceptance of design submittals containing contract deviations not separately and expressly identified in the submittal for Government consideration and approval.

3.8. DESIGN COMPLETE CONSTRUCTION DOCUMENT REQUIREMENTS

After the Final Design Submission and Review Conference and after Government acceptance of the Final Design submission, revise the design documents for the design package to incorporate the comments generated and resolved in the final review conference, perform and document a back-check review and submit the final, design complete documents. Label the final design complete documents "FOR CONSTRUCTION" or use similar language. In addition to the final drawings and specifications, the following deliverables are required for distribution and field use. The deliverable includes all documentation and supporting design analysis in final form, as well as the final review comments, disposition and the back-check. As part of the quality assurance process, the Government may perform a back-check of the released for construction documentation. Promptly correct any errors or omissions found during the Government back-check. The Government may withhold retainage from progress payments for work or materials associated with a final design package until this submittal has been received and the Government determines that it is complete.

3.9. SUBMITTAL DISTRIBUTION. MEDIA AND QUANTITIES

3.9.1. Submittal Distribution and Quantities

General: The documents which the Contractor shall submit to the Government for each submittal are listed and generally described in preceding paragraphs in this Section. Provide copies of each design submittal and design substantiation as follows (NOTE: If this is a Single Award or Multiple Award, Indefinite Delivery/Indefinite Quantity Contract, this information will be provided for each task order):

Section: 01 33 16 [Not Supplied] Page 76 of 151

Activity and Address	Drawing Size (Full Size) [Not Supplied - SubmittalR eqDistributi on: FULL SIZE] Full Sets/ *Partial Sets	Design Analyses & Specs Full Sets/ *Partial Sets	Drawing Size (Half Size) [Not Supplied Submittal ReqDistri bution: HALF SIZ E] Full Sets/ *Partial Sets	Non-BIM Data CD-ROM or DVD as Necessary (PDF& .dgn)	Furniture Submittal (Per Attachment B)	Structural Interior Design Submittal	BIM Data DVD (Per Attach F)
Commander, U.S.Army Engineer District [Not Supplied - DistrictInfoGene ral: CONSTRUCTIO N_DISTRICT]	0/0	0/0	0/0	0	1	0	0
Commander, U.S.Army Engineer District, Center of Standardization [Not Supplied - SubmittalReqDi stribution: COS]	0/0	0/0	0/0	0	N/A	0	0
Installation	0/0	0/0	0/0	0	2	0	0
U.S.Army Corps of Engineers Construction Area Office	0/0	0/0	0/0	0	1	0	0
Information Systems Engineering Command (ISEC)	0/0	0/0	0/0	1	N/A	N/A	1
Other Offices	0/0	0/0	0/0	0	N/A	0	0

^{*}NOTE: For partial sets of drawings, specifications and design analyses, see paragraph 3.9.3.3, below.

3.9.2. Web based Design Submittals

^{**}NOTE: When specified below in 3.9.2, furnish Installation copies of Drawings as paper copies, in lieu of the option to provide secure web-based submittals.

Section: 01 33 16 [Not Supplied]
Page 77 of 151

Web based design submittals will be acceptable as an alternative to the paper copies listed in the Table above, provided a single hard-copy PDF based record set is provided to the Contracting Officer for record purposes. Where the contract requires the Contractor to submit documents to permitting authorities, still provide those authorities paper copies (or in an alternate format where required by the authority). Web based design submittal information shall be provided with adequate security and availability to allow unlimited access those specifically authorized to Government reviewers while preventing unauthorized access or modification. File sizes must be of manageable size for reviewers to quickly download or open on their computers. As a minimum, drawings shall be full scale on American National Standards Institute (ANSI) D sheets (34" x 22"). In addition to the optional website, provide the BIM data submission on DVD to each activity and address noted above in paragraph 3.9.1 for each BIM submission required in Attachment F.

3.9.3. Mailing of Design Submittals

- 3.9.3.1. Mail all design submittals to the Government during design and construction, using an overnight mailing service. The Government will furnish the Contractor addresses where each copy shall be mailed to after award of the contract (or individual task order if this is an indefinite delivery/indefinite quantity, task order contract). Mail the submittals to zero (0) different addresses. Assemble drawing sheets, specs, design analyses, etc. into individual sets; do not combine duplicate pages from individual sets so that the government has to assemble a set.
- 3.9.3.2. Each design submittal shall have a transmittal letter accompanying it indicating the date, design percentage, type of submittal, list of items submitted, transmittal number and point of contact with telephone number.
- 3.9.3.3. Provide partial sets of drawings, specifications, design analyses, etc., as designated in the Table in paragraph 3.9.1, to those reviewers who only need to review their applicable portions of the design, such as the various utilities. The details of which office receives what portion of the design documentation will be worked out after award.

3.10. AS-BUILT DOCUMENTS

Provide as-built drawings and specifications in accordance with Section 01 78 02.00 10, CLOSEOUT SUBMITTALS. Update LEED design phase documentation during construction as needed to reflect construction changes and advancing project completion status (example - Commissioning Plan updates during construction phase) and include updated LEED documentation in construction closeout submittal.

Section: 01 33 16 [Not Supplied] Page 78 of 151

ATTACHMENT A STRUCTURAL INTERIOR DESIGN (SID) REQUIREMENTS

1.0 GENERAL INFORMATION

Structural Interior Design includes all building related elements and components generally part of the building itself, such as wall finishes, ceilings finishes, floor coverings, marker/bulletin boards, blinds, signage and built in casework. Develop the SID in conjunction with the furniture footprint.

2.0 STRUCURAL INTERIOR DESIGN (SID) REQUIREMENTS FOR THE INTERIM AND FINAL DESIGN SUBMITTALS

2.1. FORMAT AND SCHEDULE

Prepare and submit for approval an interior and exterior building finishes scheme for an interim design submittal. The DOR shall meet with and discuss the finish schemes with the appropriate Government officials prior to preparation of the schemes to be presented. Present original sets of the schemes to reviewers at an interim design conference.

At the conclusion of the interim phase, after resolutions to the comments have been agreed upon between DOR and Government reviewers, the Contractor may proceed to final design with the interior finishes scheme presented.

The SID information and samples are to be submitted in 8 ½" x 11" format using three ring binders with pockets on the inside of the cover. When there are numerous pages with thick samples, use more than one binder. Large Dring binders are preferred to O-ring binders. Use page protectors that are strong enough to keep pages from tearing out. Anchor large or heavy samples with mechanical fasteners, Velcro, or double-faced foam tape rather than rubber cement or glue. Fold out items must have a maximum spread of 25 ½". Provide cover and spine inserts sheets identifying the document as "Structural Interior Design" package. Include the project title and location, project number, Contractor/A/E name and phone number(s), submittal stage and date.

Design submittal requirements include, but are not limited to:

2.1.1. Narrative of the Structural Interior Design Objectives

The SID shall include a narrative that discusses the building related finishes. Include topics that relate to base standards, life safety, sustainable design issues, aesthetics, durability and maintainability, discuss the development and features as they relate to the occupants requirements and the building design.

2.1.2. Interior Color Boards

Identify and key each item item on the color boards to the contract documents to provide a clear indication of how and where each item will be used. Arrange finish samples to the maximum extent possible by room type in order to illustrate room color coordination. Label all samples on the color boards with the manufacturer's name, patterns and colors name and number. Key or code samples to match key code system used on contract drawings.

Material and finish samples shall indicate true pattern, color and texture. Provide photographs or colored photocopies of materials or fabrics to show large overall patterns in conjunction with actual samples to show the actual colors. Finish samples must be large enough to show a complete pattern or design where practical.

Color boards shall include but not be limited to original color samples of the following:

All walls finishes and ceiling finishes, including corner guards, acrylic wainscoting and wall guards/chair rail finishes

All tile information, including tile grout color and tile patterns.

- All flooring finishes, including patterns.
- All door, door frame finishes and door hardware finishes
- All signage, wall base, toilet partitions, locker finishes and operable/folding partitions and trim

Section: 01 33 16 [Not Supplied]
Page 79 of 151

- All millwork materials and finishes (cabinets, counter tops, etc.)
- All window frame finishes and window treatments (sills, blinds, etc.)

Color board samples shall reflect all actual finish textures, patterns and colors required as specified. Patterned samples shall be of sufficient size to adequately show pattern and its repeat if a repeat occurs.

2.1.3. Exterior Color Boards

Prepare exterior finishes color boards in similar format as the interior finishes color boards, for presentation to the reviewers during an interim design conference. Provide original color samples of all exterior finishes including but not limited to the following:

- All Roof Finishes
- All Brick and Cast Stone Samples
- All Exterior Insulation and Finish Samples
- All Glass Color Samples
- All Exterior Metals Finishes
- All Window & Door Frame Finishes
- All Specialty Item Finishes, including trim

Identify each item on the exterior finishes color boards and key to the building elevations to provide a clear indication of how and where each item will be used.

2.2. STRUCTURAL INTERIOR DESIGN DOCUMENTS

2.2.1. General

Structural interior design related drawings must indicate the placement of extents of SID material, finishes and colors and must be sufficiently detailed to define all interior work. The following is a list of minimum requirements:

2.2.2. Finish Color Schedule

Provide finish color schedule(s) in the contract documents. Provide a finish code, material type, manufacturer, series, and color designations. Key the finish code to the color board samples and drawings.

2.2.3. Interior Finish Plans

Indicate wall and floor patterns and color placement, material transitions and extents of interior finishes.

2.2.4. Furniture Footprint Plans

Provide furniture footprint plans showing the outline of all freestanding and systems furniture for coordination of all other disciplines.

2.2.5. Interior Signage

Include interior signage plans or schedules showing location and quantities of all interior signage. Key each interior sign to a quantitative list indicating size, quantity of each type and signage text.

2.2.6. Interior Elevations, Sections and Details

Indicate material, color and finish placement.

Section: 01 33 16 [Not Supplied]
Page 80 of 151

ATTACHMENT B FURNITURE, FIXTURES & EQUIPMENT (FF&E) REQUIREMENTS

1.0 FF&E REQUIREMENTS FOR THE INTERIM AND FINAL DESIGN SUBMITTALS

1.1. FORMAT AND SCHEDULE

Prepare and submit for approval a comprehensive FF&E scheme for an interim design submittal. The Contractor's interior designer, not a furniture dealer, shall develop the design. FF&E is the selection, layout, specification and documentation of furniture includes but is not limited to workstations, seating, tables, storage and shelving, filing, trash receptacles, clocks, framed artwork, artificial plants, and other accessories. Contract documentation is required to facilitate pricing, procurement and installation. The FF&E package is based on the furniture footprint developed in the Structural Interior Design (SID) portion of the interior design. Develop the FF&E package concurrently with the building design to ensure that there is coordination between the electrical outlets, switches, Jboxes, communication outlets and connections, and lighting as appropriate. In addition, coordinate layout with other building features such as architectural elements, thermostats, location of TV's, GF/GI equipment (for example computers, printers, copiers, shredders, faxes), etc. Locate furniture in front of windows only if the top of the item falls below the window and unless otherwise noted, do not attach furniture including furniture systems to the building. If project has SIPRNET and/or NIPRNET, coordinate furniture layout with SIPRNET and NIPRNET separation requirements. Verify that access required by DOIM for SIPRNET box and conduit is provided. The DOR shall interview appropriate Government personnel to determine FF&E requirements for furniture and furnishings prior to preparation of the scheme to be presented. Determine FFE items and quantities by, but not limited to: (1) the number of personnel to occupy the building, (2) job functions and related furniture/office equipment to support the job function, (3) room functions, (4) rank and grade. Present original sets of the scheme to reviewers at an interim design conference upon completion of the interim architectural submittal or three months prior to the submittal of the final FF&E package (whichever comes first).

Design may proceed to final with the FF&E scheme presented at the conclusion of the interim phase, after resolutions to the comments have been agreed upon between DOR and Government reviewers.

Provide six copies of the electronic versions of all documents upon completion of the final architectural submittal or ten months prior to the contract completion date (whichever comes first), to ensure adequate time for furniture acquisition. Provide unbound, electronic drawings in CAD and BIM. Provide all files needed to v,/iew complete drawings. Submit all text documents in Microsoft Word or Excel..

Submit four copies of the final and complete FF&E information and samples in 8 ½" x 11" format using three ring binders with pockets on the inside of the cover upon completion of the final architectural submittal or ten months prior to the contract completion date (whichever comes first). Use more than one binder when there are numerous pages with thick samples. Large D-ring binders are preferred to O-ring binders. Use page protectors that are strong enough to keep pages from tearing out for upholstery and finish boards. Anchor large or heavy samples with mechanical fasteners, Velcro, or double-faced foam tape rather than rubber cement or glue. Fold out items must have a maximum spread of 25 ½". Provide cover and spine inserts sheets identifying the document as "Furniture, Fixtures & Equipment" package and include the project title and location, project number, Contractor/A/E name and phone number(s), submittal stage and date.

Provide electronic copies of all documents upon completion of the final architectural submittal or ten months prior to the contract completion date (whichever comes first), to ensure adequate time for furniture acquisition. Provide six compact disks with all drawings files needed to view the complete drawings unbound and in the latest version AutoCAD. Provide six additional compact disks of all text documents in Microsoft Word or Excel.

Design submittal requirements include, but are not limited to:

1.1.1. Narrative of Interior Design Objectives

Provide a narrative description of the furniture, to include functional, safety and ergonomic considerations, durability, sustainability, aesthetics, and compatibility with the building design.

1.1.2. Furniture Order Form

Section: 01 33 16 [Not Supplied]
Page 81 of 151

Prepare one Furnishings Order Form for each item specified in the design. This form identifies all information required to order each individual item. In addition to the project name and location, project number, and submittal phase, the order form must include:

- (a) Furniture item illustration and code
- (b) Furniture item name
- (c) Job name, location, and date
- (d) General Services Administration (GSA) FSC Group, part, and section
- (e) Manufacturer, Product name and Product model number or National Stock Number (NSN)
- (f) Finish name and number (code to finish samples)
- (g) Fabric name and number, minimum Wyzenbeek Abrasion Test double rubs (code to fabric samples)
- (h) Dimensions
- (i) Item location by room number and room name
- (j) Quantity per room
- (k) Total quantity
- (I) Special instructions for procurement ordering and/or installation (if applicable)
- (m) Written Product Description: include a non-proprietary paragraph listing the salient features of the item to include but not limited to:
 - (1) required features and characteristics
 - (2) ergonomic requirements
 - (3) functional requirements
 - (4) testing requirements
 - (5) furniture style
 - (6) construction materials
 - (7) minimum warranty

The following is an example for "m" features and characteristics, ergonomic requirements and functional requirements:

Chair Description:

- (1) Mid-Back Ergonomic Task Chair
- (2) Pneumatic Gaslift; Five Star Base
- (3) Mesh Back; Upholstered Seat
- (4) Height and Width Adjustable Task Arms:
 - a. Arm Height: 6"- 11" (+-1/2")
 - b. Arm Width: 2"-4" adjustment
- (5) Height Adjustable Lumbar Support
- (6) Adjustable Seat Height 16"-21" (+- 1")
- (7) Sliding Seat Depth Adjustment 15"-18" (+-1")
- (8) Standard Hard Casters (for carpeted areas)
- (9) Overall Measurements:
 - a. Overall width: 25" 27"
 - b. Overall depth: 25"–28"

Section: 01 33 16 [Not Supplied]
Page 82 of 151

- (10) Must have a minimum of the following adjustments (In addition to the above):
 - a. 360 Degree Swivel
 - b. Knee-Tilt with Tilt Tension
 - c. Back angle
 - d. Forward Tilt
 - e. Forward Tilt and Upright Tilt Lock

For projects with systems furniture, also provide a written description of the following minimum requirements:

- (1) Type furniture systems (panel, stacking panels, spine wall, desk based system, or a combination)
- (2) Minimum noise reduction coefficient (NRC)
- (3) Minimum sound transfer coefficient (STC)
- (4) Minimum flame spread and smoke development
- (5) UL testing for task lighting and electrical system
- (6) Panel widths and heights and their locations (this may be done on the drawings)Worksurface types and sizes (this may be done on the drawings)
- (7) Worksurface edge type
- (8) Varying panel/cover finish materials and locations (locations may be shown on the drawings)
- (9) Storage requirements
- (10) Keyboard requirements
- (11) Lock and keying requirements
- (12) Accessory components (examples: tack boards, marker boards, paper management)
- (13) Electrical and communication raceway requirement; type, capacity and location (base, beltline, below and/or above beltline)
- (14) Locations of communication cables (base, beltline, below and/or above beltline, top channel)
- (15) Types of electrical outlets
- (16) Types of communication jacks; provided and installed by others
- (17) Locations of electrical outlets and communication jacks (this may be done on the drawings)
- (18) Type of cable (examples: Cat. 5, Cat. 6, fiber optic; UTP or STP, etc.) system needs to support; provided and installed by others

1.1.3. Alternate Manufacturer List

Provide a table consisting of major furniture items that lists the manufacturers products specified on the Order Form and two alternate manufacturers. Major furniture items include, but are not limited to, casegoods, furniture systems, seating, and tables. Organize matrix by item code and item name. Supply alternates that are available on GSA Schedule and meet the requirements of the Furniture Order Form. One of the two alternates must be from UNICOR if possible. Provide manufacturer name address, telephone number, product series and product name for each alternate manufacturer.

1.1.4. FF&E Procurement List

Provide a table that lists all FF&E furniture, mission unique equipment and building Contractor Furnished/Contractor Installed (CF/CI) items. Give each item a code and name and designate whether item will be procured as part of the FF&E furniture, mission unique equipment or the building construction contract. Use the item code to key all FF&E documents including location plans, color boards, data sheets, cost estimate, etc.

1.1.5. Points of Contact (POCs)

Section: 01 33 16 [Not Supplied]
Page 83 of 151

Provide a comprehensive list of POCs needed to implement the FF&E package. This would include but not be limited to appropriate project team members, using activity contacts, interior design representatives, construction contractors and installers involved in the project. In addition to name, address, phone, fax and email, include each contact's job function. Divide the FF&E package into different sections based on this listing, applies to order forms and cost estimates.

1.1.6. Color Boards

Provide color boards for all finishes and fabrics for all FF&E items. Finishes to be included but not limited to paint, laminate, wood finish, fabric, etc.

1.1.7. Itemized Furniture Cost Estimate

Provide an itemized cost estimate of furnishings keyed to the plans and specifications of products included in the package. This cost estimate should be based on GSA price schedules. The cost estimate must include separate line items for general contingency, installation, electrical hook-up for systems furniture or other furniture requiring hardwiring by a licensed electrician, freight charges and any other related costs. Installation and freight quotes from vendors should be use in lieu of a percentage allowance when available. Include a written statement that the pricing is based on GSA schedules. An estimate developed by a furniture dealership may be provided as support information for the estimate, but must be separate from the contractor provided estimate.

1.2. INTERIOR DESIGN DOCUMENTS

1.2.1. Overall Furniture and Area Plans

Provide floor Plans showing locations and quantities of all freestanding, and workstation furniture proposed for each floor of the building. Key each room to a large scale Furniture Placement Plan showing the furniture configuration, of all furniture. Provide enlarged area plans with a key plan identifying the area in which the building is located. Key all the items on the drawings by furniture item code. Do not provide manufacturer specific information such as product names and numbers on drawings, Drawings shall be non-proprietary. This is typical for FFE on all plans, including those mentioned below.

1.2.2. Workstation Plans

Show each typical workstation configuration in plan view, elevations or isometric view. Drawings shall illustrate panels and all major components for each typical workstation configuration. Identify workstations using the same numbering system as shown on the project drawings. Key components to a legend on each sheet which identifies and describes the components along with dimensions. Provide the plan, elevations and isometric of each typical workstation together on the same drawing sheet.

1.2.3. Panel Plans

Show panel locations and critical dimensions from finished face of walls, columns, panels including clearances and aisle widths. Key panel assemblies to a legend which shall include width, height, configuration of frames, panel fabric and finishes (if there are different selections existing within a project), powered or non-powered panel and wall mount locations.

1.2.4. Desk Plans

Provide typical free standing desk configurations in plan view, elevation or isometric view and identify components to clearly represent each desk configuration.

1.2.5. Reflected Ceiling Plans

Provide typical plans showing ceiling finishes and heights, lighting fixtures, heating ventilation and air conditioning supply and return, and sprinkler head placement for coordination of furniture.

1.2.6. Electrical and Telecommunication Plans

Section: 01 33 16 [Not Supplied] Page 84 of 151

Show power provisions including type and locations of feeder components, activated outlets and other electrical componentsShow locations and quantities of outlets for workstations. Clearly identify different outlets, i.e. electrical, LAN and telecommunication receptacles indicating each type proposed. Show wiring configuration, (circuiting, switching, internal and external connections) and provide as applicable.

1.2.7. Artwork Placement Plans

Provide an Artwork Placement Plan to show location of artwork, assign an artwork item code to each piece of artwork. As an alternative, artwork can be located on the Furniture Plans. Provide a schedule that identifies each piece by room name and number. Provide installation instructions; include mounting height.

1.2.8. Window Drapery Plans

Provide Interior Window Drapery Plans. Key each drapery treatment to a schedule showing color, pattern, material, drapery size and type, draw direction, location and quantities.

1.3. FURNITURE SELECTION

- 1.3.1. Select furniture from the GSA Schedules. Specify furniture available open market when an item is not available on the GSA Schedules. Provide justification fort items not available on the GSA Schedules.
- 1.3.2. To the greatest extent possible when specifying furniture work within a manufacturer's family of furniture for selections, example: Steelcase, Turnstone, Brayton International, Metro, and Vecta are all Steelcase companies. Each alternate should also be specified from a manufacturer's family of furniture, example: first set of alternates would be specified from Knoll's family of furniture and the second from Herman Miller family of furniture. It may be necessary to make some selections from other than a manufacturer's family of furniture if costs are not reasonable for particular items, some items are not available or appropriate for the facility or the items are not on GSA Schedule. If this occurs, consider specifying product from an open line that is accessible by numerous dealerships. Select office furniture including case goods, tables, storage, seating, etc. that is compatible in style, finish and color. Select furniture that complies with ANSI/BIFMA and from manufacturer's standard product line as shown in the most recent published price list and/or amendment and not custom product.

1.4. CONSTRUCTION

- 1.4.1. Provide knee space at workstations and tables that is not obstructed by panels/legs that interfere with knee space of seated person and specificy modesty panels at walls to be of a height or be hinged to allow access to building wall electrical outlets and communication jacks. Provide desks, storage and tables with leveling devices to compensate for uneven floors.
- 1.4.2. Specify workstations and storage of steel construction. Provide worksurface tops constructed to prevent warpage. Provide user friendly features such as radius edges. Do not use sharp edges and exposed connections and ensure the underside of desks, tables and worksurfaces are completely and smoothly finished. Provide abutting worksurfaces that mate closely and are of equal heights when used in side-by-side configurations in order to provide a continuous and level worksurface.
- 1.4.3. Drawers shall stay securely closed when in the closed position and protect wires from damage during drawer operation. Include a safety catch to prevent accidental removal when fully open
- 1.4.4. Unless otherwise noted, provide lockable desks and workstations, filing cabinets and storage. Key all locks within a one person office the same; key all one person offices within a building differently. If an office or open office area has more than one workstation, key all the workstations differently, but key all locks within an individual workstation the same. Use tempered glass glazing when glazing is required. Use light-emitting diode (LED)/solid state lighting where task lighting is required in furniture.

1.5. FINISHES AND UPHOLSTERY

1.5.1. Specify neutral colors for casegoods, furniture systems, storage and tables. Specify desk worksurfaces and table tops that are not too light or too dark in color and have a pattern to help hide soiling. Accent colors are

Section: 01 33 16 [Not Supplied]
Page 85 of 151

allowed in break and lounge areas. Keep placement of furniture systems panel fabric accent colors to a minimum. All finishes shall be cleanable with ordinary household cleaning solutions.

- 1.5.2. Use manufacturer's standard fabrics; including textile manufacturers fabrics that have been graded into the furniture manufactures fabric grades and are available through their GSA Schedule. Customers Own Material (COM) can be used in headquarter buildings in command suites with executive furniture. Coordinate specific locations with Corps of Engineers Interior Designer.
- 1.5.3. Specify seating upholstery that meets Wyzenbeek Abrasion Test, 55,000 minimum rubs. Specify a soil retardant finish for woven fabrics if Crypton or vinyl upholstery is not provided for seating in dining areas. Use manufacturer's standard fabrics. This includes textile manufacturers fabrics that have been graded into the furniture manufactures fabric grades and are available through their GSA Schedule. Specify upholstery and finish colors and patterns that help hide soiling. Specify finishes that can be cleaned with ordinary household cleaning solutions.

1.6. ACCESSORIES

- 1.6.1. Specify all accessories required for completely finished furniture installation. Provide filing cabinets and storage for office supplies. Provide tack surfaces at workstations with overhead storage. Provide tackable surfaces at workstations with overhead storage.
- 1.6.2. Not Used.
- 1.6.3. Workstations are to be equipped with stable keyboard trays that have height adjustability, tilting capability, including negative tilt, have a mouse pad at same height as the keyboard tray that can accommodate both left and right handed users, and retractable under worksurface.

1.7. MISSION UNIQUE EQUIPMENT

Funding for FF&E furniture items and mission unique equipment (MUE) items are from two different sources. Separate the designs and procurement documentation for FFE items and MUE. MUE includes, but is not limited to, items such as industrial shelving, workbenches, appliances, fitness equipment, IT equipment and supporting carts. The User will purchase and install mission unique equipment items, unless otherwise noted. Identify locations of known MUE items such as industrial shelving, workbenches, appliances, etc. for space planning purposes.

1.8. SUSTAINABILITY

- 1.8.1. For all designs provided regardless of facility type, make every effort to implement all aspects of sustainability to the greatest extent possible for all the selections made in the FF&E package. This includes but is not limited to the selection of products that consider: **Material Chemistry and Safety of Inputs** (What chemicals are used in the construction of the selections?); **Recyclability** (Do the selections contain recycled content?); **Disassembly** (Can the selections be disassembled at the end of their useful life to recycle their materials?).
- 1.8.2. Make selections to the greatest extent possible of products that possess current McDonough Braungart Design Chemistry (MBDC) certification or other "third-party" certified Cradle to Cradle program, Forest Stewardship Council (FSC) certification, GREENGAURD certification or similar "third-party" certified products consisting of low-emitting materials.

1.9. FURNITURE SYSTEMS

1.9.1. General.

Where appropriate, design furniture systems in open office areas. Coordinate style and color of furniture systems with other storage, seating, etc. in open office areas. Minimize the number of workstation typicals and the parts and pieces required for the design to assist in future reconfiguration and inventorying.

1.9.2. Connector Systems.

Specify a connector system that allows removal of a single panel or spine wall within a typical workstation configuration without requiring disassembly of the workstation or removal of adjacent panels. Specify connector

Section: 01 33 16 [Not Supplied]
Page 86 of 151

system with tight connections and continuous visual seals. When Acoustical panels are used, provide connector system with continuous acoustical seals. Specify concealed clips, screws, and other construction elements, where possible.

1.9.3. Panels and Spine Walls

Specify panels and spine walls with hinged or removable covers that permit easy access to the raceway when required but are securely mounted and cannot be accidentally dislodged under normal conditions. Panels shall be capable of structurally supporting more than 1 fully loaded component per panel per side. Raceways are to be an integral part of the panel and must be able to support lay-in cabling and have a large capacity for electrical and IT. Do not thread cables through the frame.

1.9.4. Electrical And Information/Technology (IT)

Design furniture with electrical systems that meets requirements of UL 1286 when powered panels are required and UL approved task lights that meet requirements of NFPA 70. Dependent on user requirements and Section 01 10 00, paragraph 3 requirements, it is recommended that workstation electrical and IT wiring entry come from the building walls to eliminate the use of power poles and access at the floor. Design electrical and IT systems that are easily accessed in the spine wall and panels without having to move return panels and components. Electrical and IT management will be easily accessible by removable wall covers which can be removed while workstation components are still attached. Specify connector system that has continuation of electrical and IT wiring within workstations and workstation to workstation.

1.9.5. Pedestals

Specify pedestals that are interchangeable from left to right, and right to left, and retain pedestal locking system capability.

1.10. EXECUTIVE FURNITURE

- 1.10.1. Design for executive furniture in command areas, coordinate specific locations with Corps of Engineers Interior Designer. Use upgraded furniture, upholsteries and finishes in command suites. This includes but is not limited to wood casegoods, seating and tables. Select executive furniture casegoods from a single manufacturer and style line, to include workstations, credenzas, filing, and storage, etc.
- 1.10.2. Specify furniture with wood veneer finish (except worksurfaces) with mitered solid wood edge of same wood type. Provide worksurface plastic laminate that closely matches adjacent wood veneer. Other executive office furniture such as seating, tables, executive conference room furniture, etc. shall be compatible in style, finish and color with executive furniture casegoods.

1.11. SEATING

1.11.1. General

Specify appropriate chair casters and glides for the floor finish where the seating is located. Universal casters that are appropriate for both hard surface flooring and carpet are preferred. All seating shall support up to a minimum of 250 lbs.

1.11.2. Desk and Guest Seating

Select ergonomic desk chairs with casters, non-upholstered adjustable arms, waterfall front, swivel, tilt, variable back lock, adjustable back height or adjustable lumbar support, pneumatic seat height adjustment, and padded, contoured upholstered seat and back. Desk and guest chair backs may be other than upholstered such as mesh fabric if it is ergonomically designed, forms to back and is comfortable. Depending on scale of desk chair provide seat pan forward and back adjustment to increase or decrease depth of seat pan. All desk chairs shall have an adjustable seat height range of 4 1/2", range to include 16 1/2-20". Select guest chairs that are compatible in style, finish and color with the desk chairs.

1.11.3. Conference Room Seating

Section: 01 33 16 [Not Supplied]
Page 87 of 151

At tables, select ergonomic conference seating with casters, non-upholstered arms, waterfall front, swivel, tilt, pneumatic seat height adjustment, and padded, contoured seat and back, unless otherwise noted. Select arm height and/or design that allows seating to be moved up closely to the table top. Conference chair backs may be other than upholstered such as mesh fabric if it is ergonomically designed, forms to back and is comfortable. Perimeter conference chairs shall be compatible in style, finish and color with conference seating at the tables.

1.11.4. Lounge, Waiting and Reception Area Seating

Select seating with arms and cushioned, upholstered seat and back. In heavy use areas, arms shall be easily cleaned such as non-upholstered arms or upholstered arms with wood arm caps unless otherwise noted.

1.11.5. Break Room Seating

Select stackable seating that is easily cleaned. Seating shall be appropriate for table and counter heights as applicable with non-upholstered arms if arms are required. Chairs shall have metal legs and composite materials for seats.

1.11.6. Lounge, Waiting and Reception Furniture.

Design for end and coffee tables with plastic laminate tops that are compatible in style finish and color with the seating.

1.12. FILING AND STORAGE.

Select storage and shelving units that meet customer's functional load requirements for stored items. Specify counterweights for filing cabinets when required by the manufacturer for stability. File drawers shall allow only one drawer to be opened at a time. Provide heavy duty storage and shelving if information is not available.

1.13. TRAINING TABLES.

Don't use plastic laminate self edge. Training tables shall be reconfigurable, moveable and storable; lighter weight folding with dollies or castered as necessary. Specify dollies if required.

1.14. FURNITURE WARRANTIES.

Specify manufacturer's performance guarantees or warranties that include parts, labor and transportation as follows:

Furniture System, unless otherwise noted – 10 year minimum
Furniture System Task Lights – 2 year minimum, excluding bulbs
Furniture System Fabric – 3 year minimum
Desks - 10 year minimum
Seating, unless otherwise noted - 10 year minimum
Seating Mechanisms and Pneumatic Cylinders - 10 years
Fabric - 3 years minimum
Filing and Storage - 10 year minimum
Tables, unless otherwise noted - 10 year minimum
Table Mechanisms – 5 year
Table Ganging Device - 1 year
Items not listed above - 1 year minimum

Section: 01 33 16 [Not Supplied]
Page 88 of 151

ATTACHMENT C TRACKING COMMENTS IN DRCHECKS

1.0 General

The Government and DB Contractor shall set up the project in Dr Checks. Throughout the design process, the parties shall enter, track, and back-check comments using the DrChecks system. Government reviewers enter design review comments into DrChecks. Designers of Record shall annotate comments timely and specifically to indicate exactly what action will be taken or why the action is not required. Comments considered critical by the conference participants shall be flagged as such.

2.0 DrChecks Review Comments

The Contractor and the Government shall monitor DrChecks to assure all comments are annotated and agreed to by the designers and reviewers prior to the next submittal. The DrChecks comments and responses shall be printed and included in the design analysis for record.

- 2.1. Conference participants (reviewers) will expect coordination between Design Analysis calculations and the submitted design. Reviewers will also focus on the design submittal's satisfaction of the contract requirements.
- 2.2. The Designers of Record shall answer each comment in DrChecks with a formal response prior to the next submittal, clearly indicating what action will be taken and what drawing/spec will change. Designers of Record are encouraged to directly contact reviewers to discuss and agree to the formal comment responses rather than relying only on DrChecks and review meetings to discuss comments. With the next design conference, reviewers will back-check answers to the comments against the submittal, in addition to reviewing additional design work.
- 2.3. Comments that, in the DB Contractor's opinion, require effort outside the scope of the contract shall be clearly indicated as such in DrChecks. The DB Contractor shall not proceed with work outside the contract until a modification to the contract is properly executed, if one is necessary.

3.0 DrChecks Initial Account Set-Up

To initialize an office's use of DrChecks, choose a contact person within the office to call the DrChecks Help Desk at 800-428-HELP, M-F, 8AM-5PM, Central time. This POC will be given an office password to distribute to others in the office. Individuals can then go to the hyperlink at http://www.projnet.org and register as a first time user. Upon registration, each user will be given a personal password to the DrChecks system.

3.1. Once the office and individuals are registered, the COE's project manager or lead reviewer will assign the individuals and/or offices to the specific project for review. At this point, persons assigned can make comments, annotate comments, and close comments, depending on their particular assignment.

4.0 DrChecks Reviewer Role

The Contractor is the technical reviewer and the Government is the compliance reviewer of the DB designers design documents. Each reviewer enters their own comments into the Dr Checks system. To enter comments:

- 4.1. Log into DrChecks.
- 4.2. Click on the appropriate project.
- 4.3. Click on the appropriate review conference. An Add comment screen will appear.
- 4.4. Select or fill out the appropriate sections (particularly comment discipline and type of document for sorting) of the comment form and enter the comment in the space provided.
- 4.5. Click the Add Comment button. The comment will be added to the database and a fresh screen will appear for the next comment you have.

Section: 01 33 16 [Not Supplied]
Page 89 of 151

4.6. Once comments are all entered, exit DrChecks by choosing "My Account" and then Logout.

5.0 DrChecks Comment Evaluation

The role of the designers of record is to evaluate and respond to the comments entered by the Government reviewers and by the DB Contractor. To respond to comments:

- 5.1. Log into DrChecks.
- 5.2. Click on the appropriate project.
- 5.3. Under "Evaluate" click on the number under "Pending".
- 5.4. Locate the comments that require your evaluation. (Note: If you know the comment number you can use the Quick Pick window on your home page in DrChecks; enter the number and click on go.)
- 5.5. Select the appropriate evaluation (concur, non-concur, for information only, or check and resolve) and add the response.
- 5.6. Click on the Add button. The evaluation will be added to the database and a fresh screen will appear with the next comment.
- 5.7. Once evaluations are all entered, exit DrChecks by choosing "My Account" and then Logout.

6.0 DrChecks Back-check

At the following design conference, participants will back-check comment annotations against newly presented documents to verify that the designers' responses are acceptable and completed. The Contractor and Government reviewers shall either enter additional back-check comments, as necessary or close those that are resolved as a result of the design conferences:

- 6.1. Log into DrChecks.
- 6.2. Click on the appropriate project.
- 6.3. Under "My Backcheck" click on the number under "Pending".
- 6.4. If you agree with the designer's response select "Close Comment" and add a closing response if desired.
- 6.5. If you do not agree with the designer's response or the submittal does not reflect the response given, select "Issue Open". enter additional information.
- 6.6. Click on the Add button. The back-check will be added to the database and a fresh screen will appear with the next comment.
- 6.7. Once back-checks are all entered, exit DrChecks by choosing "My Account" and then Logout. The design is completed and final when there are no pending comments to be evaluated and there are no pending or open comments under back-check.

Section: 01 33 16 [Not Supplied]
Page 90 of 151

ATTACHMENT D SAMPLE FIRE PROTECTION AND LIFE SAFETY CODE REVIEW

Instructions: Use the information outlined in this document to provide the minimum requirement for development of Fire Protection and Life Safety Code submittals for all building projects. Additional and supplemental information may be used to further develop the code review. Insert N/A after criteria, which may be "not applicable".

1.0	SAMPLE FIRE PROTECTION AND LIFE SAFETY CODE REVIEW
1.1.	Project Name (insert name and location)
1.2.	Applicable Codes and Standards
1.2.1.	Unified Facilities Criteria (UFC): 3-600-01, Design: Fire Protection Engineering For Facilities
1.2.2. limitatior	International Building Code (IBC) for fire resistance requirements, allowable floor area, building height as and building separation distance requirements, except as modified by UFC 3-600-01.
1.2.3. and life s	National Fire Protection Association (NFPA) 101 Life Safety Code (latest edition), for building egress safety and applicable criteria in UFC 3-600-01.
1.2.4. for facilit	ADA and ABA Accessibility Guidelines. For Buildings and Facilities See Section 01 10 00, Paragraph 3 by specific criteria.
1.3. IBC cha	Occupancy Classification pters 3 and 4
1.4. IBC cha	Construction Type pter 6
1.5. IBC cha	Area Limitations pter 5, table 503
1.6. IBC sect	Allowable Floor Areas tion 503, 505
1.7. IBC sect	Allowable area increases tion 506, 507
1.8. IBC sect	Maximum Height of Buildings tion 504
1.9.	Fire-resistive substitution
1.10. IBC table	Occupancy Separations e 302.3.2
1.11.	Fire Resistive Requirements
1.11.1.	Exterior Walls - [] hour rating, IBC table 601, 602
1.11.2.	Interior Bearing walls - [] hour rating
1.11.3.	Structural frame - [] hour rating

1.11.4.

Permanent partitions - [____] hour rating

Section: 01 33 16 [Not Supplied]
Page 91 of 151

- 1.11.5. Shaft enclosures [____] hour rating1.11.6. Floors & Floor-Ceilings [___] hour rating
- 1.11.7. Roofs and Roof Ceilings [] hour rating
- 1.12. Automatic Sprinklers and others used to determine the need for automatic Extinguishing Equipment, Extinguishing Systems, Foam Systems, Standpipe
- 1.12.1. UFC 3-600-01, chapters 4 and 6 systems, wet chemical systems, etc. State which systems are required and to what criteria they will be designed.
- 1.12.2. UFC 3-600-01, Appendix B Occupancy Classification. Note the classification for each room. This may be accomplished by classifying the entire building and noting exceptions for rooms that differ (E.g. The entire building is Light Hazard except boiler room and storage rooms which are [_____], etc.)
- 1.12.3. UFC 3-600-01, Chapter 3 Sprinkler Design Density, Sprinkler Design Area, Water Demand for Hose Streams (supply pressure and source requirements).
- 1.12.4. UFC 3-600-01, Chapter 4 Coverage per sprinkler head. Extended coverage sprinkler heads are not permitted.
- 1.12.5. Available Water Supply. Provide the results of the water flow tests showing the available water supply static pressure and residual pressure at flow. Based on this data and the estimated flow and pressure required for the sprinkler system, determine the need for a fire pump.
- 1.12.6. NFPA 13, Para. 8.16.4.6.1. Provide backflow preventer valves as required by the local municipality, authority, or water purveyor. Provide a test valve located downstream of the backflow preventer for flow testing the backflow preventer at full system demand flow. Route the discharge to an appropriate location outside the building.
- 1.13. Kitchen Cooking Exhaust Equipment

Describe when kitchen cooking exhaust equipment is provided for the project. Type of extinguishing systems for the equipment should be provided. per NFPA 96. Show all interlocks with manual release switches, fuel shutoff valves, electrical shunt trips, exhaust fans, and building alarms.

- 1.14. Portable Fire Extinguishers, fire classification and travel distance. per NFPA 10
- 1.15. Enclosure Protection and Penetration Requirements. Opening Protectives and Through Penetrations
- 1.15.1. IBC Section712, 715 and Table 715.3. Mechanical rooms, exit stairways, storage rooms, janitor hour rating. IBC Table 302.1.1
- 1.15.2. Fire Blocks, Draft Stops, Through Penetrations and Opening Protectives
- 1.16. Fire Dampers. Describe where fire dampers and smoke dampers are to be used (IBC Section 716 and NFPA 90A). State whether isolation smoke dampers are required at the air handler.
- 1.17. Detection Alarm and Communication. UFC 3-600-01, (Chapter 5); NFPA 101 para. 3.4 (chapters 12-42); NFPA 72
- 1.18. Mass Notification. Describe building/facility mass notification system (UFC 4-021-01) type and type of base-wide mass notification/communication system. State whether the visible notification appliances will be combined with the fire alarm system or kept separate. (Note: Navy has taken position to combine visible notification appliances with fire alarm).
- 1.19. Interior Finishes (classification). NFPA 101.10.2.3 and NFPA 101.7.1.4
- 1.20. Means of Egress

[Not Supplied] Page 92 of 151

1.20.1. Separation of Means of Egress, NFPA 101 chapters 7 and 12-42; NFPA101.7.1.3 1.20.2. Occupant Load, NFPA101.7.3.1 and chapters 12-42. 1.20.3. Egress Capacity (stairs, corridors, ramps and doors) NFPA101.7.3.3 1.20.4. Number of Means of Egress, NFPA101.7.4 and chapters 12-42. 1.20.5. Dead end limits and Common Path of Travel, NFPA 101.7.5.1.6 and chapters 12-42. 1.20.6. Accessible Means of Egress (for accessible buildings), NFPA101.7.5.4 1.20.7. Measurement of Travel Distance to Exits, NFPA101.7.6 and chapters 12-42. 1.20.8. Discharge from Exits, NFPA101.7.7.2 1.20.9. Illumination of Means of Egress, NFPA101.7.8 1.20.10. Emergency Lighting, NFPA101.7.9 1.20.11. Marking of Means of Egress, NFPA101.7.10 1.21. Elevators, UFC 3-600-01, Chapter 6; IBC and ASME A17.1 - 2000, (Safety Code for Elevators and Escalators) 1.22. Accessibility Requirements, ADA and ABA Accessibility Guidelines for Buildings and Facilities 1.23. Certification of Fire Protection and Life Safety Code Requirements. (Note: Edit the Fire team membership if necessary). Preparers of this document certify the accuracy and completeness of the Fire Protection and Life Safety features for this project in accordance with the attached completed form(s). Designer of Record. Certification of Fire protection and Life Safety Code Requirements. (Note: Edit the Fire team members if necessary). Preparers of this document certify the accuracy and completeness of the Fire Protection and Life Safety features of this project. Fire Protection Engineer of Record: Signature and Stamp Date OR Architect of Record: Signature and Stamp Date Mechanical Engineer of Record:

Electrical Engineer of Record:

Signature and Stamp

Date

Section: 01 33 16

Signature/Date

[Not Supplied] Page 93 of 151 Section: 01 33 16 [Not Supplied]
Page 94 of 151

ATTACHMENT E LEED SUBMITTALS

tion: C	11 3	3 16			LEED Submittais	[Not	
						Page	95 t
						_	
	pe					Date Submitted (to be filled in by Contractor)	S
	aim					trac	Government Reviewer's Use (OCT09REV)
	is Claimed					S No.	60
	t is					<u>></u>	, S
	Check Here if Credit			>		.⊑) (
	Ç			Onl		<u>le</u> q	S
占	<u>.</u>			dit		≡	_U.
gra	운			Au		ō o	, A
ara	y e			ədit		d (t	<u>§</u>
≝	Š			ö		ite	±
EED Credit Paragraph	Contractor			Provide for Credit Audit Only		μqr	l a
0	trac	LEED-NC v2.2		ide		ญ	l l
Щ	Con	Submittals (OCT09REV)		Pro/		Sate	9
AR		FEATURE	DUE AT	4	REQUIRED DOCUMENTATION	DATE	RE
ENERA							
		ERAL - All calculations shall be in accord					
					ace.army.mil/enWeb, "Engineering Criteria". OCT09REV ribe special circumstances or considerations regarding the project's credit approach.		
					ntract drawings with applicable discipline drawings, labeled For Reference Only.		
					oject submittals by either having a different due date or being an added submittal not re	eauired by	v GB
		09REV		Ċ	, , ,		•
	OCT	09REV GENERAL - Audit documentation	may include but is n	ot li			
					List of all Final Design submittals revised after final design to reflect actual closeout conditions. Revised Final Design submittals OR - Statement confirming that no		Proi
					conditions. Revised Final Design submittals OR - Statement confirming that no changes have been made since final design that effect final design submittal		Eng
			Closeout		documents.		(PE
ATEGO	RY 1	- SUSTAINABLE SITES					
		Construction Activity Pollution			List of drawings and specifications that address the erosion control, particulate/dust		
PR1	.,	Prevention (PREREQUISITE)	**Final Design		control and sedimentation control measures to be implemented.		C
CT09RE	:V		**Final Design		Delineation and labeling of "LEED Project site boundary" on site plan.		C
					Narrative that indicates which compliance path was used (NPDES or Local		
					standards) and describes the measures to be implemented on the project. If a local		
			**Final Design		standard was followed, provide specific information to demonstrate that the local standard is equal to or more stringent than the NPDES program.		CI
			i iliai Desigli		Standard is equal to or more stringent than the Nr DES program.		C
S1		Site Selection	Final Design		Statement confirming that project does not meet any of the prohibited criteria.		CI
CT09RE	V		**Final Design		Delineation and labeling of "LEED Project site boundary" on site plan.		CI
					LEED Site plan drawing that shows all proposed development, line depicting		
					boundary of all bodies of water and/or wetlands within 100 feet of project boundary and a line depicting 5' elevation above 100 year flood line that falls within project		
			Final Design	Х	boundary. Not required if neither condition applies.		CI
		Development Density & Community	i mai Beoign		Option 1: LEED Site vicinity plan showing project site and surrounding development.		Ŭ.
32		Connectivity	Final Design		Show density boundary or note drawing scale.		CI
CT09RE	V	Connectivity	**Final Design		Delineation and labeling of "LEED Project site boundary" on site plan.		CI
			, and the second		Option 1: Table indicating, for project site and all surrounding sites within density		
					radius (keyed to site vicinity plan), site area and building area. Project development		
			Final Design		density calculation. Density radius calculation. Development density calculation within density radius.		CI
			Final Design		within density radius.		U
					Option 2: LEED Site vicinity plan showing project site, the 1/2 mile community radius,		
					pedestrian walkways and the locations of the residential development(s) and Basic		
			Final Design		Services surrounding the project site.		CI
			Fine! David		Option 2: List (including business name and type) of all Basic Services facilities		
			Final Design		within the 1/2 mile radius, keyed to site vicinity plan.		CI
					Narrative describing contamination and the remediation activities included in project.		
33		Brownfield Redevelopment	Final Design		Include statement indicating how site was determined to be a brownfield.		С
CT09RE	V		**Final Design		Delineation and labeling of "LEED Project site boundary" on site plan.	-	С
		Alternative Transportation: Public			Statement indicating which option for compliance applies. State whether public transportation is existing or proposed and, if proposed, cite source of this		
64.1		Transportation Access	Final Design		information.		С
CT09RE	V		**Final Design		Delineation and labeling of "LEED Project site boundary" on site plan.		C
					Option 1: LEED Site vicinity plan showing project site, mass transit stops and		
			Final Design		pedestrian path to them with path distance noted. Option 2: LEED Site vicinity plan showing project site, bus stops and pedestrian path		С
			Final Design		to them with path distance noted.		С
			i mai bosigii		no area. man paan diotanoo notod.		
		Alternative Transportation: Bicycle			FTE calculation. Bicycle storage spaces calculation. Shower/changing facilities		
4.2		Storage & Changing Rooms	Final Design		calculation.		С
			Final Dasias		List of drawings that show the location(s) of bicycle storage areas. Statement		С
			Final Design		indicating distance from building entrance.		
					List of drawings that show the location(s) of shower/changing facilities and, if located		
			Final Design		outside the building, statement indicating distance from building entrance.		AF
		Altomotivo Transportation La Facilità		_	Ctotoment indicating which entire for a service and the latter to the la		_
		Alternative Transportation: Low Emitting & Fuel Efficient Vehicles	Final Design		Statement indicating which option for compliance applies. FTE calculation. Statement indicating total parking capacity of site.		С
4.3		a raci Emolent Venicles	**Final Design		Delineation and labeling of "LEED Project site boundary" on site plan.		C
34.3 CT09RE	V			_	Option 1: Low-emission & fuel-efficient vehicle calculation.		C

		T	1	1	T	Page	96 o
	g					or)	
	Check Here if Credit is Claimed					Date Submitted (to be filled in by Contractor)	Govemment Reviewer's Use (OCT09REV)
	SCIE					Conf	1601
	i ii					by	00
	Cre			N Y		i p	Jse
윤	ië ië			15		fille	ır's L
Credit Paragraph	F			t Auc		to be	iewe
Para	Jeck			redi		ed (t	Rev
edit	o C			o C		mit	ent
Č	ract	LEED-NC v2.2		ide		Suk	mme
LEED (Contractor	Submittals (OCT09REV)		Provide for Credit Audit Only		Date	3006
PAR	Ŭ	FEATURE	DUE AT		REQUIRED DOCUMENTATION	DATE	REV
					Option 1: List of drawings and specification references that show location and number of preferred parking spaces for low-emission & fuel-efficient vehicles and		
			Final Design		signage.		CIV
					Option 1: Statement indicating quantity, make, model and manufacturer of low-		
			Final Design		emission & fuel-efficient vehicles to be provided. Statement confirming vehicles are zero-emission or indicating ACEEE vehicle scores.		CIV
			Final Design		Option 2: Low-emission & fuel-efficient vehicle parking calculation.		CIV
			Final Design		Option 2: List of drawings and specification references that show location and number of preferred parking spaces and signage.		CIV
			F: 15 :				On /
			Final Design		Option 3: Low-emission & fuel-efficient vehicle refueling station calculation.		CIV
			Final Design		Option 3: List of drawings and specifications indicating location and number of refueling stations, fuel type and fueling capacity for each station for an 8-hour period.		CIV
					Option 3: Construction product submittals indicating what was provided and confirming compliance with respect to fuel type and fueling capacity for each station		
			Closeout	Χ	for an 8-hour period.		CIV
SS4.4		Alternative Transportation: Parking Capacity	Final Design		Statement indicating which option for compliance applies.		CIV
OCT09RE	ΞV	Сарасиу	**Final Design		Delineation and labeling of "LEED Project site boundary" on site plan.		CIV
			Final Design		Option 1: Preferred parking calculation including number of spaces required, total provided, preferred spaces provided and percentage.		CIV
					Option 2: FTE calculation. Preferred parking calculation including number of spaces		
			Final Design	-	provided, preferred spaces provided and percentage. Options 1 and 2: List of drawings and specification references that show location and		CIV
			Final Design		number of preferred parking spaces and signage.		CIV
					Option 3: Narrative indicating number of spaces required and provided and describing infrastructure and support programs with description of project features to		
			Final Design		support them.	<u> </u>	CIV
		Site Development: Protect or Restore			Option 1: List of drawing and specification references that convey site disturbance		
SS5.1 OCT09RE	=\/	Habitat	**Final Design **Final Design		limits. Delineation and labeling of "LEED Project site boundary" on site plan.		CIV
301001KL	Ĭ				Option 2: LEED site plan drawing that delineates boundaries of each preserved and		
			**Final Design	-	restored habitat area with area (sf) noted for each. Option 2: Percentage calculation of restored/preserved habitat to total site area. List		CIV
					of drawings and specification references that convey restoration planting		011
	ļ		**Final Design	<u> </u>	requirements.	<u> </u>	CIV
		Site Development: Maximize Open			Option 2: LEED site plan drawing delineating boundary of vegetated open space adjacent to building with areas of building footprint and designated open space		
SS5.2		Space Space	Final Design		noted.		CIV
OCT09RE	ΞV		**Final Design		Delineation and labeling of "LEED Project site boundary" on site plan.	<u> </u>	CIV
SS6.1 OCT09RE	Į V	Stormwater Design: Quantity Control	Final Design **Final Design		Statement indicating which option for compliance applies. Delineation and labeling of "LEED Project site boundary" on site plan.		CIV
					Option 1: Indicate pre-development and post-development runoff rate(cfs) and runoff quantity (cf) -OR - Narrative describing site conditions, measures and controls to be		
			Final Design	-	implemented to prevent excessive stream velocities and erosion. Option 2: Indicate pre-development and post-development runoff rate(cfs) and runoff		CIV
			Final Design		quantity (cf). Indicate percent reduction in each.		CIV
					For non-structural controls, list all BMPs used and, for each, describe the function of the BMP and indicate the percent annual rainfall treated. List all structural controls		
					and, for each, describe the pollutant removal and indicate the percent annual rainfall		
SS6.2 OCT09RE	l V	Stormwater Design: Quality Control	Final Design **Final Design	-	treated. Delineation and labeling of "LEED Project site boundary" on site plan.		CIV
1 U 31XI	- * 	<u>. </u>	I mai Design	1			
					LEED site plan drawing indicating locations and quantities of each paving type, including areas of shaded pavement. Percentage calculation indicating percentage of		
SS7.1 OCT09RE	\ =\/	Heat Island Effect: Non-Roof	**Final Design **Final Design	-	reflective/shaded/open grid area. Delineation and labeling of "LEED Project site boundary" on site plan.		CIV
COTUSKE	_ v	1	i mai Design			<u> </u>	LIV
					Option 1: Percentage calculation indicating percentage of SRI compliant roof area. List of drawings and specification references that convey SRI requirements and roof		
SS7.2		Heat Island Effect: Roof	Final Design	<u> </u>	slopes.		ARC

tion. C	,, ,	3 10			LEED Submittals	[INOL	
						Page	97 (
	Check Here if Credit is Claimed			λĺ		Date Submitted (to be filled in by Contractor)	Government Reviewer's Use (OCT09REV)
_	ΞĒC			Provide for Credit Audit Only		lilled	-
jrapł	-lere			Audi		pe (3
araç	X			edit /		d (to	, 3
₩				Š		nitte	1
LEED Credit Paragraph	Contractor	LEED-NC v2.2		le fo		Subr	
	ontra	Submittals (OCT09REV)		rovic		ate (3
 AR	O	FEATURE	DUE AT	Δ	REQUIRED DOCUMENTATION	DATE	RI
			Final Danian		Option 1: List of specified roof materials indicating, for each, product type,		
			Final Design OCT09REV		manufacturer, product name and identification if known, SRI value and roof slope. OCT09REV		Al
			**Closeout OCT09REV		Option 1: List of installed roof materials indicating, for each, manufacturer, product name and identification, SRI value and roof slope.		P
			Closeout	Χ	Option 1: Manufacturer published product data or certification confirming SRI		Р
			Final Design Final Design	1	Option 2: Percentage calculation indicating percentage of vegetated roof area. Option 3: Combined reflective and green roof calculation.		AF
			Y		Option 3: List of specified roof materials indicating, for each, product type,		Π
			Final Design OCT09REV		manufacturer, product name and identification if known, SRI value and roof slope. OCT09REV		\perp
			**Closeout		Option 3: List of installed roof materials indicating, for each, manufacturer, product		
			OCT09REV Closeout	Х	name and identification, SRI value and roof slope. Option 3: Manufacturer published product data or certification confirming SRI		F
		T				1	т —
					Interior Lighting: List of drawings and specification references that convey interior lighting requirements (location and type of all installed interior lighting, location of		
					non-opaque exterior envelope surfaces, allowing confirmation that maximum candela		
					value from interiorfixtures does not intersect non-opaque building envelope surfaces). - OR - List of drawings and specification references that show automatic lighting		
88		Light Pollution Reduction	Final Design		controls that turn off non-essential lighting during non-business hours.		EL
CT09RE	V		**Final Design		Delineation and labeling of "LEED Project site boundary" on site plan. Exterior Lighting: List of drawings and specification references that convey exterior	<u> </u>	EL
					lighting requirements (location and type of all site lighting and building		l
			Final Design		façade/landscape lighting).	 	EL
			Final Design		Exterior Site Lighting Power Density (LPD): Tabulation for exterior site lighting indicating, for each location identification or description, units of measure, area or distance of the location, actual LPD using units consistent with ASHRAE 90.1, and the ASHRAE allowable LPD for that type of location. Percentage calculation of actual versus allowable LPD for all site lighting.		EL
					Exterior Building Facade/Landscape Lighting Power Density (LPD): Tabulation for exterior building facade/landscape lighting indicating, for each location identification or description, units of measure, area or distance of the location, actual LPD using units consistent with ASHRAE 90.1, and the ASHRAE allowable LPD for that type of location. Percentage calculation of actual versus allowable LPD for all building		
			Final Design		facade/landscape lighting. Exterior Lighting IESNA Zone: Indicate which IESNA zone is applicable to the		EL
			Final Design		Exterior Lighting IESNA Zone: Indicate which IESNA zone is applicable to the project.		EL
					Exterior Lighting Site Lumen table indicating, for each fixture type, quantity installed, initial lamp lumens per luminaire, initial lamp lumens above 90 degrees from Nadir,		
			Final Design		total lamp lumens and total lamp lumens above 90 degrees. Percentage of site lamp lumens above 90 degrees from nadir to total lamp lumens.		EL
			Final Design		Exterior Lighting Narrative describing analysis used for addressing requirements for light trespass at site boundary and beyond.		EL
			i iliai Design		μιζητι τι συμάθου αι ότις υνατιάστη από νεγυπά.		LEL
TEGO	RY 2	– WATER EFFICIENCY Water Efficient Landscaping: Reduce by					Т
≣1.1	<u> </u>	50%	Final Design		Statement indicating which option for compliance applies.		С
T09RE	V		**Final Design		Delineation and labeling of "LEED Project site boundary" on site plan. Calculation indicating, for baseline and design case, total water applied, total		С
					potable water applied, total non-potable water applied. Design case percent potable	1	
	-		Final Design Final Design	-	water reduction. If nonpotable water is used, indicate source of nonpotable water. List of landscape plan drawings.	<u> </u>	C
			rınaı Design		<u>ызгонанизоаре</u> ріан инамінуз.		T
					Narrative describing landscaping and irrigation design strategies, including water use		
			Final Design		calculation methodology used to determine savings and, if non-potable water is used, specific information about source and available quantity.		С
F4 ^		Water Efficient Landscaping: No	-				
E1.2	1	Potable Water Use or No Irrigation	Same as WE1.1	1	Same as WE1.1 Statement confirming which option for compliance applies.	1	C

Section: 01 33 16

	1	- · · ·	1	1		Page	98 of
	ned					Date Submitted (to be filled in by Contractor)	(<u>)</u>
	Claimed					ontra	Government Reviewer's Use (OCT09REV)
	<u>.v</u>					Č	CT
	Sred			Ş		d i)) es
hq	e if (Ō		e fille	ı's U
EED Credit Paragraph	Check Here if Credit			Provide for Credit Audit Only		to be	iewe
Par	heck			Credi		ted (Rev
redit	tor C			for (bmit	ment
ED C	Contractor	LEED-NC v2.2		ovide		e Sc	vem
PAR	Ŝ	Submittals (OCT09REV) FEATURE	DUE AT	Pro	REQUIRED DOCUMENTATION	DATE	ලි REV
PAK		PEATURE	DUE AT		REQUIRED DOCUMENTATION	DATE	KEV
			Final Design		Statement confirming which occupancy breakdown applies (default or special). For special occupancy breakdown, indicate source and explanation for ratio.		MEC
			Final Design		Occupancy calculation including male/female numbers for FTEs, visitors, students, customers, residential and other type occupants/users		MEC
			Final Design		Statement indicating percent of male restrooms with urinals. Statement indicating annual days of operation.		MEC
					Baseline flush fixture calculation spreadsheet indicating, for each fixture type, gender, flush rate, daily uses per person for each occupant type identified in		
			Final Design		occupancy calculation and annual baseline flush fixture water usage.		MEC
					Design case flush fixture calculation spreadsheet indicating, for each fixture type, gender, fixture manufacturer, fixture model number, flush rate, percent of occupants		
					using this fixture type, daily uses per person for each occupant type identified in		
			Final Design		occupancy calculation and annual design case flush fixture water usage. Option 1: If onsite non-potable water is used, identify source(s), indicate annual		MEC
			Final Design		quantity from each source and indicate total annual quantity from all onsite non- potable water sources.		MEC
					Option 1: Summary calculation indicating baseline annual water consumption, design		
			Final Design		case annual water consumption, non-potable annual water consumption and total percentage annual water savings.		MEC
					Option 2: Statement confirming on-site treatment of all generated wastewater to		
			Final Design		tertiary standards and all treated wastewater is either infiltrated or used on-site. Option 2: List of drawing and specification references that convey design of on-site		MEC
			Final Design		wastewater treatment features.		CIV
					Option 2: On-site water treatment quantity calculation indicating all on-site		
					wastewater source(s), annual quantity treated, annual quantity infiltrated and annual		
			Final Design		quantity re-used on site from each source and totals for annual quantity treated, annual quantity infiltrated and annual quantity re-used on site from all sources.		CIV
					Option 2: Wastewater summary calculation indicating design case annual flush fixture water usage, annual on-site water treatment and percentage sewage		
			Final Design		convyance reduction. Narrative describing project strategy for reduction of potable water use for sewage		MEC
					conveyance, including specific information on reclaimed water usage and treated		
			Final Design		wastewater usage.		MEC
WE3.1		Water Use Reduction: 20% Reduction	Final Design		Statement confirming which occupancy breakdown applies (default or special). For special occupancy breakdown, indicate source and explanation for ratio.		MEC
	1		i mai Dosign		pposition occupantly broadcasting indicate occioe and explanation for faile.		IVILO
			Final Design		Occupancy calculation including male/female numbers for FTEs, visitors, students, customers, residential and other type occupants/users		MEC
	İ		_		Statement indicating percent of male restrooms with urinals. Statement indicating		
			Final Design		annual days of operation.		MEC
					Baseline flush fixture calculation spreadsheet indicating, for each fixture type,		
			Final Design		gender, flush rate, daily uses per person for each occupant type identified in occupancy calculation and annual baseline flush fixture water usage.		MEC
	1		20igii		Design case flush fixture calculation spreadsheet indicating, for each fixture type,		•
					gender, fixture manufacturer, fixture model number, flush rate, percent of occupants		
			Final Design		using this fixture type, daily uses per person for each occupant type identified in occupancy calculation and annual design case flush fixture water usage.		MEC
			Closeout	х	Manufacturer published product data or certification confirming fixture water usage.		PE
WE3.2	DV ^	Water Use Reduction: 30% Reduction	Same as WE3.1	,	Same as WE3.1		MEC
CAIEGO	K 1 3	- ENERGY AND ATMOSPHERE Fundamental Commissioning of the					
EAPR1		Building Energy Systems (PREREQUISITE)	**Final Design		**Owner's Project Requirements document		ALL
		,	**Final Design		**Basis of Design document for commissioned systems		MEC, ELEC
			-				MEC,
L	1		**Final Design	l	**Commissioning Plan	L	ELEC

							Oupp
						Page	99 UI
LEED Credit Paragraph	Contractor Check Here if Credit is Claimed	LEED-NC v2.2 Submittals (OCT09REV)		Provide for Credit Audit Only		Date Submitted (to be filled in by Contractor)	Government Reviewer's Use (OCT09REV)
PAR		FEATURE	DUE AT		REQUIRED DOCUMENTATION Statement confirming all commissioning requirements have been incorporated into	DATE	REV
			Closeout		construction documents.		PE
			Closeout		Commissioning Report Statement listing the mandatory provisions of ASHRAE 90.1 that project meets		PE MEC
EAPR2		Minimum Energy Performance (PREREQUISITE)	Final Design		relative to compliance with this prerequisite and indicating which compliance path was used.		ELEC ARC
EAPR3		Fundamental Refrigerant Management (PREREQUISITE)	Final Design		Statement indicating which option for compliance applies.		MEC
			Final Design		Option 2: Narrative describing phase out plan, including specific information on phase out dates and refrigerant quantities.		MEC
EA1		Optimize Energy Performance	Final Design		Statement indicating which compliance path option applies.		MEC
			Final Design		Option 1: Statement confirming simulation software capabilities and confirming assumptions and methodology.		MEC
					Option 1: General information including simulation program, principal heating source, percent new construction and renovation, weather file, climate zone and Energy Star		
			Final Design		Target Finder score.		MEC
			Final Design		Option 1: Space summary listing, for each building use, the conditioned area, unconditioned area and total area and include total area for each category		MEC
			Final Design		Option 1: List of all simulation output advisory message data and show difference between baseline and proposed design		MEC
			Final Design Final Design		Option 1: Comparison summary for energy model inputs including description of baseline and design case energy model inputs, showing both by element type Option 1: Energy type summary lising, for each energy type, utility rate description, units of energy and units of demand		MEC MEC
			Final Design		Option 1: Statement indicating whether project uses on-site renewable energy. If yes list all sources and indicate, for each source, backup energy type, annual energy generated, rated capacity and renewable energy cost	,	MEC
			Final Design		Option 1: If analysis includes exceptional calculation methods, statement describing how exceptional calculation measure cost savings is determined		MEC
			Final Design		Option 1: If analysis includes exceptional calculation methods, for each exceptional calculation method indicate energy types and, for each energy type, annual energy savings, annual cost savings, and brief descriptive narrative		MEC
			Final Design		Option 1: Baseline performance rating compliance report table indicating, for each energy end use, whether it is a process load, energy type, annual and peak energy demand for all four orientations. For each orientation indicate total annual energy use for each orientation and total annual process energy use.	,	MEC
			Final Design		Option 1: Baseline energy cost table indicating, for each energy type, annual cost for all four orientations and building total energy cost.		MEC
			Final Design		Option 1: Proposed Design performance rating compliance report table indicating, for each energy end use, whether it is a process load, energy type, annual and peak energy demand, baseline annual and peak energy demand and percent savings. Indicate total annual energy use and total annual process energy use for both proposed design and baseline and percent savings.	r	MEC
			Final Design		Option 1: Proposed Design energy cost table indicating, for each energy type, annua cost for all four orientations and building total energy cost.	I	MEC
			Final Design		Option 1: Energy cost and consumption by energy type report indicating, for each energy type, proposed design and baseline annual use and annual cost, percent savings annual use and annual cost. Indicate for renewable energy annual energy generated and annual cost. Indicate exceptional calculations annual energy savings and annual cost savings. Indicate building total annual energy use, annual energy cost for proposed design and baseline and indicate percent savings annual energy use and annual energy cost.		MEC

				1	· · · · · · · · · · · · · · · · · · ·	age 1	۱۸ ۸۱ ۵۱ ۵۱ ۵۱ ۱
					ľ	aye i	00 01
LEED Credit Paragraph	or Check Here if Credit is Claimed			Provide for Credit Audit Only		Date Submitted (to be filled in by Contractor)	Government Reviewer's Use (OCT09REV)
Ö	Contractor	LEED-NC v2.2		ide f		Suk	əmm
Щ	Con	Submittals (OCT09REV)		Pro		Date	80
PAR		FEATURE	DUE AT		REQUIRED DOCUMENTATION	DATE	REV
			Final Design Final Design		Option 1: Compliance summaries from energy simulation software. If software does not produce compliance summaries provide output summaries and example input summaries for baseline and proposed design supporting data in the tables. Output summaries must include simulated energy consumption by end use and total energy use and cost by energy type. Example input summaries should represent most common systems and must include occupancy, use pattern, assumed envelope component sizes and descriptive features and assumed mechanical equipment types and descriptive features Option 1: Energy rate tariff from project energy providers (only if not using LEED Reference Guide default rates)		MEC MEC
EA2.1		On-Site Renewable Energy	Final Design		Statement indicating which compliance path option applies.		ELEC
			Final Design		List all on-site renewable energy sources and indicate, for each source, backup energy type, annual energy generated, rated capacity and renewable energy cost. Indicate total annual energy use (all sources), total annual energy cost (all sources) and percent renewable energy cost.		ELEC MEC
	1		Final Design		Option 1: Indicate, for renewable energy,proposed design total annual energy		ELEC
			Final Design		generated and annual cost.		MEC
			Final Design Final Design		Option 2: Indicate CBECS building type and building gross area. Provide the following CBECS data: median annual electrical intensity, median annual non-electrical fuel intensity, average electric energy cost, average non-electric fuel cost, annual electric energy use and cost, annual non-electric fuel use and cost. Option 2: Narrative describing renewable systems and explaining calculation method used to estimate annual energy generated, including factors influencing performance.		ELEC MEC ELEC MEC
EA2.2		On-Site Renewable Energy	Same as EA2.1		Same as EA2.1		ELEC MEC
LAZ.Z	1	On-Site Renewable Energy	Same as LAZ.		Daille as Enz. I		ELEC
EA2.3 EA3		On-Site Renewable Energy Enhanced Commissioning	Same as EA2.1 **Final Design		Same as EA2.1 **Owner's Project Requirements document (OPR)		MEC ALL
EAS		Elinanced Commissioning	Filial Design		Owner's Floject Requirements document (OFR)		ELEC
			**Final Design		**Basis of Design document for commissioned systems (BOD)		MEC
			**Final Design		**Commissioning Plan		MEC
			01 .		Statement confirming all commissioning requirements have been incorporated into		
	-		Closeout Closeout		construction documents. **Commissioning Report		PE PE
			**Final Design		Statement by CxA confirming Commissioning Design Review		
			Closeout		Statement by CxA confirming review of Contractor submittals for compliance with OPR and BOD		PE
			Closeout		**Systems Manual		PE
			Classer		Statement by CVA confirming completion of CVAM ato# === 1 ======= t ======		חר
			Closeout		Statement by CxA confirming completion of O&M staff and occupant training **Scope of work for post-occupancy review of building operation, including plan for resolution of outstanding issues		PE PE
			**Predesign		Statement confirming CxA qualifications and contractual relationships relative to work on this project, demonstrating that CxA is an independent third party.		MEC
EA4		Enhanced Refrigerant Management	Final Design		Refrigerant impact calculation table with all building data and calculation values as shown in LEED 2.2 Reference Guide Example Calculations		MEC
	1		Final Design	L	Narrative describing any special circumstances or explanatory remarks OCT09REV		L
E 4 5			Closeout	Х	Cut sheets highlighting refrigerant data for all HVAC components.		PE
EA5	+-	Measurement & Verification	Closeout Closeout	╂—	Statement indicating which compliance path option applies. Measurement and Verification Plan		PE PE
			Closeout		**Scope of work for post-occupancy implementation of M&V plan		PE
EA6		Green Power	Closeout		Statement indicating which compliance path option applies.		PE
			Closeout		Option 1: Indicate proposed design total annual electric energy usage		PE
			Closeout		Option 2: Indicate actual total annual electric energy usage		PE
					Option 3: Calculation indicating building type, total gross area, median electrical		
	1		Closeout	1	intensity and annual electric energy use		PE

ction: C)1 3	3 16			LEED Submittals	[Not	
NEED Credit Paragraph	Contractor Check Here if Credit is Claimed	LEED-NC v2.2 Submittals (OCT09REV)	DUE AT	Provide for Credit Audit Only		Bate Submitted (to be filled in by Contractor)	Government Reviewer's Use (OCT09REV)
			Olavasi		Green power provider summary table indicating, for each purchase type, provider name, annual quantity green power purchased and contract term. Indicate total		
			Closeout Closeout		annual green power use and indicate percent green power Narrative describing how Green Power or Green Tags are purchased		PE PE
CATEGO	DV 1	MATERIAL C AND RECOURCES	, 5,000001		primiting accounting near creating one of creating and paramascu		
MRPR1	N 1 4	Storage & Collection of Recyclables (PREREQUISITE) Building Reuse: Maintain 75% of	Final Design		Statement confirming that recycling area will accommodate recycling of plastic, metal, paper, cardboard and glass. Narrative indicating any other materials addressed and coordination with pickup. If project includes a building addition, confirm that area of building addition does not		ARC
MR1.1		Existing Walls, Floors & Roof	**Final Design		exceed 2x the area of the existing building. Spreadsheet listing, for each building structural/envelope element, the existing area		ARC
MR1.2		Building Reuse: Maintain 95% of Existing Walls, Floors & Roof	**Final Design Same as MR1.1		and reused area. Total percent reused. Same as MR1.1		ARC
MR1.3		Building Reuse: Maintain 50% of Interior Non-Structural Elements	**Final Design		If project includes a building addition, confirm that area of building addition does not exceed 2x the area of the existing building.		ARC
WITCH.5		menor non orderar Elements	**Final Design		Spreadsheet listing, for each building interior non-structural element, the existing area and reused area. Total percent reused.		ARC
MR2.1		Construction Waste Management: Divert 50% From Disposal	**Preconstruction		Waste Management Plan		PE
			**Construction Quarterly and Closeout		Spreadsheet calculations indicating material description, disposal/diversion location (or recycling hauler), weight, total waste generated, total waste diverted, diversion percentage		PE
			**Construction		OCT09REV		
			Quarterly and Closeout		Receipts/tickets for all items on spreadsheet		PE
MR2.2		Construction Waste Management: Divert 75% From Disposal	Same as MR2.1		Same as MR2.1		PE
MR3.1		Materials Reuse: 5%	Closeout		Statement indicating total materials value and whether default or actual.		PE
MR3.2		Materials Reuse: 10%	Closeout Same as MR3.1		Spreadsheet calculations indicating, for each reused/salvaged material, material description, source or vendor, cost. Total reused/salvaged materials percentage. Same as MR3.1		PE PE
MR4.1		Recycled Content: 10% (post- consumer + 1/2 pre-consumer)	Closeout		Statement indicating total materials value and whether default or actual.		PE
			Closeout		Spreadsheet calculations indicating, for each recycled content material, material name/description, manufacturer, cost, post-consumer recycled content percent, preconsumer recycled content percent, source of recycled content data. Total post-consumer content materials cost, total pre-consumer content materials cost, total combined recycled content materials cost.		PE
			Final Design or NLT		**Purchasing Plan consisting of spreadsheet indicated above, filled in with estimated		
			Preconstruction Closeout	Х	quantities to show strategy for achieving goal. OCT09REV Manufacturer published product data or certification, confirming recycled content percentages in spreadsheet		PE PE
MR4.2		Recycled Content: 20% (post- consumer + 1/2 pre-consumer)	Same as MR4.1		Same as MR4.1		PE
MR5.1		Regional Materials:10% Extracted, Processed & Manufactured Regionally	Closeout		Statement indicating total materials value and whether default or actual.		PE
		The state of the s			Spreadsheet calculations indicating, for each regional material, material name/description, manufacturer, cost, percent compliant, harvest distance, manufacture distance, source of manufacture and harvest location data. Total		
			Closeout		regional materials cost, regional materials percentage.		PE

Preconstruction OCT09REV

Closeout

PE PE

**Purchasing Plan consisting of spreadsheet indicated above, filled in with estimated quantities to show strategy for achieving goal. OCT09REV Manufacturer published product data or certification confirming regional material

percentages in spreadsheet

					F	age 1	02 of
LEED Credit Paragraph	Contractor Check Here if Credit is Claimed	LEED-NC v2.2 Submittals (OCT09REV)		Provide for Credit Audit Only		Date Submitted (to be filled in by Contractor)	Government Reviewer's Use (OCT09REV)
AR		FEATURE	DUE AT		REQUIRED DOCUMENTATION	DATE	REV
R5.2		Regional Materials:20% Extracted, Processed & Manufactured Regionally	Same as MR5 1		Same as MR5.1		PE
R6		Rapidly Renewable Materials	Closeout		Statement indicating total materials value and whether default or actual.		PE
			Closeout		Spreadsheet calculations indicating, for each rapidly renewable material, material name/description, manufacturer, cost, rapidly renewable content percent, rapidly renewable product value. Total rapidly renewable product value, rapidly renewable materials percentage.		PE
			Final Design OCT09REV		**Purchasing Plan consisting of spreadsheet indicated above, filled in with estimated quantities to show strategy for achieving goal. OCT09REV Manufacturer published product data or certification confirming rapidly renewable		ARC
R7		Certified Wood	Closeout Closeout	Χ	material percentages in spreadsheet Statement indicating total materials value and whether default or actual.		PE PE
ii(/		Certified Wood	Closeout		Spreadsheet calculations indicating, for each certified wood material, material name/description, vendor, cost, wood component percent, certified wood percent of wood component, FSC chain of custody certificate number. Total certified wood product value, certified wood materials percentage.		PE
			Final Design or NLT Preconstruction		**Purchasing Plan consisting of spreadsheet indicated above, filled in with estimated quantities to show strategy for achieving goal. OCT09REV		PE
					Vendor invoices, FSC chain of custody certificates and anufacturer published product data or certification confirming all certified wood materials percentages in		
			Closeout	Χ	spreadsheet.		PE
ATEGO	RY 5	- INDOOR ENVIRONMENTAL QUALIT	<u>Y</u>	1	Statement indicating which option for compliance applies, stating applicable	T	
QPR1		Minimum IAQ Performance (PREREQUISITE)	Final Design		criteria/requirement, and confirming that project has been designed to meet the applicable requirements.		MEC
			Final Design		Narrative describing the project's ventilation design, including specifics about fresh air intake volumes and special considerations.		MEC
QPR2		Environmental Tobacco Smoke (ETS) Control (PREREQUISITE)	Final Design		Statement indicating which option for compliance applies, stating applicable criteria/requirement, and confirming that project has been designed to meet the applicable requirements.		ARC
			Final Design		List of drawing and specification references that convey conformance to applicable requirements (signage, exhaust system, room separation details, etc).		ARC
Q1		Outdoor Air Delivery Monitoring	Final Design		Statement indicating which option for compliance applies and confirming that project has been designed to meet the applicable requirements. List of drawing and specification references that convey conformance to applicable		MEC
			Final Design		requirements.		MEC
			Final Design		Narrative describing the project's ventilation design and CO2 monitoring system, including specifics about monitors, operational parameters and setpoints.		MEC
			Closeout	٨	Cut sheets for CO2 monitoring system.		PE
Q2	L	Increased Ventilation	Final Design		Statement indicating which option for compliance applies and confirming that project has been designed to meet the applicable requirements.		MEC
			Final Design		Narrative describing the project's ventilation design, including specifics about zone fresh air intake volumes and demonstrating compliance.		MEC
			Final Design		Option 2: Narrative describing design method used for determining natural ventilation design, including calculation methodology/model results and demonstrating compliance.		MEC
			Final Design		List of drawing and specification references that convey conformance to applicable requirements.		MEC
Q3.1		Construction IAQ Management Plan: During Construction	**Preconstruction		Construction IAQ Management Plan		PE
			Closeout		Statement confirming whether air handling units were operated during construction Dated jobsite photos showing examples of IAQ management plan practices being		PE
			Closeout		implemented. Label photos to indicate which practice they demonstrate. Minimum one photo of each practice at each building.		PE
					Spreadsheet indicating, for each filter installed during construction, the manufacturer,	1	
		Construction IAQ Management Plan:	Closeout		model number, MERV rating, location installed, and if it was replaced immediately prior to occupancy.		PE

tion: C)1 3	3 16			LEED Submittals	Not 3] age 1 1]	
						rage ii	J3 ()I
LEED Credit Paragraph	Contractor Check Here if Credit is Claimed	LEED-NC v2.2 Submittals (OCT09REV)		Provide for Credit Audit Only		Date Submitted (to be filled in by Contractor)	Government Reviewer's Use (OCT09REV)
AR		FEATURE	DUE AT		REQUIRED DOCUMENTATION	DATE	REV
			Closeout		Statement indicating which option for compliance applies and confirming that required activities have occurred that meet the applicable requirements. Option 1a: Narrative describing the project's flushout process, including specifics about temperature, airflow and duration, special considerations (if any) and		PE
			Closeout		demonstrating compliance.		PE
			Closeout		Option 1b: Narrative describing the project's pre-occupancy and post-occupancy flushout processes, including specifics about temperature, airflow and duration, special considerations (if any) and demonstrating compliance. Option 2: Narrative describing the project's IAQ testing process, including specifics		PE
			Classout		about contaminants tested for, locations, remaining work at time of test, retest		D.E.
			Closeout Closeout		parameters and special considerations (if any). Option 2: IAQ testing report demonstrating compliance.		PE PE
Q4.1		Low Emitting Materials: Adhesives & Sealants	Closeout		Spreadsheet indicating, for each applicable indoor adhesive, sealant and sealant primer used, the manufacturer, product name/model number, VOC content, LEED VOC limit, and source of VOC data.		PE
			Closeout		Spreadsheet indicating, for each applicable indoor aerosol adhesive, the manufacturer, product name/model number, VOC content, LEED VOC limit, and source of VOC data - OR - Statement confirming no indoor aerosol adhesives were used for the project.		PE
			Closeout	Х	Manufacturer published product data or certification confirming material VOCs in spreadsheet		PE
Q4.2		Low Emitting Materials: Paints & Coatings	Closeout		Spreadsheet indicating, for each applicable indoor paint and coating used, the manufacturer, product name/model number, VOC content, LEED VOC limit, and source of VOC data.		PE
					Spreadsheet indicating, for each applicable indoor anti-corrosive/anti-rust paint and coating used, the manufacturer, product name/model number, VOC content, LEED VOC limit, and source of VOC data - OR - Statement confirming no indoor anti-		
			Closeout		corrosive/anti-rust paints were used for the project . Manufacturer published product data or certification confirming material VOCs in		PE
			Closeout	X	spreadsheet Spreadsheet indicating, for each indoor carpet used, the manufacturer, product name/model number, if it meets LEED requirement (yes/no) and source of LEED		PE_
Q4.3		Low Emitting Materials: Carpet Systems	Closeout		compliance data. Spreadsheet indicating, for each indoor carpet cushion used, the manufacturer, product name/model number, if it meets LEED requirement (yes/no) and source of LEED compliance data - OR - Statement confirming no indoor carpet cushion was		PE
			Closeout		used for the project. Manufacturer published product data or certification confirming material CRI label in		PE
			Closeout	X	spreadsheet Spreadsheet indicating, for each indoor composite wood and agrifiber product used,		PE
Q4.4		Low Emitting Materials: Composite Wood & Agrifiber Products	Closeout		the manufacturer, product name/model number, if it contains added urea formaldehyde (yes/no) and source of LEED compliance data.		PE
			Closeout	Х	Manufacturer published product data or certification confirming material urea formaldehyde in spreadsheet		PE
Q5		Indoor Chemical & Pollutant Source Control	Closeout OCT09REV		Spreadsheet indicating, for each permanent entryway system used, the manufacturer, product name/model number and description of system. Roll-up and carpet systems requiring weekly cleaning to earn this credit are not a permitted option for Army projects.		PE
			Final Design		List of drawing and specification references that convey locations and installation methods for entryway systems.		ARC
			Final Design		Spreadsheet indicating, for each chemical use area, the room number, room name, description of room separation features (walls, floor/ceilings, openings) and pressure differential from surrounding spaces with doors closed - OR - Statement confirming that project includes no chemical use areas and that no hazardous cleaning materials are needed for building maintenance.		ARC MEC
			Final Design		If project includes chemical use areas: List of drawing and specification references that convey locations of chemical use areas, room separation features and exhaust system.		ARC MEC
			Closeout OCT09REV		If project includes chemical use areas: Spreadsheet indicating, for AHUs/mechanical ventilation equipment serving occupied areas, the manufacturer, model number, MERV rating, location installed, and if it was replaced immediately prior to occupancy (yes/no) - OR - Statement confirming that project does not use mechanical equipment for ventilation of occupied areas.		

OCT 2009

[Not Supplied]

113	उ १७					
				F	age 1	04 of
heck Here if Credit is Claimed			Sredit Audit Only		ted (to be filled in by Contractor)	Government Reviewer's Use (OCT09REV)
			for (bmit	nent
trac	LEED-NC v2.2		/ide		nS e	emr
Co			Pro		Dat	
	FEATURE	DUE AT				REV
		E: 15 :		with individual lighting controls and the percentage of workstations with individual		51.50
	Controllability of Systems: Lighting	Final Design		lighting controls.		ELEC
		Final Design		For each shared multi-occupant space, provide a brief description of lighting controls.		ELEC
		Final Design		Narrative describing lighting control strategy, including type and location of individual controls and type and location of controls in shared multi-occupant spaces. Calculation indicating total number of individual workstations, number of workstations.		ELEC
	Controllability of Systems: Thermal			with individual thermal comfort controls and the percentage of workstations with		
	Comfort	-		individual thermal comfort controls. For each shared multi-occupant space, provide a brief description of thermal comfort		MEC
		Final Design		controls. Narrative describing thermal comfort control strategy, including type and location of		MEC
		Final Design		individual and shared multi-occupant controls.		MEC
	Thermal Comfort: Design	Final Design		Design criteria spreadsheet indicating, for spring, summer, fall and winter, maximum indoor space design temperature, minimum indoor space design temperature and maximum indoor space design humidity.		MEC
	, and the second			Narrative describing method used to establish thermal comfort control conditions and how systems design addresses the design criteria, including compliance with the		
	Thermal Comfort: Verification			Narrative describing the scope of work for the thermal comfort survey, including		MEC MEC
	Daylight & Views: Daylight 75% of Spaces	Final Design		Option 1: Table indicating all regularly occupied spaces with space area and space area with 2% daylighting factor. Sum of regularly occupied areas and regularly occupied areas with 2% daylighting factor. Percentage calculation of areas with 2% daylighting factor to total regularly occupied areas.		ARC
	·	Final Design		Option 1: Glazing factor calculation table		ARC
		Final Design		Option 2: Simulation model method, software and output data		ARC
				Option 2: Table indicating all regularly occupied spaces with space area, space area with minimum 25 footcandles daylighting illumination, and method of providing glare control. Sum of regularly occupied areas and regularly occupied areas with 25 fc		
		Final Design		occupied areas.		ARC
		Final Design		reasons for excluding the space.		ARC
				List of drawing and specification references that convey exterior glazed opening		ARC
				Manufacturer published product data or certification confirming glazing Tvis in		
	Doulisht & Vious Vious for 000/ of	Closeout	X	Table indicating all regularly occupied spaces with space area and space area with access to views. Sum of regularly occupied areas and regularly occupied areas with		PE
	Spaces	Final Design		occupied areas.		ARC
_		Final Design				ARC
				LEED Floor plan drawings showing line of sight diagramming of views areas in each regularly occupied space. List of drawing/specification references that convey		
		Final Design		exterior glazed opening head and sill heights.		ARC
RY 6	- FACILITY DELIVERY PROCESS					
	Innovation in Design	Final Design		Narrative decribing intent, requirement for credit, project approach to the credit. List of drawings and specification references that convey implementation of credit. All other documentation that validates claimed credit		
		Final Design		paror accumentation that valuates dailined dedit.		
	-	Final Design				
	Innovation in Design	Final Design				
	LEED Accredited Professional	Final Design		Narrative indicating name of LEED AP, company name of LEED AP, description of LEED AP's role and responsibilities in the project.		ARC
	Contractor Check Here if Credit is Claimed	LEED-NC v2.2 Submittals (OCT09REV) FEATURE Controllability of Systems: Lighting Controllability of Systems: Thermal Comfort Thermal Comfort: Verification Daylight & Views: Daylight 75% of Spaces Daylight & Views: Views for 90% of Spaces Proceedings of Spaces Innovation in Design	LEED-NC v2.2 Submittals (OCT09REV) FEATURE Controllability of Systems: Lighting Final Design Final Design Controllability of Systems: Thermal Comfort Final Design Final Design Final Design Final Design Final Design Thermal Comfort: Verification Daylight & Views: Daylight 75% of Spaces Final Design OCT09REV Final Design OCT09REV Final Design OCT09REV	LEED-NC v2.2 Submittals (OCT09REV) FEATURE Controllability of Systems: Lighting Final Design OCT09REV Final Design Final Design Final Design Final Design Final Design Final Design OCT09REV Final Design Final Design OCT09REV Final Design OCT09REV	LEED-NC V2.2 Submittals (OCTO9REV)	Description Description

Section: 01 33 16

Section: 01 33 16 [Not Supplied]
Page 105 of 151

ATTACHMENT F

Version 07-07-2010

BUILDING INFORMATION MODELING REQUIREMENTS

1.0 Section 1 - Submittal Format

1.1. <u>Design Deliverables</u>. Develop all designs using Building Information Modeling (BIM) and Computer Aided Design (CAD) software. Design submittal drawings shall be [Not Supplied - SubmittalReqDistribution: FULL_SIZE] size, suitable for half-size scaled reproduction.

2.0 Section 2 – Design Requirements

- 2.1. <u>BIM Model and Facility Data</u>. Contractor shall use BIM application(s) and software(s) to develop project designs. "Facility Data" is defined as associated intelligent attribute data. The "Model" is defined as 3D graphics that includes Facility Data and output as described in the paragraph 'Output' below. Contractors will use the Model to produce accurate Construction Documents. For each Center of Standardization (CoS) facility type included in this project, all BIM Models and associated Facility Data shall be submitted in Bentley Systems BIM [Not Supplied SubmittalReqCADDSystem: BENTLEY_VERSION] with associated USACE Bentley BIM Workspace (which includes specific standard BIM libraries and definitions). This Workspace can be downloaded from the CAD/BIM Technology Center. [Where available, the workspace will be specific to this CoS Facility Standard Design. The Contractor will be provided a baseline multi-discipline BIM Project Model for the CoS Facility Standard Design type, where such a model exists (for the purposes of site adaptation).] The USACE Bentley BIM Workspace is dependent on specific versions of the Bentley BIM suite of products and only the versions of the software that are listed in the Contractor instructions included with the USACE BIM Workspace are permitted to be used.
- 2.1.1. <u>Reference.</u> Refer to ERDC TR-06-10, "U.S. Army Corps of Engineers Building Information Modeling Road Map" from the CAD/BIM Technology Center website for more information on the USACE BIM implementation goals.
- 2.2. <u>Drawings</u>. Deliver CAD files used for the creation of the Construction Documents Drawings per requirements in Section 01 33 16, the criteria of the USACE [Not Supplied DistrictInfoGeneral : ISSUING_DISTRICT] District, and as noted herein. Specification of a CAD file format for these Drawings does not limit which BIM application(s) or software(s) may be used for project development and execution.
- 2.2.1. <u>IFC Support.</u> The Contractor's selected BIM application(s) and software(s) must support the IFC (Industry Foundation Class see www.iai-tech.org). Submit any deviations from or additions to the IFC property sets for any new spaces, systems, and equipment for Government approval.
- 2.2.2. <u>Submittal Requirements</u>. BIM submittals shall be fully interoperable, compatible, and editable with the Bentley BIM tools. Use the specified version of the USACE Bentley BIM Workspace and conform to the requirements of **Sections 3 and 4 below**.
- 2.2.3. BIM Project Execution Plan.
- 2.2.3.1. Develop a BIM Project Execution Plan ("Plan" or "PxP") documenting the BIM and analysis technologies selected for the Project Model (integrated with the AEC CAD Standard) from concept development through As-Builts as a design, production, coordination, construction, and documentation tool and the collaborative process by which it shall be executed. See Section 7 for additional guidance on developing the Plan.
- 2.2.4. BIM Requirements..
- 2.2.4.1. <u>Facility Data</u>. Develop the Facility Data consisting of a set of intelligent elements for the Model (e.g., doors, air handlers, electrical panels). This Facility Data shall include all material definitions and attributes that are necessary for the Project facility design and construction. Additional data in support of Section 6 Contractor Electives is encouraged.

Section: 01 33 16 [Not Supplied]
Page 106 of 151

2.2.4.2. <u>Model Content</u>. The Model and Facility Data shall include, at a minimum, the requirements of Section 4 below.

- 2.2.4.3. <u>Model Granularity</u>. Models may vary in level of detail for individual elements within a model, but at a minimum must include all features that would be included on a quarter inch (1/4" = 1'0") scaled drawing (e.g. at least 1/16th, 1/8th and 1/4th), or appropriately scaled civil drawings.
- 2.2.4.4. <u>Output</u>. Submitted CAD drawings (e.g., plans, elevations, sections, schedules, details, etc.) shall be derived (commonly known as extractions, views or sheets) and maintained from the submitted Model and Facility Data.
- 2.3. Quality Control. Implement quality control (QC) parameters for the Model, including:
- 2.3.1. <u>Model Standards Checks</u>. QC validation used to ensure that the Project Facility Data set has no undefined, incorrectly defined or duplicated elements. Report non-compliant elements and corrective action plan to correct non-compliant elements. Provide the government with detailed justification and request government approval for any non-compliant element which the contractor proposes to be allowed to remain in the Model.
- 2.3.2. <u>CAD Standards Checks</u>. QC checking performed to ensure that the fonts, dimensions, line styles, levels and other construction document formatting issues are followed per the A/E/C CADD Standard.
- 2.3.3. Other Parameters. Develop such other QC parameters as Contractor deems appropriate for the Project and provide to the Government for concurrence.
- 2.4. <u>Design and Construction Reviews.</u> Perform design and construction reviews at each submittal stage under Section 3 to test the Model, including:
- 2.4.1. <u>Visual Checks.</u> Checking to ensure the design intent has been followed and that there are no unintended elements in the Model.
- 2.4.2. <u>Interference Management Checks.</u> Locate conflicting spatial data in the Model where two elements are occupying the same space. Log hard interferences (e.g., mechanical vs. structural or mechanical vs. mechanical overlaps in the same location) and soft interferences, (e.g., conflicts regarding equipment clearance, service access, fireproofing, insulation) in a written report and resolve.
- 2.4.3. <u>IFC Coordination View.</u> Provide an IFC Coordination View in IFC Express format for all deliverables. Provide exported property set data for all IFC supported named building elements.
- 2.4.4. <u>Other Parameters.</u> Develop such other Review parameters as the Contractor deems appropriate for the Project and provide to the Government for concurrence..

3.0 Section 3 – Design Stage Submittal Requirements

- 3.1. General Submittal Requirements.
- 3.1.1. Provide submittals in compliance with BIM Project Execution Plan deliverables at stages as described hereinafter.
- 3.1.2. At each Stage in Paragraphs 3.3 through 3.6, provide a Contractor-certified written report confirming that consistency checks as identified in Paragraphs 2.3 and 2.4 have been completed. This report shall be discussed as part of the review process and shall address cross-discipline interferences, if any.
- 3.1.3. At each Stage in Paragraphs 3.3 through 3.6, provide the Government with:
- The Model, Facility Data, Workspace and CAD Data files in native Bentley BIM/CAD.
- A 3-D interactive review format of the Model in Bentley Navigator, Autodesk Navisworks, Adobe 3D PDF 7.0 (or later), Google Earth KMZ or other format per Plan requirements. The file format for reviews can change between submittals.

Section: 01 33 16 [Not Supplied]
Page 107 of 151

- A list of all submitted files. The list should include a description, directory, and file name for each file submitted. For all CAD sheets, include the sheet title and sheet number. Identify files that have been produced from the submitted Model and Facility Data.

- 3.1.4. The Government will confirm acceptability of all submittals identified in Section 3 in coordination with the USACE [Not Supplied DistrictInfoGeneral : ISSUING_DISTRICT] BIM Manager
- 3.2. Initial Design Conference Submittal.
- 3.2.1. Submit a digital copy of the Plan where, in addition to Paragraph 3.1.4, the USACE Geographic District BIM Manager will coordinate with the USACE CoS BIM Manager to confirm acceptability of the Plan or advise as to additional processes or activities necessary to be incorporated.
- 3.2.2. Within thirty (30) days after the approval of the Plan, conduct a demonstration to review the Plan for clarification, and to verify the functionality of Model technology workflow and processes. If modifications are required, the Contractor shall complete the modifications and resubmit the Plan and perform subsequent demonstration for Government acceptance. There will be no payment for design or construction until the Plan is acceptable to the Government. The Government may also withhold payment for design and construction for unacceptable performance in executing the approved Plan.
- 3.3. <u>Interim Design Submittals.</u>
- 3.3.1. <u>BIM and CAD Data</u>. The Model shall include the requirements identified in Paragraph 2.2.4 as applicable to the Interim Design package(s).
- 3.4. <u>Final Design Submissions and Design Complete Submittals.</u>
- 3.4.1. <u>BIM and CAD Data</u>. The Model shall include the requirements identified in Paragraph 2.2.4. Acceptance according to Paragraph 3.1.4 is required before commencement of construction, as described in Paragraph 3.7.6 of Section 01 33 16.
- 3.5. <u>Construction Submittals Over-The-Shoulder Progress Reviews</u>. Periodic quality control meetings or construction progress review meetings shall include quality control reviews on the implementation and use of the Model, including interference management and design change tracking information.
- 3.6. <u>Final As-Builts BIM and CAD Data Submittal.</u> Submit the final Model, Facility Data, and CAD files reflecting as-built conditions for Government Approval, as specified in Section 01 78 02.00 10, PROJECT CLOSEOUT.

4.0 Section 4 – BIM Model Minimum Requirements and Output

- 4.1. <u>General Provisions</u>. The deliverable Model shall be developed to include the systems described below as they would be built and the processes of installing them, and to reflect final as-built conditions. The deliverable model at the interim design stage and at the final design stage ("released for construction") shall be developed to include as many of the systems described below as are necessary and appropriate at that design stage.
- 4.2. <u>Architectural/Interior Design</u>. The Architectural systems Model may vary in level of detail for individual elements, but at a minimum must include all features that would be included on a quarter inch (1/4"=1'0") scaled drawing. Additional <u>minimum</u> Model requirements include:
- 4.2.1. <u>Spaces</u>. The Model shall include spaces defining accurate net square footage and net volume, and holding data for the room finish schedule for including room names and numbers. Include Programmatic Information provided by the Government or validated program to verify design space against programmed space, using this information to validate area quantities.
- 4.2.2. <u>Walls and Curtain Walls</u>. Each wall shall be depicted to the exact height, length, width and ratings (thermal, acoustic, fire) to properly reflect wall types. The Model shall include all walls, both interior and exterior, and the necessary intelligence to produce accurate plans, sections and elevations depicting these design elements.

Section: 01 33 16 [Not Supplied]
Page 108 of 151

4.2.3. <u>Doors, Windows and Louvers</u>. Doors, windows and louvers shall be depicted to represent their actual size, type and location. Doors and windows shall be modeled with the necessary intelligence to produce accurate window and door schedules.

- 4.2.4. <u>Roof.</u> The Model shall include the roof configuration, drainage system, penetrations, specialties, and the necessary intelligence to produce accurate plans, building sections and generic wall sections where roof design elements are depicted.
- 4.2.5. <u>Floors</u>. The floor slab shall be developed in the structural Model and then referenced by the architectural Model for each floor of the Project building.
- 4.2.6. <u>Ceilings</u>. All heights and other dimensions of ceilings, including soffits, ceiling materials, or other special conditions shall be depicted in the Model with the necessary intelligence to produce accurate plans, building sections and generic wall sections where ceiling design elements are depicted.
- 4.2.7. <u>Vertical Circulation</u>. All continuous vertical components (i.e., non-structural shafts, architectural stairs, handrails and guardrails) shall be accurately depicted and shall include the necessary intelligence to produce accurate plans, elevations and sections in which such design elements are referenced.
- 4.2.8. <u>Architectural Specialties and Woodwork.</u> All architectural specialties (i.e., toilet room accessories, toilet partitions, grab bars, lockers, and display cases) and woodwork (i.e., cabinetry and counters) shall be accurately depicted with the necessary intelligence to produce accurate plans, elevations and sections in which such design elements are referenced.
- 4.2.9. <u>Signage.</u> The Model shall include all signage and the necessary intelligence to produce accurate plans and schedules.
- 4.2.10. <u>Schedules</u>. Provide door, window, hardware sets using BHMA designations, flooring, wall finish, and signage schedules from the Model, indicating the type, materials and finishes used in the design.
- 4.3. <u>Furniture.</u> The furniture systems Model may vary in level of detail for individual elements within a Model, but at a minimum must include all features that would be included on a quarter inch (1/4"=1'0") scaled drawing, and have necessary intelligence to produce accurate plans. Representation of furniture elements is to be 2D. Contractor may provide a minimal number of 3D representations as examples. Examples of furniture include, but are not limited to, desks, furniture systems, seating, tables, and office storage.
- 4.3.1. <u>Furniture Coordination</u>. Furniture that makes use of electrical, data or other features shall include the necessary intelligence to produce coordinated documents and data.
- 4.4. <u>Equipment</u>. The Model may vary in level of detail for individual elements within a Model. Equipment shall be depicted to meet layout requirements with the necessary intelligence to produce accurate plans and minimum schedules depicting their configuration. Examples of equipment include but are not limited to copiers, printers, refrigerators, ice machines and microwaves.
- 4.4.1. <u>Schedules</u>. Provide furniture and equipment schedules from the model indicating the materials, finishes, mechanical, and electrical requirements.
- 4.5. <u>Structural</u>. The structural systems Model may vary in level of detail for individual elements, but at a minimum must include all features that would be included on a quarter inch (1/4"=1'0") scaled drawing. Additional minimum Model requirements include:
- 4.5.1. <u>Foundations</u>. All necessary foundation and/or footing elements, with necessary intelligence to produce accurate plans and elevations
- 4.5.2. <u>Floor Slabs</u>. Structural floor slabs shall be depicted, including all necessary recesses, curbs, pads, closure pours, and major penetrations accurately depicted.

Section: 01 33 16 [Not Supplied]
Page 109 of 151

4.5.3. <u>Structural Steel</u>. All steel columns, primary and secondary framing members, and steel bracing for the roof and floor systems (including decks), including all necessary intelligence to produce accurate structural steel framing plans and related building/wall sections.

- 4.5.4. <u>Cast-in-Place Concrete</u>. All walls, columns, and beams, including necessary intelligence to produce accurate plans and building/wall sections depicting cast-in-place concrete elements.
- 4.5.5. <u>Expansion/Contraction Joints.</u> Joints shall be accurately depicted.
- 4.5.6. <u>Stairs</u>. The structural Model shall include all necessary openings and framing members for stair systems, including necessary intelligence to produce accurate plans and building/wall sections depicting stair design elements.
- 4.5.7. <u>Shafts and Pits</u>. The structural Model shall include all necessary shafts, pits, and openings, including necessary intelligence to produce accurate plans and building/wall sections depicting these design elements.
- 4.6. <u>Mechanical</u>. The mechanical systems Model may vary in level of detail for individual elements, but at a minimum must include all features that would be included on a quarter inch (1/4"=1'0") scaled drawing. Small diameter (less than 1-1/2" NPS) field-routed piping is not required in the model. Additional <u>minimum</u> Model requirements include:
- 4.6.1. <u>HVAC</u>. All necessary heating, ventilating, air-conditioning and specialty equipment, including air distribution ducts for supply, return, and ventilation and exhaust ducts, including control system, registers, diffusers, grills and hydronic baseboards with necessary intelligence to produce accurate plans, elevations, building/wall sections and schedules.
- 4.6.1.1. <u>Mechanical Piping</u>. All necessary piping and fixture layouts, and related equipment, including necessary intelligence to produce accurate plans, elevations, building/wall sections, and schedules.
- 4.6.2. <u>Plumbing</u>. All necessary plumbing piping and fixture layouts, floor and area drains, and related equipment, including necessary intelligence to produce accurate plans, elevations, building/wall sections, riser diagrams, and schedules.
- 4.6.3. <u>Equipment Clearances</u>. All HVAC and Plumbing equipment clearances shall be modeled for use in interference management and maintenance access requirements.
- 4.6.4. <u>Elevator Equipment</u>. The Model shall include the necessary equipment and control system, including necessary intelligence to produce accurate plans, sections and elevations depicting these design elements.
- 4.7. <u>Electrical/Telecommunications</u>. The electrical systems Model may vary in level of detail for individual elements, but at a minimum must include all features that would be included on a quarter inch (1/4"=1'0") scaled drawing. Small diameter (less than 1-1/2"Ø) field-routed conduit is not required in the model. Additional minimum Model requirements include:
- 4.7.1. <u>Interior Electrical Power and Lighting</u>. All necessary interior electrical components (i.e., lighting, receptacles, special and general purpose power receptacles, lighting fixtures, panelboards, cable trays and control systems), including necessary intelligence to produce accurate plans, details and schedules. Lighting and power built into furniture/equipment shall be modeled.
- 4.7.2. <u>Special Electrical Systems.</u> All necessary special electrical components (i.e., security, Mass Notification, Public Address, nurse call and other special occupancies, and control systems), including necessary intelligence to produce accurate plans, details and schedules.
- 4.7.3. <u>Grounding Systems.</u> <u>Grounding Systems.</u> All necessary grounding components (i.e., lightning protection systems, static grounding systems, communications grounding systems, bonding), including necessary intelligence to produce accurate plans, details and schedules.

Section: 01 33 16 [Not Supplied]
Page 110 of 151

4.7.4. <u>Communications</u>. All existing and new communications service controls and connections, both above ground and underground with necessary intelligence to produce accurate plans, details and schedules. Cable tray routing shall be modeled without detail of cable contents.

- 4.7.5. <u>Exterior Building Lighting</u>. All necessary exterior lighting with necessary intelligence to produce accurate plans, elevations and schedules. The exterior building lighting Model shall include all necessary lighting, relevant existing and proposed support utility lines and equipment required with necessary intelligence to produce accurate plans, details and schedules.
- 4.7.6. <u>Equipment Clearances</u>. The model shall incorporate and define all electrical and communications working spaces, clearances, and required access
- 4.8. <u>Fire Protection</u>. The fire protection system Model may vary in level of detail for individual elements, but at a minimum must include all features that would be included on a quarter inch (1/4"=1'0") scaled drawing. Additional <u>minimum</u> Model requirements include:
- 4.8.1. <u>Fire Protection System.</u> All relevant fire protection components (i.e., branch piping, sprinkler heads, fittings, drains, pumps, tanks, sensors, control panels) with necessary intelligence to produce accurate plans, elevations, building/wall sections, riser diagrams, and schedules. All fire protection piping shall be modeled.
- 4.8.2. <u>Fire Alarms</u>. Fire alarm/mass notification devices and detection system shall be indicated with necessary intelligence to produce accurate plans depicting them.
- 4.9. <u>Civil</u>. The civil Model may vary in level of detail for individual elements, but at a minimum must include all features that would be included on a one inch (1"=100') scaled drawing. Additional <u>minimum</u> Model requirements include:
- 4.9.1. <u>Terrain (DTM)</u>. All relevant site conditions and proposed grading, including necessary intelligence to produce accurate Project site topographical plans and cross sections.
- 4.9.2. <u>Drainage</u>. All existing and new drainage piping, including upgrades thereto, including necessary intelligence to produce accurate plans and profiles for the Project site.
- 4.9.3. <u>Storm Water and Sanitary Sewers</u>. All existing and new sewer structures and piping, including upgrades thereto, on the Project site with necessary connections to mains or other distribution points as appropriate, including necessary intelligence to produce accurate plans and profiles for the Project site.
- 4.9.4. <u>Utilities</u>. All necessary new utilities connections from the Project building(s) to the existing or newly-created utilities, and all existing above ground and underground utility conduits, including necessary intelligence to produce accurate plans and site-sections.
- 4.9.5. <u>Roads and Parking</u>. All necessary roadways and parking lots or parking structures, including necessary intelligence to produce accurate plans, profiles and cross-sections.

5.0 Section 5 - Ownership and Rights in Data

5.1. Ownership. The Government has ownership of and rights at the date of Closeout Submittal to all CAD files, BIM Model, and Facility Data developed for the Project in accordance with FAR Part 27, clauses incorporated in Section 00 72 00, Contract Clauses and Special Contract Requirement 1.14 GOVERNMENT RE-USE OF DESIGN (Section 00 73 00). The Government may make use of this data following any deliverable.

6.0 Section 6 - Contractor Electives

6.1. <u>Applicable Criteria.</u> If the Contractor elected to include one or more of the following features as an elective in its accepted contract proposal for additional credit during the source selection, as described in the proposal submission requirements and evaluation criteria, the following criteria are requirements, as applicable to those elective feature(s).

Section: 01 33 16 [Not Supplied]
Page 111 of 151

6.2. <u>COBIE Compliance.</u> The Model and Facility Data for the Project shall fulfill Construction Operations Building Information Exchange (COBIE) requirements as defined by the Whole Building Design Guide organization, including all requirements for the indexing and submission of Portable Document Format (PDF) and other appropriate file formats that would otherwise be printed and submitted in compliance with Project operations and maintenance handover requirements.

- 6.3. <u>Project Scheduling using the Model</u>. In the BIM Execution Plan and during the Preliminary BIM Execution Plan Review, provide an overview of the use of BIM in the development and support of the project construction schedule.
- 6.3.1. <u>Submittal Requirements</u>. During the Submittal stages, the Contractor shall deliver the construction schedule with information derived from the Model.
- 6.3.1.1. <u>Construction Submittals Over-The-Shoulder Progress Reviews</u>. Periodic quality control meetings or construction progress review meetings shall include quality control reviews on the implementation and use of the Model for project scheduling.
- 6.4. <u>Cost Estimating.</u> In the BIM Execution Plan and during the Preliminary BIM Execution Plan Review, provide an overview of the use of BIM in the development and support of cost estimating requirements, or other applications such as cost analysis and estimate validation.
- 6.4.1. <u>Submittal Requirements</u>. During the Submittal stages, the Contractor shall deliver cost estimating information derived from the Model.
- 6.4.2. <u>Project completion</u>. At project completion, the Contractor shall provide an MII (Micro Computer Aided Cost Estimating System Generation II) Cost Estimate which follows the USACE Cost Engineering Military Work Breakdown System (WBS), a modified Uniformat, to at least the sub-systems level and uses quantity information supplied directly from BIM output to the maximum extent possible, though other "Gap" quantity information will be included as necessary for a complete and accurate cost estimate.
- 6.4.2.1. Sub system level extracted quantities from the BIM for use within the estimate shall be provided according to how detailed line items or tasks should be installed/built so that accurate costs can be developed and/or reflected. Therefore, when developing a BIM, the designer shall be cognizant of what tasks need to be separated appropriately at the beginning stages of model development, such as tasks done on the first floor versus the same task on higher floors that will be more labor intensive and therefore need to have a separate quantity and be priced differently. Tasks and their extracted quantities from the BIM shall be broken done by their location (proximity in the structure) as well as the complexity of its installation.
- 6.4.2.2. At all design stages it shall be understood that BIM output as described in this document will not generate all quantities that are necessary in order to develop a complete and accurate cost estimate of the project based on the design. An example of this would be plumbing that is less than 1.5" diameter and therefore not expected to be modeled due to granularity; this information is commonly referred to as The Gap. Quantities from The Gap and their associated costs shall be included in the final project actual cost estimates as well.
- 6.5. Other Analyses and Reports. Structural, energy and efficiency, EPACT 2005 & EISA 2007, lighting design, daylighting, electrical power, psychrometric processing, shading, programming, LEED, fire protection, code compliance, Life Cycle Cost, acoustic, plumbing.

7.0 Section 7 – BIM Project Execution Plan Template

7.1. Contractors will utilize the latest version of the USACE BIM PROJECT EXECUTION PLAN (USACE PxP) Template to develop an acceptable Plan. The template can be downloaded from the CAD/BIM Technology Center website.

Section: 01 33 16 [Not Supplied] Page 112 of 151

Section: 01 33 16 [Not Supplied] Page 113 of 151

Section: 01 33 16

ATTACHMENT G DESIGN SUBMITTAL DIRECTORY AND SUBDIRECTORY FILE ARRANGEMENT

Organize electronic design submittal files in a subdirectory/file structure in accordance with the following table. The Contractor may suggest a slightly different structure, subject to the discretion of the government.

Design Submittal Directory and Subdirectory File Arrangement.

Directory	Sub-Directory	Sub-Directory or Files	Files
Submittal/Package	Narratives	PDF file or files with updated design	
Name		narrative for each applicable design	
		discipline	
	Drawings	PDF (subdirectory)	Single PDF file with all
			applicable drawing sheets -
			bookmarked by sheet
			number and name
		BIM (subdirectory) See Attachment F.	BIM project folder (with
			files) per the USACE
			Workspace. Include an
			Excel drawing index file with
			each drawing sheet listed
			by sheet #, name and
			corresponding dgn file
			name (Final Design &
	Decien Analysis 0	Individual DDE files containing decision	Design Complete only)
	Design Analysis & Calculations	Individual PDF files containing design	
	Calculations	analysis and calculations for each	
		discipline applicable to the submittal PDF file with Fire Protection and Life	
		Safety Code Review checklist	
	LEED	PDF file with updated Leed Check List	
		PDF file or files with LEED Templates	
		for each point with applicable	
		documentation included in each file.	
		LEED SUBMITTALS	
	Energy Analysis	PDF with baseline energy consumption	
	3, 1,11	analysis	
		PDF with actual building energy	
		consumption analysis	
	Specifications	Single PDF file with table of contents	
		and all applicable specifications	
		sections.	
		Submittal Register (Final Design &	
		Design Complete submittal only)	
	Design Quality	PDF file or files with DQC checklist(s)	
	Control	and/or statements	
	Building	PDF file of rendering for each building	
	Rendering(s)	type included in contract (Final Design	
		& Design Complete).	

Section: 01 45 04.00 10 [Not Supplied] Page 115 of 151

SECTION 01 45 04.00 10 CONTRACTOR QUALITY CONTROL

1.0 GENERAL	
-------------	--

- 1.1. REFERENCES
- 1.2. PAYMENT
- 2.0 PRODUCTS (NOT APPLICABLE)
- 3.0 EXECUTION
- 3.1. GENERAL REQUIREMENTS
- 3.2. QUALITY CONTROL PLAN
- 3.3. COORDINATION MEETING
- 3.4. QUALITY CONTROL ORGANIZATION
- 3.5. SUBMITTALS AND DELIVERABLES
- 3.6. CONTROL
- 3.7. TESTS
- 3.8. COMPLETION INSPECTION
- 3.9. DOCUMENTATION
- 3.10. NOTIFICATION OF NONCOMPLIANCE

Section: 01 45 04.00 10 [Not Supplied]
Page 116 of 151

1.0 GENERAL

1.1. REFERENCES

The publications listed below form a part of this specification to the extent referenced. The publications are referred to within the text by the basic designation only. Refer to the latest edition, as of the date of the contract solicitation.

- ASTM INTERNATIONAL (ASTM)
- ASTM D 3740 Minimum Requirements for Agencies

Engaged in the Testing and/or Inspection of Soil and Rock as Used in Engineering Design and Construction

- ASTM E 329 Agencies Engaged in the Testing and/or Inspection of Materials Used in Construction
- U.S. ARMY CORPS OF ENGINEERS (USACE)
 ER 1110-1-12 Quality Management

1.2. PAYMENT

There will be no separate payment for providing and maintaining an effective Quality Control program. Include all costs associated therewith in the applicable unit prices or lump-sum prices contained in the Contract Line Item Schedule.

2.0 PRODUCTS (Not Applicable)

3.0 EXECUTION

3.1. GENERAL REQUIREMENTS

The Contractor is responsible for quality control and shall establish and maintain an effective quality control system in compliance with the Contract Clause titled "Inspection of Construction." The quality control system shall consist of plans, procedures, and organization necessary to produce an end product, which complies with the contract requirements. The system shall cover all design and construction operations, both onsite and offsite, and shall be keyed to the proposed design and construction sequence. The site project superintendent is responsible for the quality of work on the job and is subject to removal by the Contracting Officer for non-compliance with the quality requirements specified in the contract. The site project superintendent in this context shall be the highest level manager responsible for the overall construction activities at the site, including quality and production. The site project superintendent shall maintain a physical presence at the site at all times, except as otherwise acceptable to the Contracting Officer, and shall be responsible for all construction and construction related activities at the site.

3.2. QUALITY CONTROL PLAN

Furnish for Government review, not later than 30 days after receipt of notice to proceed, the Contractor Quality Control (CQC) Plan proposed to implement the requirements of the Contract Clause titled "Inspection of Construction." The plan shall identify personnel, procedures, control, instructions, tests, records, and forms to be used. The Government will consider an interim plan for the first 30 days of operation. Design and construction may begin only after acceptance of the CQC Plan or acceptance of an interim plan applicable to the particular feature of work to be started. The Government will not permit work outside of the features of work included in an accepted interim plan to begin until acceptance of a CQC Plan or another interim plan containing the additional features of work to be started. Where the applicable Code issued by the International Code Council calls for an inspection by the Building Official, the Contractor shall include the inspections in the Quality Control Plan and shall perform the inspections. The Designer of Record shall develop a program for any special inspections required by the applicable International Codes and the Contractor shall perform these inspections, using qualified inspectors. Include the special inspection plan in the QC Plan.

Section: 01 45 04.00 10 [Not Supplied] Page 117 of 151

3.2.1. Content of the CQC Plan

The CQC Plan shall include, as a minimum, the following to cover all design and construction operations, both onsite and offsite, including work by subcontractors, fabricators, suppliers, and purchasing agents subcontractors, designers of record, consultants, architect/engineers (AE), fabricators, suppliers, and purchasing agents:

- 3.2.1.1. A description of the quality control organization. Include a chart showing lines of authority and an acknowledgment that the CQC staff shall implement the three phase control system for all aspects of the work specified. A CQC System Manager shall report to the project superintendent or someone higher in the contractor's organization.
- 3.2.1.2. The name, qualifications (in resume format), duties, responsibilities, and authorities of each person assigned a CQC function. Also include those responsible for performing and documenting the inspections required by the International Codes and the special inspection program developed by the designer of record.
- 3.2.1.3. A copy of the letter to the CQC System Manager, signed by an authorized official of the firm, which describes the responsibilities and delegates sufficient authorities to adequately perform the functions of the CQC System Manager, including authority to stop work which is not in compliance with the contract. The CQC System Manager shall issue letters of direction to all other various quality control representatives outlining duties, authorities, and responsibilities. Furnish copies of these letters.
- 3.2.1.4. Procedures for scheduling, reviewing, certifying, and managing submittals, including those of subcontractors, offsite fabricators, suppliers, and purchasing agents subcontractors, designers of record, consultants, architect engineers (AE), offsite fabricators, suppliers, and purchasing agents. These procedures shall be in accordance with Section 01 33 00 SUBMITTAL PROCEDURES.
- 3.2.1.5. Control, verification, and acceptance testing procedures for each specific test to include the test name, specification paragraph requiring test, feature of work to be tested, test frequency, and person responsible for each test. Use only Government approved Laboratory facilities.
- 3.2.1.6. Procedures for tracking preparatory, initial, and follow-up control phases and control, verification, and acceptance tests including documentation.
- 3.2.1.7. Procedures for tracking design and construction deficiencies from identification through acceptable corrective action. These procedures shall establish verification that identified deficiencies have been corrected.
- 3.2.1.8. Reporting procedures, including proposed reporting formats.
- 3.2.1.9. A list of the definable features of work. A definable feature of work is a task, which is separate and distinct from other tasks, has separate control requirements, and may be identified by different trades or disciplines, or it may be work by the same trade in a different environment. Although each section of the specifications may generally be considered as a definable feature of work, there are frequently more than one definable feature under a particular section. This list will be agreed upon during the coordination meeting.
- 3.2.1.10. A list of all inspections required by the International Codes and the special inspection program required by the code and this contract.
- 3.2.2. Additional Requirements for Design Quality Control (DQC) Plan

The following additional requirements apply to the Design Quality Control (DQC) plan:

3.2.2.1. The Contractor's QCP Plan shall provide and maintain a Design Quality Control (DQC) Plan as an effective quality control program which will assure that all services required by this design-build contract are performed and provided in a manner that meets professional architectural and engineering quality standards. As a minimum, competent, independent reviewers identified in the DQC Plan shall review all documents. Use personnel who were not involved in the design effort to produce the design to perform the independent technical review (ITR). The ITR is intended as a quality control check of the design. Include, at least, but not necessarily limited to, a review of the contract requirements (the accepted contract or task order proposal and amended RFP), the basis of design, design calculations, the design configuration management documentation and check the design documents for

Section: 01 45 04.00 10 [Not Supplied] Page 118 of 151

errors, omissions, and for coordination and design integration. The ITR team is not required to examine, compare or comment concerning alternate design solutions but should concentrate on ensuring that the design meets the contract requirements. Correct errors and deficiencies in the design documents prior to submitting them to the Government.

- 3.2.2.2. Include in the DQC Plan the discipline-specific checklists to be used during the design and quality control of each submittal. Submit these completed checklists at each design phase as part of the project documentation.
- 3.2.2.3. A Design Quality Control Manager, who has the responsibility of being cognizant of and assuring that all documents on the project have been coordinated, shall implement the DQC Plan This individual shall be a person who has verifiable engineering or architectural design experience and is a registered professional engineer or architect. Notify the Government, in writing, of the name of the individual, and the name of an alternate person assigned to the position.

3.2.3. Acceptance of Plan

Government acceptance of the Contractor's plan is required prior to the start of design and construction. Acceptance is conditional and will be predicated on satisfactory performance during the design and construction. The Government reserves the right to require the Contractor to make changes in his CQC Plan and operations including removal of personnel, as necessary, to obtain the quality specified.

3.2.4. Notification of Changes

After acceptance of the CQC Plan, notify the Government in writing of any proposed change. Proposed changes are subject to Government acceptance.

3.3. COORDINATION MEETING

After the Postaward Conference, before start of design or construction, and prior to acceptance by the Government of the CQC Plan, the Contractor and the Government shall meet and discuss the Contractor's quality control system. Submit the CQC Plan for review a minimum of 7 calendar days prior to the Coordination Meeting. During the meeting, a mutual understanding of the system details shall be developed, including the forms for recording the CQC operations, design activities, control activities, testing, administration of the system for both onsite and offsite work, and the interrelationship of Contractor's Management and control with the Government's Quality Assurance. The Government will prepare minutes of the meeting for signature by both parties. The minutes shall become a part of the contract file. There may be occasions when either party will call for subsequent conferences to reconfirm mutual understandings and/or address deficiencies in the CQC system or procedures which may require corrective action by the Contractor.

3.4. QUALITY CONTROL ORGANIZATION

3.4.1. Personnel Requirements

The requirements for the CQC organization are a CQC System Manager, a Design Quality Manager, and sufficient number of additional qualified personnel to ensure contract compliance. The CQC organization shall also include personnel identified in the technical provisions as requiring specialized skills to assure the required work is being performed properly. The Contractor's CQC staff shall maintain a presence at the site at all times during progress of the work and have complete authority and responsibility to take any action necessary to ensure contract compliance. The CQC staff shall be subject to acceptance by the Contracting Officer. Provide adequate office space, filing systems and other resources as necessary to maintain an effective and fully functional CQC organization. Promptly furnish complete records of all letters, material submittals, shop drawing submittals, schedules and all other project documentation to the CQC organization. The CQC organization shall be responsible to maintain these documents and records at the site at all times, except as otherwise acceptable to the Contracting Officer.

3.4.2. CQC System Manager

Identify as CQC System Manager an individual within the onsite work organization who shall be responsible for overall management of CQC and have the authority to act in all CQC matters for the Contractor. The CQC System

Section: 01 45 04.00 10 [Not Supplied] Page 119 of 151

Manager shall be a graduate engineer, graduate architect, or a BA/BS graduate of an ACCE accredited construction management college program. The CQC system Manager may alternately be an engineering technician with at least 2 years of college and an ICC certification as a Commercial Building Inspector (Residential Building Inspector certification will be required for Military Family Housing projects). In addition, the CQC system manager shall have a minimum of 5 years construction experience on construction similar to this contract. The CQC System Manager shall be on the site at all times during construction and shall be employed by the prime Contractor. Assign the CQC System Manager no other duties (except may also serve as Safety and Health Officer, if qualified and if allowed by Section 00 73 00). Identify an alternate for the CQC System Manager in the plan to serve in the event of the System Manager's absence. The requirements for the alternate shall be the same as for the designated CQC System Manager but the alternate may have other duties in addition to serving in a temporary capacity as the acting QC manager.

- 3.4.3. CQC Personnel
- 3.4.3.1. In addition to CQC personnel specified elsewhere in the contract provide specialized CQC personnel to assist the CQC System Manager in accordance with paragraph titled Area Qualifications.
- 3.4.3.2. These individuals may be employees of the prime or subcontractor; be responsible to the CQC System Manager; are not intended to be full time, but must be physically present at the construction site during work on their areas of responsibility; have the necessary education and/or experience in accordance with the experience matrix listed herein. These individuals may perform other duties but must be allowed sufficient time to perform their assigned quality control duties as described in the Quality Control Plan. One person may cover more than one area, provided that they are qualified to perform QC activities for the designated areas below and provided that they have adequate time to perform their duties:
- 3.4.4. Experience Matrix
- 3.4.4.1. Area Qualifications
- 3.4.4.1.1. Civil Graduate Civil Engineer or (BA/BS) graduate in construction management with 4 years experience in the type of work being performed on this project or engineering technician with 5 yrs related experience.
- 3.4.4.1.2. Mechanical Graduate Mechanical Engineer or (BA/BS) graduate in construction management with 4 yrs related experience or engineering technician with an ICC certification as a Commercial Mechanical Inspector with 5 yrs related experience.
- 3.4.4.1.3. Electrical Graduate Electrical Engineer or (BA/BS) graduate in construction management with 4 yrs related experience or engineering technician with an ICC certification as a Commercial Electrical Inspector with 5 yrs related experience.
- 3.4.4.1.4. Structural Graduate Structural Engineer or (BA/BS) graduate in construction management with 4 yrs related experience or person with an ICC certification as a Reinforced Concrete Special Inspector and Structural Steel and Bolting Special Inspector (as applicable to the type of construction involved) with 5 yrs related experience.
- 3.4.4.1.5. Plumbing Graduate Mechanical Engineer or (BA/BS) graduate in construction management with 4 yrs related experience, or person with an ICC certification as a Commercial Plumbing Inspector with 5 yrs related experience.
- 3.4.4.1.6. Concrete, Pavements and Soils Materials Technician (present while performing tests) with 2 yrs experience for the appropriate area
- 3.4.4.1.7. Testing, Adjusting and Balancing Specialist must be a member (TAB) Personnel of AABC or an experienced technician of the firm certified by the NEBB (present while testing, adjusting, balancing).
- 3.4.4.1.8. Design Quality Control Manager Registered Architect or Professional Engineer (not required on the construction site)

Section: 01 45 04.00 10 [Not Supplied]
Page 120 of 151

3.4.4.1.9. Registered Fire Protection Engineer with 4 years related experience or engineering technician with 5 yrs related experience (but see requirements for Fire Protection Engineer of Record to witness final testing in Section 01 10 00, paragraph 5.10, Fire Protection).

3.4.4.1.10. QC personnel assigned to the installation of the telecommunication system or any of its components shall be Building Industry Consulting Services International (BICSI) Registered Cabling Installers, Technician Level. Submit documentation of current BICSI certification. In lieu of BICSI certification, QC personnel shall have a minimum of 5 years experience in the installation of the specified copper and fiber optic cable and components. They shall have factory or factory approved certification from each equipment manufacturer indicating that they are qualified to install and test the provided products. QC personnel shall witness and certify the testing of telecommunications cabling and equipment.

3.4.5. Additional Requirement

In addition to the above experience and/or education requirements the CQC System Manager shall have completed the course entitled "Construction Quality Management for Contractors". This course is periodically offered at [Not Supplied - ConstructionReqQC : COURSE_LOCATION]. Inquire of the District or Division sponsoring the course for fees and other expenses involved, if any, for attendance at this course.

3.4.6. Organizational Changes

When it is necessary to make changes to the CQC staff, the Contractor shall revise the CQC Plan to reflect the changes and submit the changes to the Contracting Officer for acceptance.

3.5. SUBMITTALS AND DELIVERABLES

Make submittals as specified in Section 01 33 00 **SUBMITTAL PROCEDURES**. The CQC organization shall certify that all submittals and deliverables are in compliance with the contract requirements.

3.6. CONTROL

Contractor Quality Control is the means by which the Contractor ensures that the construction, to include that of subcontractors and suppliers, complies with the requirements of the contract. The CQC organization shall conduct at least three phases of control for each definable feature of the construction work as follows:

3.6.1. Preparatory Phase

Perform this phase prior to beginning work on each definable feature of work, after all required plans/documents/materials are approved/accepted, and after copies are at the work site. This phase shall include:

- 3.6.1.1. A review of each paragraph of applicable specifications, reference codes, and standards. Make a copy of those sections of referenced codes and standards applicable to that portion of the work to be accomplished in the field at the preparatory inspection. Maintain these copies in the field, available for use by Government personnel until final acceptance of the work.
- 3.6.1.2. A review of the contract drawings.
- 3.6.1.3. A check to assure that all materials and/or equipment have been tested, submitted, and approved.
- 3.6.1.4. Review of provisions that have been made to provide required control inspection and testing.
- 3.6.1.5. Examination of the work area to assure that all required preliminary work has been completed and is in compliance with the contract.
- 3.6.1.6. A physical examination of required materials, equipment, and sample work to assure that they are on hand, conform to approved shop drawings or submitted data, and are properly stored.
- 3.6.1.7. A review of the appropriate activity hazard analysis to assure safety requirements are met.

Section: 01 45 04.00 10 [Not Supplied]
Page 121 of 151

3.6.1.8. Discussion of procedures for controlling quality of the work including repetitive deficiencies. Document construction tolerances and workmanship standards for that feature of work.

- 3.6.1.9. A check to ensure that the portion of the plan for the work to be performed has been accepted by the Contracting Officer.
- 3.6.1.10. Discussion of the initial control phase.
- 3.6.1.11. Notify the Government at least 24 hours in advance of beginning the preparatory control phase. This phase shall include a meeting conducted by the CQC System Manager and attended by the superintendent, other CQC personnel (as applicable), and the foreman responsible for the definable feature. Document the results of the preparatory phase actions by separate minutes prepared by the CQC System Manager and attached to the daily CQC report. The Contractor shall instruct applicable workers as to the acceptable level of workmanship required in order to meet contract specifications.

3.6.2. Initial Phase

Accomplish this phase at the beginning of a definable feature of work. Include the following actions:

- 3.6.2.1. Check work to ensure that it is in full compliance with contract requirements. Review minutes of the preparatory meeting.
- 3.6.2.2. Verify adequacy of controls to ensure full contract compliance. Verify required control inspection and testing.
- 3.6.2.3. Establish level of workmanship and verify that it meets minimum acceptable workmanship standards. Compare with required sample panels as appropriate.
- 3.6.2.4. Resolve all differences.
- 3.6.2.5. Check safety to include compliance with and upgrading of the Accident Prevention plan and activity hazard analysis. Review the activity analysis with each worker.
- 3.6.2.6. Notify the Government at least 24 hours in advance of beginning the initial phase. The CQC System Manager shall prepare and attach to the daily CQC report separate minutes of this phase. Indicate exact location of initial phase for future reference and comparison with follow-up phases.
- 3.6.2.7. Repeat the initial phase any time acceptable specified quality standards are not being met.

3.6.3. Follow-up Phase

Perform daily checks to assure control activities, including control testing, are providing continued compliance with contract requirements, until completion of the particular feature of work. The checks shall be made a matter of record in the CQC documentation. Conduct final follow-up checks and correct deficiencies prior to the start of additional features of work which may be affected by the deficient work. Do not build upon nor conceal non-conforming work.

3.6.4. Additional Preparatory and Initial Phases

Conduct additional preparatory and initial phases on the same definable features of work if: the quality of on-going work is unacceptable; if there are changes in the applicable CQC staff, onsite production supervision or work crew; if work on a definable feature is resumed after a substantial period of inactivity; or if other problems develop.

3.7. TESTS

3.7.1. Testing Procedure

Perform specified or required tests to verify that control measures are adequate to provide a product which conforms to contract requirements and project design documents. Upon request, furnish to the Government

Section: 01 45 04.00 10 [Not Supplied]
Page 122 of 151

duplicate samples of test specimens for possible testing by the Government. Testing includes operation and/or acceptance tests when specified. The Contractor shall procure the services of a Corps of Engineers approved testing laboratory, or establish an approved testing laboratory at the project site. The Contractor may elect to use a laboratory certified and accredited by the Concrete and cement Reference Laboratory (CCRL) or by AASHTO Materials Reference Laboratory (AMRL) for testing procedures that those organizations certify. The Contractor shall perform the following activities and record and provide the following data:

- 3.7.1.1. Verify that testing procedures comply with contract requirements and project design documents.
- 3.7.1.2. Verify that facilities and testing equipment are available and comply with testing standards.
- 3.7.1.3. Check test instrument calibration data against certified standards.
- 3.7.1.4. Verify that recording forms and test identification control number system, including all of the test documentation requirements, have been prepared.
- 3.7.1.5. Include results of all tests taken, both passing and failing tests, recorded on the CQC report for the date taken. Include specification paragraph reference, location where tests were taken, and the sequential control number identifying the test. If approved by the Contracting Officer, actual test reports may be submitted later with a reference to the test number and date taken. Provide an information copy of tests performed by an offsite or commercial test facility directly to the Contracting Officer. Failure to submit timely test reports as stated may result in nonpayment for related work performed and disapproval of the test facility for this contract.
- 3.7.2. Testing Laboratories

3.7.2.1. Capability Check

The Government reserves the right to check laboratory equipment in the proposed laboratory for compliance with the standards set forth in the contract specifications and to check the laboratory technician's testing procedures and techniques. Laboratories utilized for testing soils, concrete, asphalt, and steel shall meet criteria detailed in ASTM D 3740 and ASTM E 329.

3.7.2.2. Capability Recheck

If the selected laboratory fails the capability check, the Government will assess the Contractor a charge of \$1,375 to reimburse the Government for each succeeding recheck of the laboratory or the checking of a subsequently selected laboratory. Such costs will be deducted from the contract amount due the Contractor.

3.7.3. Onsite Laboratory

The Government reserves the right to utilize the Contractor's control testing laboratory and equipment to make assurance tests, and to check the Contractor's testing procedures, techniques, and test results at no additional cost to the Government.

3.7.4. Furnishing or Transportation of Samples for Government Quality Assurance Testing

The Contractor is responsible for costs incidental to the transportation of samples or materials. Deliver samples of materials for test verification and acceptance testing by the Government to the Corps of Engineers Laboratory, f.o.b., at the following address:

For delivery by mail:

[Not Supplied - ConstructionReqQC : LAB_NAME]

[Not Supplied - ConstructionReqQC : LAB ATTN]

[Not Supplied - ConstructionReqQC : LAB_MAIL]

[Not Supplied - ConstructionReqQC : LAB_STATE]

For other deliveries:

[Not Supplied - ConstructionReqQC : LAB NAME OTHER]

Section: 01 45 04.00 10 [Not Supplied]
Page 123 of 151

[Not Supplied - ConstructionReqQC : LAB_ATTN_OTHER]
[Not Supplied - ConstructionReqQC : LAB_MAIL_OTHER]
[Not Supplied - ConstructionReqQC : LAB_STATE_OTHER]

The area or resident office will coordinate, exact delivery location, and dates for each specific test.

3.8. COMPLETION INSPECTION

3.8.1. Punch-Out Inspection

Near the end of the work, or any increment of the work established by a time stated in the SPECIAL CONTRACT REQUIREMENTS Clause, "Commencement, Prosecution, and Completion of Work", or by the specifications, the CQC Manager shall conduct an inspection of the work. Prepare a punch list of items which do not conform to the approved drawings and specifications and include in the CQC documentation, as required by paragraph DOCUMENTATION. The list of deficiencies shall include the estimated date by which the deficiencies will be corrected. The CQC System Manager or staff shall make a second inspection to ascertain that all deficiencies have been corrected. Once this is accomplished, the Contractor shall notify the Government that the facility is ready for the Government Pre-Final inspection.

3.8.2. Pre-Final Inspection

As soon as practicable after the notification above, the Government will perform the pre-final inspection to verify that the facility is complete and ready to be occupied. A Government Pre-Final Punch List may be developed as a result of this inspection. The Contractor's CQC System Manager shall ensure that all items on this list have been corrected before notifying the Government, so that a Final inspection with the customer can be scheduled. Correct any items noted on the Pre-Final inspection in a timely manner. Accomplish these inspections and any deficiency corrections required by this paragraph within the time slated for completion of the entire work or any particular increment of the work if the project is divided into increments by separate completion dates.

3.8.3. Final Acceptance Inspection

The Contractor's Quality Control Inspection personnel, plus the superintendent or other primary management person, and the Contracting Officer's Representative shall attend the final acceptance inspection. Additional Government personnel including, but not limited to, those from Base/Post Civil Facility Engineer user groups and major commands may also attend. The Government will formally schedule the final acceptance inspection based upon results of the Pre-Final inspection. Provide notice to the Government at least 14 days prior to the final acceptance inspection and include the Contractor's assurance that all specific items previously identified to the Contractor as being unacceptable, along with all remaining work performed under the contract, will be complete and acceptable by the date scheduled for the final acceptance inspection. Failure of the Contractor to have all contract work acceptably complete for this inspection will be cause for the Contracting Officer to bill the Contractor for the Government's additional inspection cost in accordance with the contract clause titled "Inspection of Construction".

3.9. DOCUMENTATION

- 3.9.1. Maintain current records providing factual evidence that required quality control activities and/or tests have been performed. These records shall include the work of subcontractors and suppliers using government-provided software, QCS (see Section 01 45 01.10). The report includes, as a minimum, the following information:
- 3.9.1.1. Contractor/subcontractor and their area of responsibility.
- 3.9.1.2. Operating plant/equipment with hours worked, idle, or down for repair.
- 3.9.1.3. Work performed each day, giving location, description, and by whom. When Network Analysis (NAS) is used, identify each phase of work performed each day by NAS activity number.

Section: 01 45 04.00 10 [Not Supplied]
Page 124 of 151

3.9.1.4. Test and/or control activities performed with results and references to specifications/drawings requirements. Identify the applicable control phase (Preparatory, Initial, Follow-up). List deficiencies noted, along with corrective action.

- 3.9.1.5. Quantity of materials received at the site with statement as to acceptability, storage, and reference to specifications/drawings requirements.
- 3.9.1.6. Submittals and deliverables reviewed, with contract reference, by whom, and action taken.
- 3.9.1.7. Offsite surveillance activities, including actions taken.
- 3.9.1.8. Job safety evaluations stating what was checked, results, and instructions or corrective actions.
- 3.9.1.9. Instructions given/received and conflicts in plans and/or specifications.
- 3.9.1.10. Provide documentation of design quality control activities. For independent design reviews, provide, as a minimum, identity of the ITR team, the ITR review comments, responses and the record of resolution of the comments.
- 3.9.2. Contractor's verification statement.

These records shall indicate a description of trades working on the project; the number of personnel working; weather conditions encountered; and any delays encountered. These records shall cover both conforming and deficient features and shall include a statement that equipment and materials incorporated in the work and workmanship comply with the contract. Furnish the original and one copy of these records in report form to the Government daily within 24 hours after the date covered by the report, except that reports need not be submitted for days on which no work is performed. As a minimum, submit one report for every 7 days of no work and on the last day of a no work period. Account for all calendar days throughout the life of the contract. The first report following a day of no work shall be for that day only. The CQC System Manager shall sign and date reports. The report shall include copies of test reports and copies of reports prepared by all subordinate quality control personnel. The Contractor may submit these forms electronically, in lieu of hard copy.

3.10. NOTIFICATION OF NONCOMPLIANCE

The Contracting Officer will notify the Contractor of any detected noncompliance with the foregoing requirements. The Contractor shall take immediate corrective action after receipt of such notice. Such notice, when delivered to the Contractor at the work site, shall be deemed sufficient for the purpose of notification. If the Contractor fails or refuses to comply promptly, the Contracting Officer may issue an order stopping all or part of the work until satisfactory corrective action has been taken. No part of the time lost due to such stop orders shall be made the subject of claim for extension of time or for excess costs or damages by the Contractor.

End of Section 01 45 04.00 10

Section: 01 50 02 [Not Supplied]
Page 125 of 151

SECTION 01 50 02.[Not Supplied - ProjectInfo : TONUM] TEMPORARY CONSTRUCTION FACILITIES

- 1.0 OVERVIEW
- 1.1. GENERAL REQUIREMENTS
- 1.3. BULLETIN BOARD, PROJECT SIGN, AND PROJECT SAFETY SIGN

Section: 01 50 02 [Not Supplied]
Page 126 of 151

1.0 OVERVIEW

- 1.1. GENERAL REQUIREMENTS
- 1.1.1. This section contains requirements specifically applicable to this task order. The requirements of Base ID/IQ contract Section 01 50 02 apply to this task order, except as otherwise specified herein.
- 1.3. BULLETIN BOARD, PROJECT SIGN, AND PROJECT SAFETY SIGN
- 1.3.1. Bulletin Board (As Specified in Base contract)
- 1.3.2. Project and Safety Signs (Added to Stress standardization of signs, in the event that the Base ID/IQ Section 01 50 02 does not contain this information)

Erect a project sign and a site safety sign with informational details as provided by the Government at the Post award conference, within 15 days prior to any work activity on project site. Update the safety sign data daily, with light colored metallic or non-metallic numerals. Remove the signs from the site upon completion of the project. Engineer Pamphlet EP 310-1-6a contains the standardized layout and construction details for the signs. It can be found through a GOOGLE Search or try http://www.usace.army.mil/publications/eng-pamphlets/ep310-1-6a/s-16.pdf.

End of Section 01 50 02.[Not Supplied - ProjectInfo: TONUM]

Section: APPENDIX A [Not Supplied]
Page 127 of 151

APPENDIX A Geotechnical Information

Section: APPENDIX B [Not Supplied]
Page 128 of 151

APPENDIX B List of Drawings

Section: APPENDIX C [Not Supplied]
Page 129 of 151

APPENDIX C Utility Connections

Section: APPENDIX D [Not Supplied]
Page 130 of 151

APPENDIX D Results of Fire Flow Tests

Section: APPENDIX E [Not Supplied]
Page 131 of 151

APPENDIX E Environmental Information

Section: APPENDIX F [Not Supplied]
Page 132 of 151

APPENDIX F Conceptual Aesthetic Considerations

Section: APPENDIX G [Not Supplied]
Page 133 of 151

APPENDIX G GIS Data

Section: APPENDIX H [Not Supplied]
Page 134 of 151

APPENDIX H Exterior Signage

Section: APPENDIX I [Not Supplied]
Page 135 of 151

APPENDIX I Acceptable Plants List

Section: APPENDIX J [Not Supplied]
Page 136 of 151

APPENDIX J Drawings

Section: APPENDIX K [Not Supplied]
Page 137 of 151

APPENDIX K Fuel Cost Information

The following utility rates for this installation are provided for design

Electrical:

Demand Charge - \$xx.xx per kilowatt

Energy Charge - \$ x.xx per kilowatt-hour Blended Rate - \$ x.xx per kilowatt-hour (blended annual energy and demand cost)

Natural Gas:

Commodity Charge Rate - \$ x.xx per thousand cubic feet

Water:

Commodity Charge Rate - \$x.xx per [volume]

Sewer

Commodity Charge Rate - \$x.xx per [volume]

Purchased/Central Steam:

Commodity Charge Rate - \$x.xx per [unit of measure]

Purchased High Temperature Water:

Commodity Charge Rate - \$x.xx per [unit of measure]

Purchased Chilled Water:

Commodity Charge Rate - \$x.xx per [unit of measure]

APPENDIX L

LEED Project Credit Guidance (MAY 10)

This spreadsheet indicates Army required credits, Army preferred credits, project-specific ranking of individual point preferences, assumptions guidance for individual credits, and references to related language in the RFP for individual credits.

LEED Credit Paragraph	LEED Project Credit Guidance	Army Guidance: Required - Preferred - Avoid	Project Preference Ranking: (1=most preferred, blank=no preference, X=preference not applicable to this credit, Rqd=required)	
PAR	FEATURE		Pro	REMARKS
SUSTAINABLE SITES		T		
SSPR1	Construction Activity Pollution Prevention (PREREQUISITE)	Rqd	Rqd	All LEED prerequisites are required to be met.
SS1	Site Selection	·	Х	See paragraph LEED CREDITS COORDINATION.

SS2	Development Density & Community Connectivity - OPTION 1 DENSITY Development Density & Community Connectivity - OPTION 2 CONNECTIVITY		X	See paragraph LEED CREDITS COORDINATION. See paragraph LEED CREDITS COORDINATION.
SS3	Brownfield Redevelopment		X	See paragraph LEED CREDITS COORDINATION.
SS4.1	Alternative Transportation: Public Transportation Access		X	See paragraph LEED CREDITS COORDINATION.
SS4.2	Alternative Transportation: Bicycle Storage & Changing Rooms	Pref		Assume that non-transient building occupants are NOT housed on Post unless indicated otherwise. Requires provision of
SS4.3	Alternative Transportation: Low Emitting & Fuel Efficient Vehicles - OPTION 1			vehicles, which cannot be purchased with construction funds. Assume Government will not provide vehicles unless indicated otherwise. Assume that 50% of GOV fleet is NOT alternative fuel vehicles unless indicated otherwise.
SS4.3	Alternative Transportation: Low Emitting & Fuel Efficient Vehicles - OPTION 2	Pref		
SS4.3	Alternative Transportation: Low Emitting & Fuel Efficient Vehicles - OPTION 3			Requires provision of vehicle refueling stations. Installation must support type of fuel and commit to maintaining/supporting refueling stations.
SS4.4	Alternative Transportation: Parking Capacity	Pref		

	1			
	Site Development: Protect or			
SS5.1	Restore Habitat			
				Assume AGMBC option
				for aggregated open space at another location
				on the installation is not
	0, 5			available to the project
SS5.2	Site Development: Maximize Open Space	Pref		unless indicated otherwise.
000.2	Opuse	1 101		See paragraph
0004	Starmwater Designs Overtity Control	Drof		STORMWATER
SS6.1	Stormwater Design: Quantity Control	Pref		MANAGEMENT. See paragraph
				STORMWATER
SS6.2	Stormwater Design: Quality Control	Pref		MANAGEMENT.
SS7.1	Heat Island Effect: Non-Roof			Occupied to the little of the
				Coordinate with nearby airfield requirements,
				which may preclude this
SS7.2	Heat Island Effect: Roof	Pref		credit.
000	Links Dellusian Deducation	Dest		
SS8	Light Pollution Reduction	Pref		
WATER EFFICIENCY				
	Water Use Reduction (Version 3			All LEED prerequisites
WEPR1	only)	Rqd	Rqd	are required to be met.
				See paragraph IRRIGATION. Project
				must include landscaping
\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\	Water Efficient Landscaping:	D		to be eligible for this
WE1.1	Reduce by 50%	Pref		credit. Project must include
	Water Efficient Landscaping: No			landscaping to be eligible
WE1.2	Potable Water Use or No Irrigation	Pref		for this credit.
WE2	Innovative Wastewater			
VV CZ	Technologies - OPTION 1			
WE2	Innovative Wastewater Technologies - OPTION 2			
V V L Z	Technologies - OF HON 2			See paragraph
\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\				BUILDING WATER USE
WE3	Water Use Reduction	Pref		REDUCTION.
]		

ENERGY AND ATMOSPHE	RE			
EAPR1	Fundamental Commissioning of the Building Energy Systems (PREREQUISITE)	Rqd	Rqd	All LEED prerequisites are required to be met.
EAPR2	Minimum Energy Performance (PREREQUISITE)	Rqd	Rqd	All LEED prerequisites are required to be met.
EAPR3	Fundamental Refrigerant Management (PREREQUISITE)	Rqd	Rqd	All LEED prerequisites are required to be met. Earning of LEED EA1 points as indicated in
EA1	Optimize Energy Performance	Rqd	1	paragraph ENERGY CONSERVATION, as a minimum, is required.
EA2.1	On-Site Renewable Energy	Pref		See paragraph ENERGY CONSERVATION.
EA3	Enhanced Commissioning	Rqd		See paragraph COMMISSIONING. The Commissioning Authority may be provided through the Design-Build Contractor only if in accordance with USGBC Credit Interpretation Ruling (CIR) dated 9/15/06. Commissioning Authority activities begin during design phase and continue well beyond beneficial occupancy. Assume Government will not provide CxA post- occupancy activities unless indicated otherwise.
EA4	Enhanced Refrigerant Management			
EA5	Measurement & Verification			Assume Government will not provide post-occupancy activities unless indicated otherwise.
EA6	Green Power		X	See paragraph LEED CREDITS COORDINATION.

MATERIALS AND RE	SOURCES			
	Storage & Collection of Recyclables	Dad	David	All LEED prerequisites are required to be met. Coordinate with Installation during design development on collection
MRPR1	(PREREQUISITE)	Rqd	Rqd	service and receptacles.
MR1	Building Reuse			
MR2.1	Construction Waste Management: Divert 50% From Disposal	Pref		See paragraph CONSTRUCTION AND DEMOLITION WASTE MANAGEMENT.
MR2.2	Construction Waste Management: Divert 75% From Disposal	Pref		
MR3	Materials Reuse			
WINCO	Wateriale Rease			
MR4.1	Recycled Content: 10% (post- consumer + 1/2 pre-consumer)	Pref		See paragraph RECYCLED CONTENT.
MR4.2	Recycled Content: 20% (post- consumer + 1/2 pre-consumer)	Pref		
MR5.1	Regional Materials:10% Extracted, Processed & Manufactured Regionally			
MR5.2	Regional Materials:20% Extracted, Processed & Manufactured Regionally			

MR6	Rapidly Renewable Materials Certified Wood	Pref Pref		See paragraph BIOBASED AND ENVIRONMENTALLY PREFERABLE MATERIALS and paragraph FEDERAL BIOBASED PRODUCTS PREFERRED PROCUREMENT PROGRAM. See paragraph BIOBASED AND ENVIRONMENTALLY PREFERABLE MATERIALS.
INDOOR ENVIRONMENTAL	_ QUALITY			
EQPR1		Rqd	Rqd	All LEED prerequisites are required to be met.
EQPR2		Rqd	Rqd	All LEED prerequisites are required to be met. Assume all buildings are smoke free unless indicated otherwise (family housing, barracks and other lodging are facility types where smoking may be permitted in some cases).
EQ1	Outdoor Air Delivery Monitoring			
EQ2	Increased Ventilation			
EQ3.1		Pref		See paragraph CONSTRUCTION IAQ MANAGEMENT.
EQ3.2		Pref		See paragraph CONSTRUCTION IAQ MANAGEMENT.
EQ4.1	Low Emitting Materials: Adhesives & Sealants Low Emitting Materials: Paints &	Pref		See paragraph LOW- EMITTING MATERIALS. See paragraph LOW-
EQ4.2	Coatings	Pref		EMITTING MATERIALS.
EQ4.3	Low Emitting Materials: Carpet/Flooring Systems	Pref		See paragraph LOW- EMITTING MATERIALS.

EQ4.4	Low Emitting Materials: Composite Wood & Agrifiber Products	Pref		See paragraph LOW- EMITTING MATERIALS.
				System requiring weekly cleaning to earn this credit is not a permitted
EQ5	Indoor Chemical & Pollutant Source Control	Pref		option unless indicated otherwise.
EQ6.1	Controllability of Systems: Lighting			
EQ6.2	Controllability of Systems: Thermal Comfort			
EQ7.1	Thermal Comfort: Design	Rqd		See paragraph HEATING, VENTILATING AND AIR CONDITIONING.
EQ7.2	Thermal Comfort: Verification			Project must earn credit EQ7.1 to be eligible for this credit. Assume Government will not provide post-occupancy activities unless indicated otherwise.
EQ8.1	Daylight & Views: Daylight 75% of Spaces	Pref		See paragraph DAYLIGHTING.
	Daylight & Views: Views for 90% of			
EQ8.2	Spaces	Pref		
INNOVATION & DESIGN PR	ROCESS			
IDc1.1	Innovation in Design			See paragraph INNOVATION AND DESIGN CREDITS. Assume Government will not provide any activities associated with ID credits.
IDc1.2	Innovation in Design			
IDc1.3	Innovation in Design			
IDc1.4	Innovation in Design			
IDc2	LEED Accredited Professional	Rqd	Rqd	LEED AP during design and construction is required.
REGIONAL PRIORITY CREDITS (Version 3 only)				See paragraph LEED CREDITS COORDINATION.

Section: APPENDIX M [Not Supplied]
Page 145 of 151

APPENDIX M LEED Owner's Project Requirements

Section: APPENDIX N [Not Supplied]
Page 146 of 151

APPENDIX N LEED Requirements for Multiple Contractor Combined Projects

Section: APPENDIX O [Not Supplied]
Page 147 of 151

APPENDIX O LEED Strategy Tables

Section: APPENDIX P [Not Supplied]
Page 148 of 151

APPENDIX P

LEED Registration of Army Projects

15 April 2010

Number of Registrations

Each building must be registered separately, except multiple instances of a standard building on a shared site may be registered as a single project. If a single registration for multiple buildings is chosen, all buildings under the single registration must earn exactly the same points. Do not register buildings that are exempt from a specific LEED achievement requirement.

Typical Registration Procedure

- 1. Login, complete the online registration form (see guidance below) at the GBCI LEED Online website http://www.gbci.org/DisplayPage.aspx?CMSPageID=174 and submit it online.
- 2. Pay the registration fee via credit card (USACE staff: credit card PR&C is funded by project design or S&A funds).
- 3. GBCI will follow up with a final invoice, the LEED-online passwords and template information.
- 4. The individual who registers the project online is, by default, the Project Administrator.

Completing the Registration Form

BEFORE YOU BEGIN:

Create a personal account with USGBC if you do not have one.

You will need the following information:

Project name as it appears in P2 (obtain from USACE Project Manager)

Building number/physical address of project

Zip code for Installation/project location

Anticipated construction start and end dates

Total gross area all non-exempt buildings in registration

Total construction cost all non-exempt buildings only (see Project Details Section instructions below)

ACCOUNT/LOGIN INFORMATION

- 1. The person registering the project **must have an account with USGBC** (login and password) to complete the form. Go to http://www.gbci.org/, click on "register a project" at the drop-down menu for project certification (at the top of the page) and select "register now for LEED 2009" to start the project registration process. If you have an account, login with your email address and password and select "register new project" to proceed. If you do not have an account, you may select "register a new account" and follow the instructions. It is recommended that you create an account separately on the USGBC website before you start the form. IMPORTANT: USACE team members are members of USGBC and are eligible for Member prices. USACE team members registering projects should be sure to include the USACE Corporate Access ID in their personal account profile (if you do not have it contact richard.l.schneider@usace.army.mil or judith.f.milton@usace.army.mil for the number).
- 2. The Account/Login Information section is filled out by the person registering the project. It may be a Contractor or a USACE staff member.

ELIGIBILITY SECTION

Follow directions (accepting the terms and conditions)

Review your profile information and make corrections if needed

RATING SYSTEM SELECTION SECTION

Select single project registration and I know which rating system.

Select the rating system - currently only LEED-NC and LEED for Homes are approved for Army use without special approval.

LEED Minimum Program Requirements: select YES

Section: APPENDIX P [Not Supplied]
Page 149 of 151

RATING SYSTEM RESULTS SECTION

Confirm selected rating system.

PROJECT INFORMATION SECTION

Project Title: Begin the project title with a one-word identifier for the Installation. Do not include the word "Fort". After this match the project name used in P2 (contact the USACE Project Manager for this information) and identify the building being registered. Example: "Stewart 4th IBCT - DFAC".

Project Address 1 and 2: This is the physical location of the project. Provide building number, street address, block number or whatever is known to best describe the location of the project on the Installation.

Project City: Installation Name

State, Country, Zip Code: Self-explanatory

Anticipated Construction Start and End Dates: Self-explanatory – give your best guess if unknown. Note that required data entry format is: 1 or 2 digit month/1 or 2 digit date/4 digit year (example 3/23/2010)

Gross Square Footage: Provide total area all buildings in LEED project. Exclude the area of any buildings that are exempt from the LEED achievement requirement (for example, exclude an unconditioned storage shed to be constructed with a barracks complex).

Is Project Confidential: Indicate NO except, if project has security sensitivity (elements that are FOUO or higher security), indicate YES.

Notification of Local Chapter: Indicate NO unless Government/USACE Project Manager requests you to indicate YES.

Anticipated Project Type: Select the most appropriate option from the drop-down menu.

Anticipated Certification Level: Select the applicable option from the drop-down menu (Silver is the usual level).

PROJECT OWNER INFORMATION SECTION

Project Owner First Name, Last Name, email, phone, address: The Project Owner is the USACE Project Manager. Obtain this info from the USACE Project Manager.

Organization: U.S. Army Corps of Engineers. This field MUST be completed this way because it will be used as a search field by higher HQ to find all USACE registered projects. You may supplement it with district name at the end but DO NOT revise or use an acronym.

May we publish Owner information: Indicate NO

Owner Type: Pick Federal Government from drop-down menu.

Project Owner Assertion: Check the box

PAYMENT INFORMATION

Self-explanatory

Section: APPENDIX Q [Not Supplied]
Page 150 of 151

APPENDIX Q REV 1.1 – 31 MAY 2009 AREA COMPUTATIONS

Computation of Areas: Compute the "gross area" and "net area" of facilities (excluding family housing) in accordance with the following subparagraphs:

- (1) Enclosed Spaces: The "gross area" is the sum of all floor spaces with an average clear height $\geq 6'-11$ " (as measured to the underside of the structural system) and having perimeter walls which are $\geq 4'-11$ ". The area is calculated by measuring to the exterior dimensions of surfaces and walls.
- **(2) Half-Scope Spaces:** Areas of the following spaces shall count as one-half scope when calculating "gross area":
 - Balconies
 - Porches
 - Covered exterior loading platforms or facilities
 - Covered but not enclosed passageways and walks
 - Open stairways (both covered and uncovered)
 - Covered ramps
 - Interior corridors (Unaccompanied Enlisted Personnel Housing Only)
- (3) Excluded Spaces: The following spaces shall be excluded from the "gross area" calculation:
 - Crawl spaces
 - Uncovered exterior loading platforms or facilities
 - Exterior insulation applied to existing buildings
 - Open courtyards
 - Open paved terraces
 - Uncovered ramps
 - Uncovered stoops
 - Utility tunnels and raceways
 - Roof overhangs and soffits measuring less than 3'-0" from the exterior face of the building to the fascia
- (4) Net Floor Area: Where required, "net area" is calculated by measuring the inside clear dimensions from the finish surfaces of walls. If required, overall "assignable net area" is determined by subtracting the following spaces from the "gross area":
 - Basements not suited as office, special mechanical, or storage space
 - Elevator shafts and machinery space
 - Exterior walls
 - Interior partitions
 - Mechanical equipment and water supply equipment space
 - Permanent corridors and hallways
 - Stairs and stair towers
 - Janitor closets
 - Electrical equipment space
 - Electronic/communications equipment space

Alon. Al I L		MS SUBMITTAL REGISTER INPUT FORM								CONTR	RACT N	UMBER									ge		
TITLE AND LOCATION																							
Button	<righ< th=""><th>t click for Instructions</th><th></th><th></th><th></th><th>TYPE</th><th>OF</th><th>SUE</th><th>BMI</th><th>TTAL</th><th></th><th></th><th></th><th>CL</th><th>ASS</th><th>SIFICA</th><th>TIO</th><th>N</th><th>RE</th><th>VIEV</th><th>VING</th><th>OFF</th><th>FICE</th></righ<>	t click for Instructions				TYPE	OF	SUE	BMI	TTAL				CL	ASS	SIFICA	TIO	N	RE	VIEV	VING	OFF	FICE
SECTION	PARAGRAPH NUMBER	DESCRIPTION OF ITEM SUBMITTED	01 - PRECON SUBMITTALS	02 - SHOP DRAWINGS	03 - PRODUCT DATA	04 - SAMPLES	05 - DESIGN DATA	06 - TEST REPORTS	07 - CERTIFICATES	08 - MFRS INSTRUCTIONS	09 - MFRS FIELD REPORT	O&M DATA	11 - CLOSEOUI SUBMITTALS	FIO - FOR INFORMATION ONLY	DA DESIGNED OF PECOPD ABBDOVA	CR - CONFORMANCE REVIEW	DA/CR	DA/GA	DO - DISTRICT OFFICE	AO-AREA OFFICE	RO - RESIDENT OFFICE	PO - PROJECT OFFICE DR - DESIGNER OF RECORD	- ARCHITECT / E
00 72 00	52.236-13	Accident Prevention Plan	Х										1			Х				Х			
00 73 00	1.11	Dev. From Accept. Design. No Deviation from Contract					X										Х			Х			X .
00 73 00 00 73 00	1.11 1.17	Dev. From Accepted Design - Deviates from Contract Supplemental Price Breakdown	X				Χ						-	X				Х	┢	X	+	>	-
00 73 00	1.18	SSHO Qualifications	X										Ŧ		<			\vdash	H	Х	_	十	+
01 10 00	5.2.3.1	(if concrete pavement) Joint Layout Plan with design drawings					Χ	Ų								Х		L				┰	ļ
01 10 00 01 10 10	5.5.2 ***	Building Envelope Sealing Performance Testing Tests as Req by Codes - DOR Develops Test Program						X				-		X	-	-		┾	H	X	+	>	+
01 10 00	5.8.3	BAS Review Information		Х				^					Ŧ	^			Х	\vdash	Х	Х	_	Ź	
01 10 00	5.8.3	BAS Performance Verification Test	I					Х				7		X	Ŧ	Ţ		匚	Г	Х	耳	>	Κ
01 10 00 01 10 00	5.8.4 5.8.5	Testing Adjusting and Balancing Commissioning	+					X		\vdash	\dashv	\dashv		X X	+	-	1	\vdash	⊢	X	+))	
01 10 00	6.15	Environmental As Required for Site Specific					Х	^					1	^		Х		+	H	X	+)	
01 10 00	6.16	Permits as required for Site specific					Χ					1	1			X		匚		Х	#	>	Χ
01 10 00 01 32 01.00 10	5.10.2	Fire Protection Tests Preliminary Project Schedule	X	-	-			Х	Χ	H	_	_	-	X	<	-	1	₩	₽	X	+	>	4
01 32 01.00 10		Initial Project Schedule	X										-		<			+-		X	-	+	+
01 32 01.00 10	3.4.3	Design Package Schedule	Х										1)	(Х		土	I
01 32 01.00 10		Periodic schedule updates from the Contractor	X										_		<u> </u>	-		₩	H	Х	_	+	_
01 32 01.00 10 01 33 00	3.7 1.8	Time Extension Request (Schedule) Submittal Register - DOR Input Required	X										-)	(╁	┢	X	+	>	.
01 33 00	1.8	Submittal Register Updates (Design Packages, etc.)	X										1		`					Х	士	Ż	
01 33 00	1.3.1	Substitution of Manuf or Model Named in Proposal		Х	Х										,		Х	L		Х)	
01 33 16 01 33 16	1.2 1.1.2 3.2.4	Identify Designer(s) of Record Fast Track Design Package(s)	X				Х				_		-	- /	(X		₩	Х	X	+	+	+
01 33 16	1.2	Identification of all Designers of Record	Х				^						1			X		+	^	X	+	+	+
01 33 16	3.2.1	Site and Utility Des Package, incl. Substantiation					Χ									Х		I	Χ	Х		I	I
01 33 16	3.2.2/3.5	Interim Des Subm Package(s), incl. Substantiation					Х						-			Х		<u> </u>	Х	Х	_	4	_
01 33 16	3.5.1	Drawings					Х						4			X	-	₩	Х	X	-	+	+
01 33 16 01 33 16	3.5.2.2 3.5.2.3	Sitework Design Analyses					X				_		-		-	X		₩	X	X	+	+	+
01 33 16	3.5.2.4	Structural Design Analyses Security Design Analyses					X						-		-	X		+-	X	X	+	+	+
01 33 16	3.5.2.5	Architectural Design Analyses					Х						1			X		+	Х	Х	+	+	+
01 33 16	3.5.2.6	Mechanical Design Analyses					Х						T			Х		T	Х	Х		T	\top
01 33 16	3.5.2.7	Life Safety Design Analyses					Х						Ť			Х		T	Χ	Х		T	T
01 33 16	3.5.2.8	Plumbing Design Analyses					Χ									Х			Χ	Х		T	
01 33 16	3.5.2.9	Elevator Design Analyses (as Applicable)					Χ									Х			Χ	Х			
01 33 16	3.5.2.10	Electrical Design Analyses					Χ									Х			Х	Х		⊥	
01 33 16	3.5.2.11	Telecommunications Design Analyses					Х						_			Х		▙	Χ	Х		4	4
01 33 16	3.5.2.12	Cathodic Protection Design Analyses					Х						4			X	_	₩	Х	Х	-	+	+
01 33 16	3.5.3	Geotechnical Investigations and Reports					X				_		4		_	X		₩	X	X	\dashv	+	+
01 33 16 01 33 16	3.5.4 3.5.5	LEED Submittals Energy Conservation Documentation					X	H				-	+	-	-	X		┾	X	X	+	+	+
01 33 16	3.5.6	Specifications					Х				-	+	+	+	+	X	-	+	X	X	-	+	+
01 33 16	3.5.7	Building Rendering					X						1			X		+	Х		-	+	+
01 33 16	3.2.4/3.7	Final Des Submittal Package(s), incl. Substantiation					Χ				\Box				Ţ	Х		F	Χ	Х	丰	ユ	I
01 33 16 01 33 16	3.7.5 3.2.5/3.8	DD Form 1354 (Transfer of Real Property) Design Complete Submittal Package(s)	-				Х	\vdash		\vdash		+	Х	-	+	X		\vdash	Х	X	+	+	+
01 33 16	3.2.5/3.8	Design Complete Submittal Package(s) Design and Code Review Checklists	1				X	\vdash		\vdash	-	\dashv	1	\pm	+	X		+	X	X	+	+	+
01 33 16	A-2.0	SID - Interim and Final (as applicable)			Χ	Χ	Χ						1		(Х	\Box	工	工
01 33 16 01 33 16	B-2.0 F-3.1.3	FFE (as Applicable) BIM Model and data	\vdash				X				\dashv		4)	(V	H	⊢	V	X	\dashv	+	+
01 45 04.00 10		Design and Construction QC Plan	Х				٨				1		T		T	X		F	^	X	7	+	+
01 57 20.00.10	1.2	Environmental Protection Plan	Х										1		1	Х				Χ	\Box	工	工
01 78 02.00 10		Final as-Built Drawings/ BIM Model	_	-	-			H	Χ	H	_	_	Х	X X	(-	1	₩	₽	Х	+	+	+
01 78 02.00 10 01 78 02.00 10		Non-Hazardous Solid Waste Diversion Reports Provide final as-built CADD and BIM Model files	1					\vdash	۸	\vdash	-	\dashv	Х		(+		+	T	X	+	+	+
01 78 02.00 10	1.2.9	Provide scans of all other docs in Adobe.pdf format											X)	(匚		Х	コ	工	I
01 78 02.00 10		Equip-in-Place list of all installed equip and cost Data on equip not addressed in O&M manuals	+-	-	-		H	\vdash		Н	+		X X		< <	+	1	₩	H	X	\dashv	+	+
01 78 02.00 10 01 78 02.00 10		Final as-built specs - electronic files	1					\vdash		\vdash	-		X		(+		+	T	X	+	+	+
01 78 02.00 10	1.4.2.1	Warranty management plan - FAR 52.246-21											X)	(匚		Х	コ	工	I
01 78 02.00 10		Certificates of Warranty for extended warranty items	1	_	_			oxdot		\sqcup			X		(\perp	<u> </u>	\vdash	\vdash	X	+	4	+
01 78 02.00 10 01 78 02.00 10		Contractor's POCs for implementing warranty process List of each warranted equip, item, feature or system	+	\vdash	\vdash			H		H	+		X X		(+	<u> </u>	+	H	X	+	+	+
01 78 02.00 10		See also Section 01 10 00 par. 5.8.4 and 5.8.5	T	L	L			Ħ		Ħ			X)	(士	L	T	Ħ	Х	士	士	士
01 78 02.00 10		Equipment O&M Manuals - 1 electronic / 2 hard copies	I					П			I		Х		(匚		Χ	工	I	I
01 78 02.00 10		Field Training DVD Videos	1					\sqcup		Ш	_	Х		X	-	\bot		\vdash	lacksquare	X	\dashv	4	4
01 78 02.00 10 01 78 02.00 10		Pricing of CF/CI and GF/CI Property	1-	-	-			\vdash		\vdash			X X	X	+	X	-	\vdash	\vdash	X	+	+	+
01 78 02.00 10		List of Completed Cleanup Items Interim Form DD 1354									1		^ <u>X</u>		+	^ Y		H	H	^ X	\dashv	+	+
01 10 02.00 10	1.14												Λ			X				Λ			